



POOL CONSTRUCTION GENERAL NOTES

- POOL TO BE CONSTRUCTED IN INDIVIDUAL POURS THAT ARE SEQUENCED WITH ADEQUATE TIME FOR CONCRETE TO CURE AND INITIAL SHRINKAGE TO TAKE PLACE.

ELEMENT	DATE CAST (DAYS)
① POOL BOTTOM	2
② POOL WALL	30
③ POOL BOTTOM	30
④ WALL	32
⑤ WALL	32
⑥ WALL	32
⑦ POOL BOTTOM	60
⑧ POOL WALL	62
⑨ POOL WALL	62
⑩ POOL WALL	62
⑪ BUBBLE COUCH STAIR	62
⑫ UNDERWATER BENCH	62
⑬ STAIR	62
⑭ WALL	90
⑮ WALL	90

- THE "DATE CAST" IS THE MINIMUM PERIOD OF TIME SEPARATING ADJACENT POURS.
- ALL CONCRETE PLACED SHALL FOLLOW HOT & COLD WEATHER RECOMMENDED PRACTICES. IN ADDITION, ANY CONCRETE POURED ON DAYS ANTICIPATED TO HAVE A DAILY HIGH TEMPERATURE OF 90 DEGREES OR WIND SPEEDS EXCEEDING 15 MPH, SHALL BE CAST BETWEEN 10 P.M. AND 3 A.M.
- ALL POOL CONCRETE TO BE CONTINUOUSLY MET CURED FOR 28 DAYS. CONTRACTOR TO PROVIDE ADEQUATE MEANS OF DRAINAGE.
- STRUCTURAL DRAWINGS PRIMARY PURPOSE IS TO INDICATE REINFORCING REQUIRED. COORDINATE WITH POOL AND ARCHITECTURAL DRAWINGS FOR ALL EMBEDDED ITEMS AND CONCRETE PROFILES.
- SEE CIVIL DRAWINGS FOR ALL SITE PAVING, STAIRS, AND RETAINING WALLS NOT SPECIFICALLY DETAILED ON STRUCTURAL LAYOUT.
- SEE ARCHITECTURAL DRAWINGS FOR PAVING AND RETAINING WALL LAYOUT.

DRAWING INDEX

GENERAL NOTES	S1.01
DEMO PLAN	S2.00
TYPICAL FOUNDATION DETAILS	S3.01
PIER SCHEDULE	S3.01
TYPICAL POOL DETAILS	S3.02
TYPICAL CMU DETAILS	S4.01
TYPICAL FLOOR DETAILS	S5.01
TYPICAL ROOF DETAILS	S6.01