C1 = TS8x4x1/4 WITH TS4x2x1/4
C2 = 2-TS8x4x1/4 WITH TS4x2x1/4
C3 = TS8x4x1/4

PLAN NOTES:

1. FINISH FLOOR ELEVATION = 100'-0" (U.N.O.).
2. SEE SHEET 3.1.1 FOR GENERAL NOTES.
3. SEE SHEET 3.4.1 FOR PIER SCHEDULE AND TYPICAL PIER DETAILS.
4. SEE SHEET 3.4.1 FOR TYPICAL FOUNDATION DETAILS.
5. FLOOR SLAB IS 5" SLAB ON GRADE REINFORCED WITH 6x6-2.9x2.9 W.W.F. (2" FROM TOP). SEE SOILS REPORT FOR SUBGRADE PREPARATION.
6. SEE SHEET 3.2.1 FOR GRADE BEAM SCHEDULE.
7. "W2" INDICATES WALL TYPE. SEE SECTION "03"/3.5.1 FOR WALL THICKNESS AND REINF. "W1" SHALL BE TYPICAL WALL TYPE UNLESS NOTED OTHERWISE ON PLAN.
8. * INDICATES PIPE COLUMNS WITH DRAIN SLOT IN "SOUTH" FACE. SEE DETAIL "03"/3.5.8 FOR INFO.

PIER DESIGNATION

PIER DIAMETER (INCHES) — 24 — 4 — PENETRATION (FEET)
97'-0" — TOP OF PIER ELEVATION

BP1 = BASE PL 1.1/2"x20"x1'-8" SEE DETAIL "05"/3.4.1 (TYPE 1)
BP2 = BASE PL 3/4"x12"x1'-0" SEE DETAIL "05"/3.4.1 (TYPE 1)
BP3 = BASE PL 3/4"x10"x0'-10" SEE DETAIL "05"/3.4.1 (TYPE 1)

01 FOUNDATION PLAN
SCALE: 1/8"=1'-0"

ACC · ACT

ADDISON

| OWNER | LANDSCAPE | STRUCTURAL | HISTORIAN | Issue | Category | Subcategory | Sheet |
|---|---|---|---|---|---|---|---|
| **Town of Addison** | The Kellams Group<br>317-776-1417 | Ellisor Tanner<br>214-387-8393 | Alan Mason<br>214-691-7182 | ISSUE FOR BID 8-17-90 | 3 | 2 | 4 |
| ARCHITECT<br>**Cunningham Architects**<br>2700 Fairmount<br>Dallas, Texas 75201<br>214-855-5272 | THEATRE CONSULTANT<br>Theatre Projects<br>203-431-3949 | M.E.P<br>MEP Systems<br>214-754-4741 | LIGHTING<br>Pamela Hull Wilson<br>214-823-6542 | | | | |
| | INTERIORS<br>CRSS<br>713-552-2000 | CIVIL<br>Kurtz & Associates<br>214-690-3322 | GRAPHICS<br>Nottestad Design<br>214-954-1978 | | | | |