



- GLASS SCHEDULE
Key Type
- (A) 1/4" Clear Float Glass in Zipper Gasket System
 - (B) 1/4" Patterned Float Glass in Zipper Gasket System
 - (C) 1/4" Ceramic Coated Spandrel Tempered Glass in Zipper Gasket System
 - (D) 1/4" Clear Tempered Glass in Zipper Gasket System
 - (E) 1/4" Clear Float Glass in Aluminum Storefront System
 - (F) 1/4" Clear Tempered Glass in Aluminum Storefront System
 - (G) 1/4" Patterned Float Glass in Aluminum Storefront System
 - (H) 1/4" Patterned Tempered Glass in Aluminum Storefront System
 - (I) 1-3/4" Insulating Acoustic Unit (1/4" x .030 x 1/4" x 1.5 x 1/8" x 1/8") in Grouted Hollow Metal Frame
 - (K) 1-3/4" Insulating Acoustic Unit (1/4" x .030 x 1/4" x 1.5 x 1/8" x 1/8") in Custom Steel Tube Glazing or Door
 - (L) 1/4" Clear Laminated (1/8" x .030 x 1/8") Glass in Single Hung Aluminum Window
 - (M) 1/4" Tempered Patterned Glass in Single Hung Aluminum Window
 - (N) 1/4" Clear Float Glass in Grouted Hollow Metal Frame

LEVEL THREE FLOOR PLAN
8/21/01