



- GLASS SCHEDULE**
- Key Type
- (A) 1/4" Clear Float Glass in Zipper Gasket System
 - (B) 1/4" Patterned Float Glass in Zipper Gasket System
 - (C) 1/4" Ceramic Coated Spandrel Tempered Glass in Zipper Gasket System
 - (D) 1/4" Clear Tempered Glass in Zipper Gasket System
 - (E) 1/4" Clear Float Glass in Aluminum Storefront System
 - (F) 1/4" Clear Tempered Glass in Aluminum Storefront System
 - (G) 1/4" Patterned Float Glass in Aluminum Storefront System
 - (H) 1/4" Clear Tempered Glass in Aluminum Storefront System
 - (I) 1-3/4" Insulating Acoustic Unit (1/4" x .020 x 1/4" x .188 x 1/8") in Grouted Hollow Metal Frame
 - (J) 1-3/4" Insulating Acoustic Unit (1/4" x .020 x 1/4" x .188 x 1/8") in Custom Steel Tube Glazing or Door
 - (K) 1/4" Clear Laminated (1/8" x .020 x 1/8") Glass in Single Hung Aluminum Window
 - (L) 1/4" Tempered Patterned Glass in Single Hung Aluminum Window
 - (M) 1/4" Clear Float Glass in Grouted Hollow Metal Frame

LEVEL ONE FLOOR PLAN

SK 57 adderizes 48 4" φ cores located by chair & lobby

OWNER	LANDSCAPE	STRUCTURAL	HISTORIAN	ISSUE	Category	Subcategory	Sheet
Town of Addison The Kellams Group 317-776-1417	Cambridge Architects 2700 Fairmount Dallas, Texas 75201 214-855-5272	THEATRE CONSULTANT MEP Systems 214-754-4789	M.E.P. MEP Systems 214-754-4789	ISSUE FOR BID 8-17-80	4	2	14
	INTERIORS CRSS 713-552-2000	DNL Kurtz & Associates 214-880-3322	GRAPHICS Northwest Design 214-864-8176				