GENERAL NOTES:

1. WRITTEN DIMENSIONS PREVAIL OVER SCALED DIMENSIONS. NOTIFY LANDSCAPE ARCHITECT OF ANY DISCREPANCIES.
2. THE CONTRACTOR BARES ALL RESPONSIBILITY FOR VERIFYING ALL UNDERGROUND UTILITIES, PIPES, STRUCTURES, AND LINE RUNS IN THE FIELD PRIOR TO CONSTRUCTION. ANY DAMAGE TO UTILITIES THAT ARE TO REMAIN SHALL BE REPAIRED IMMEDIATELY AT NO EXPENSE TO THE OWNER. LANDSCAPE ARCHITECT ASSUMES NO RESPONSIBILITY FOR ANY NOT SHOWN ON PLANS.
3. ALL PROPOSED AND FINISHED GRADES ARE BASED ON INFORMATION PROVIDED BY THE OWNER'S SURVEY AND/OR CIVIL ENGINEER. ANY DISCREPANCIES IN ACTUAL FIELD MEASUREMENTS ARE TO BE REPORTED TO THE LANDSCAPE ARCHITECT IMMEDIATELY.
4. PRIOR TO COMMENCEMENT OF HARDSCAPE CONSTRUCTION, ALL PIERS, FOOTINGS, AND WALLS ARE TO BE SURVEYED, LAID OUT, AND STAKED IN FIELD FOR REVIEW BY LANDSCAPE ARCHITECT. CONTRACTOR SHALL ASSUME RESPONSIBILITY FOR ANY DEMOLITION, ADJUSTMENTS, OR RECONSTRUCTION RESULTING FROM UNAUTHORIZED CONSTRUCTION ACTIVITIES.
5. CONTRACTOR IS RESPONSIBLE FOR ALL QUANTITIES PER DRAWINGS AND SPECIFICATIONS. ANY QUANTITIES PROVIDED BY LANDSCAPE ARCHITECT ARE PROVIDED FOR CONVENIENCE ONLY CONTRACTORS ARE TO BID THEIR OWN VERIFIED QUANTITIES. NOTIFY LANDSCAPE ARCHITECT AT ANY DISCREPANCIES.
6. EASEMENTS SETBACKS, BUILDING, CURB AND GUTTER, UNDERGROUND UTILITIES HAVE BEEN SUPPLIED TO LANDSCAPE ARCHITECT BY THE PROJECT CIVIL ENGINEER. REFER TO CIVIL ENGINEERS DRAWINGS FOR ADDITIONAL INFORMATION.
7. POOLS AND FOUNTAINS TO BE DESIGN/ BUILD BY POOL CONTRACTOR. CONTRACTOR TO PROVIDE SEALED ENGINEERED SHOP DRAWINGS FOR STRUCTURAL AND MEP FOR REVIEW BY LANDSCAPE ARCHITECT PRIOR TO ANY CONSTRUCTION.

CONCRETE NOTES:

1. CAST-IN PLACE CONCRETE SHALL MEET THE FOLLOWING REQUIREMENT.
   - MINIMUM 3,000 PSI COMPRESSIVE STRENGTH AT 28 DAYS.
   - AGGREGATES: ASTM C33, MAXIMUM $\frac{3}{4}$" IN SIZE.
   - SLUMP: 3 TO 5 INCHES
   - AIR CONTENT: 4 TO 6 PERCENT BY VOLUME
2. CONCRETE THICKNESS:
   - PEDESTRIAN AREAS = 4" THICK
   - VEHICULAR AREAS = REFER TO CIVIL DRAWINGS
3. CONCRETE REINFORCING:
   - 4" THICK = #3's @ 18" O.C., BOTH WAYS
   - 6" THICK = REFER TO CIVIL DRAWINGS
4. SAW CUT JOINTS TO BE PLACED AS INDICATED ON PLANS TO A MINIMUM $\frac{1}{4}$" DEPTH.
5. EXPANSION JOINTS:
   - PLACE AT MAXIMUM OF 30' O.C. AND COORDINATE WITH OVERALL PAVING PATTERN AND SAW JOINTS
   - PROVIDE 24" #4 SMOOTH DOWELS AT MAXIMUM 24" ON CENTER. COAT ONE END OF DOWEL TO PREVENT BAND.

SHOP DRAWINGS:

CONTRACTOR SHALL PREPARE/PROVIDE SHOP DRAWINGS FOR REVIEW BY LANDSCAPE ARCHITECT FOR THE FOLLOWING ITEMS:

1. CONCRETE ACCENT WALL

MOCK-UP:

CONTRACTOR SHALL PREPARE/PROVIDE MOCK-UP'S FOR REVIEW BY LANDSCAPE ARCHITECT FOR THE FOLLOWING ITEMS:

1. CONCRETE ACCENT WALL

IRRIGATION:

1. RETROFIT EXISTING IRRIGATION SYSTEM TO ACCOMMODATE NEW PLANTING AT RESTROOM BUILDING.

MATERIAL LEGEND:

CONCRETE

C-1 PAVING

COLOR: STANDARD GRAY
FINISH: LIGHT SANDBLAST
PATTERN: REFER TO PLANS
JOINTS: SAW-CUT CONTROL JOINTS ⅛" DEPTH OF SIDEWALK

C-4 FEATURE WALLS

COLOR: STANDARD GRAY
FINISH: SMOOTH FORM ARCHITECTURAL FINISH (PLACE TIE HOLES AS SHOWN)
FORM WORK JOINTS: AS SHOWN ON ELEVATIONS (≈4'x 8')
HEIGHT: VARIES, REF. PLANS
NOTE: ARCHITECTURAL CONCRETE TO HAVE 90° ANGLES
W/ EASED CORNERS (NO TROWEL OR CHAMFERED CORNERS)
INSTALLATION: REFERENCE DETAIL

STONE

S-5 STONE PAVING

COLOR: PENNSYLVANIA BLUESTONE
SIZE: 12" x 36" x 1½" THICK
SETTING: 1½" MORTAR SETTING BED W/ SAND SWEPT ¾" JOINTS
FINISH: THERMAL FINISH: CUT ON ALL SIDES
INSTALLATION: REF. DETAILS
SUPPLIER: CUSTOM STONE (972.243.1144)

PAVERS

P-1 PAVERS

SIZE: 4x8
THICKNESS: 8cm
COLOR: BELLOWS BROWN
MANUFACTURER: PAVESTONE
PATTERN: SOLDIER COURSE (REFER TO PLANS)

P-5 PAVERS (ADA COMPLIANT)

SIZE: 4x8
THICKNESS: 8cm
COLOR: CAST STONE
FINISH: ADA COMPLIANT
MANUFACTURER: PAVESTONE

METALS

M-1 STEEL EDGING

COLOR: GALVANIZED
SIZE: 1/4" x 4"
INSTALLATION: PER MANUFACTURER

M-2 AREA DRAIN

MANUFACTURER: NDS
MODEL: DURACAST SQUARE HINGED GRATE (P/N D12) WITH NDS
DURACAST PVC CATCH BASIN CONNECTED TO A SEWER & DRAIN PIPE

SYMBOLS LEGEND:

GENERAL

- CENTER LINE
- LIMIT OF WORK
- MATCHLINE
- EJ — EXPANSION JOINT
- CONTROL JOINT
- STEEL EDGING

ABBREVIATIONS

TW = TOP OF WALL
BW = BOTTOM OF WALL
TF = TOP OF FOOTING
FL = FLOWLINE/INVERT
EJ = EXPANSION JOINT
CJ = CONTROL JOINT
CL = CENTER LINE
POB = POINT OF BEGINNING
TOC = TOP OF COLUMN
DD = DECK DRAIN
SD = SLOT DRAIN
CP = TOP OF COPING
BP = BOTTOM OF POOL

POINT OF BEGINING

ENLARGEMENT REFERENCE (X / L3.00)

DETAIL REFERENCE (X / X.XX)

DETAIL REFERENCE (X | X.XX)

ELEVATION REFERENCE (X / X.XX)

SECTION REFERENCE (X / X.XX)

MATERIAL REFERENCE (C-1)

590.35 SPOT GRADE

HARDSCAPE, LANDSCAPE

	Issued: ISSUE FOR PERMIT AND PRICING
L0 - MATERIALS LEGEND & NOTES	●
L1 - HARDSCAP & PLANTING PLANS	●
L2 - DETAILS	●

TRUE NORTH

PLAN NORTH

Good Fulton & Farrell Architects
2808 Fairmount Street
Suite 300
Dallas, Texas 75201
214.303.1500/Tel
214.303.1512/Fax
www.gff.com

© Good Fulton & Farrell 2009

studioOutside
824 Exposition Avenue, Suite 5
Dallas, Texas 75226
o214.954.7160
f214.954.7162

UDR℠

VITRUVIAN PARK:
PARK TOILET BUILDING

VITRUVIAN WAY
ADDISON, TX 75001

No.	Date	Item

REVISIONS

BG Drawn
BG / PF Checked
SI Approved

REGISTERED LANDSCAPE ARCHITECT — STATE OF TEXAS — 1983 — 06/28/2012

Materials Legend & Notes

GFF Project No.	10061.00
SO Project No.	12035
Date	06.28.12
Last Revision	

L0