
Kimley-Horn and Associates, Inc. Project Description for Unsignalized Intersection Priority: 5

Client: Town of Addison Date: 1/2/18 Program: ADA Self-Evaluation and Transition Plan Prepared By: CMP KHA No.: 063543021 Checked By: EPE

Corridor : Project Name: Town: GPS ID: 120 Quorum Dr Intersection of Quorum Dr and McEntire PI Addison

Item No.	Item Description	Quantity	Unit	Unit	Price	Item Cost
TxDOT 110-6001	EXCAVATION (ROADWAY)	0	CY	\$	10.00	\$ -
TxDOT 529-6002	CONC CURB (TY II)	0	LF	\$	15.00	\$ -
TxDOT 531-6001	CONC SIDEWALKS (4")	3	SY	\$	45.00	\$ 135.00
	CURB RAMPS	2	EA	\$	1,500.00	\$ 3,000.00
TxDOT 5003-6002	RETROFIT DET WARN SURF (CAST IN PLACE)	20	SF	\$	50.00	\$ 1,000.00
TxDOT 104-6015	REMOVING CONC (SIDEWALKS)	23	SY	\$	9.00	\$ 207.00
TxDOT 677	ELIM EXT PAVE MRK & MRKS	0	LF	\$	2.80	\$ -
TxDOT 666/678	REFL PAV MRK PREP, TY I & TY II (W) 24"(SLD)	120	LF	\$	8.50	\$ 1,020.00
	REPAVE ROADWAY	1	LS	\$	5,000.00	\$ 5,000.00
	FIX PONDING	0	LS	\$	2,000.00	\$ -
	FIX CURB RAMP TRANSITION	3	LS	\$	2,000.00	\$ 6,000.00
	MEDIAN NOSE MODIFICATION	0	LS	\$	5,000.00	\$ -
	REMOVE TEMPORARY OBSTRUCTION	0	LS	\$	500.00	\$ -
	FIX CURB RAMP COUNTER SLOPE	0	LS	\$	2,000.00	\$ -
Basis for Cost Proje			Subtotal:	\$ 16,362.00		
	✓ No Design Completed			gineering: (% +/-)		
	☐ Preliminary Design		Co	ontingency: (% +/-)		* -/
	☐ Final Design			Estimated P	roject Cost:	\$ 23,000.00

## Project Location







## Field Observations

Intersection Issues		Cros	swalk		Descible California	
		E	S	W	Possible Solutions	
Path of travel pavement condition	N/A	Good	N/A	Good		
Path of travel running slope is greater than 5%	N/A		N/A			
Path of travel cross slope is greater than 2% for stop control approaches	N/A	Х	N/A		Repave roadway and install crosswalk pavement markings	
Path of travel cross slope is greater than 5% for free-flow approaches	N/A	N/A	N/A	N/A		
Crosswalk width is less than 6'	N/A	N/A	N/A	N/A	Install crosswalk pavement markings	
Crosswalk striping condition	N/A	None	N/A	None		

Curb Ramp ID ('z' or 'i' in ramp label indicates no								
Curb Ramp Issues				existing	g ramp)	Possible Solutions		
	1A	2A	3A	4A				
Curb ramp does not exist and is needed			<u> </u>					
Curb ramp does not land in crosswalk	İ		İ	<u>.                                    </u>				
No 4' x 4' clear space at base of curb ramp	<u> </u>		<u> </u>	<u> </u>				
Curbed side is not 90° or has traversable adjacent surface								
Flare cross slope is greater than 10%				Х				
Curb ramp running slope is greater than 8.3%				Х				
Blended transition running slope is greater than 5%								
Cut-thru ramp running slope is greater than 5%						Remove and replace curb ramp		
Curb ramp cross slope is greater than 2%	<u> </u>		X	<u> </u>		Tromovo ana ropiaco outo tamp		
Cut-thru ramp cross slope is greater than 2%	<u> </u>		<u> </u>	<u> </u>				
Curb ramp width is less than 48"								
Cut-thru ramp width is less than 60"	<u> </u>		<u> </u>	<u> </u>				
Permanent obstruction (>0.25") in curb ramp/landing/flares				Χ				
Temporary obstruction (>0.25") in curb ramp/landing/flares	<u> </u>		<u> </u>	<u> </u>				
No textured surface at base of curb ramp	X	X	Х	Х		For intersection, commercial driveway, and park ramps, install		
No color contrast at base of curb ramp	<u> </u>		<u> </u>	İ				
Landing area does not exist and is needed	ļ		<u> </u>	ļ				
Landing area is less than 5' x 5' or slopes greater than 2%	X		X	X		Remove and replace landing area		
Curb ramp transition onto roadway is greater than 0.25"	ļ	Χ	X	Х		Fix curb ramp transition		
Counter slope of the gutter or street at the foot of the curb ramp is			İ					
greater than 5%	<u> </u>		<u> </u>	<u> </u>				
Ponding occurs at base of curb ramp			i					

Kimley-Horn and Associates, Inc. Intersection of Quorum Dr and McEntire PI

Photographs GPS ID: 120



Ramp 1A



Ramp 3A



Ramp 2A



Ramp 4A

## Opinion of Probable Construction Cost Disclaimer:

The Engineer has no control over the cost of labor, materials, equipment, or over the Contractor's methods of determining prices or over competitive bidding or market conditions. Opinions of probable costs provided herein are based on the information known to Engineer at this time and represent only the Engineer's judgment as a design professional familiar with the construction industry. The Engineer cannot and does not guarantee that proposals, bids, or actual construction costs will not vary from its opinions of probable costs.

## Project Location Map Sources:

Esri, DeLorme, NAVTEQ, USGS, Intermap, iPC, NRCAN, Esri Japan, METI, Esri China (Hong Kong), Esri (Thailand), TomTom, 2013, DigitalGlobe, GeoEye, i-cubed, USDA, AEX, Getmapping, Aerogrip, IGN, IGP, swisstopo, and the GIS User Community