
Kimley-Horn and Associates, Inc. Project Description for Unsignalized Intersection Priority: 2

Client: Town of Addison Date: 1/2/18 Program: ADA Self-Evaluation and Transition Plan Prepared By: CMP KHA No.: 063543021 Checked By: EPE

Keller Springs Rd Intersection of Keller Springs Rd and driveway (Lat. 32.9686; Long. -96.8253) Corridor : Project Name: GPS ID: 106 Town: Addison

Item No.	Item Description	Quantity	Unit	U	Init Price	Item Cost
TxDOT 110-6001	EXCAVATION (ROADWAY)	0	CY	\$	10.00	\$ -
TxDOT 529-6002	CONC CURB (TY II)	0	LF	\$	15.00	\$ -
TxDOT 531-6001	CONC SIDEWALKS (4")	0	SY	\$	45.00	\$ -
	CURB RAMPS	2	EA	\$	1,500.00	\$ 3,000.00
	RETROFIT DET WARN SURF (CAST IN PLACE)	0	SF	\$	50.00	\$ -
TxDOT 104-6015	REMOVING CONC (SIDEWALKS)	21	SY	\$	9.00	\$ 189.00
TxDOT 677	ELIM EXT PAVE MRK & MRKS	0	LF	\$	2.80	\$ -
TxDOT 666/678	REFL PAV MRK PREP, TY I & TY II (W) 24"(SLD)	0	LF	\$	8.50	\$ -
	REPAVE ROADWAY	0	LS	\$	5,000.00	\$ -
	FIX PONDING	0	LS	\$	2,000.00	\$ -
	FIX CURB RAMP TRANSITION	1	LS	\$	2,000.00	\$ 2,000.00
	MEDIAN NOSE MODIFICATION	0	LS	\$	5,000.00	\$ -
	REMOVE TEMPORARY OBSTRUCTION	0	LS	\$	500.00	
	FIX CURB RAMP COUNTER SLOPE	0	LS	\$	2,000.00	•
Basis for Cost Proje			Subtotal:	\$ 5,189.00		
	☑ No Design Completed			Engineering: (% +		\$ 1,405.50
	□ Preliminary Design			Contingency: (% +		,
	☐ Final Design			Estimated	d Project Cost:	\$ 8,000.00

Project Location







Field Observations

Intersection Issues		Cros	swalk		Possible Solutions		
		E	S	W	Fossible Solutions		
Path of travel pavement condition							
Path of travel running slope is greater than 5%							
Path of travel cross slope is greater than 2% for stop control							
approaches	All driveway path of travel issues and possible solutions provide				solutions provided in driveway shapefile (TRPEDDRV)		
	, u.	pai		o ana poconono	columnic provided in dividual chapeline (1111 252111)		
Path of travel cross slope is greater than 5% for free-flow approaches							
Crosswalk width is less than 6'							
Crosswalk striping condition							

		_			
		Ramp	DID ('z' or 'i' in ramp label indicates no		
Curb Ramp Issues			existing ramp)	Possible Solutions	
	3A	4A			
Curb ramp does not exist and is needed	<u> </u>				
Curb ramp does not land in crosswalk	<u> </u>				
No 4' x 4' clear space at base of curb ramp	<u> </u>				
Curbed side is not 90° or has traversable adjacent surface					
Flare cross slope is greater than 10%					
Curb ramp running slope is greater than 8.3%	l				
Blended transition running slope is greater than 5%					
Cut-thru ramp running slope is greater than 5% Curb ramp cross slope is greater than 2%				Remove and replace curb ramp	
		Х		Tremove and replace curb famp	
Cut-thru ramp cross slope is greater than 2%					
Curb ramp width is less than 48"		Х			
Cut-thru ramp width is less than 60"	l				
Permanent obstruction (>0.25") in curb ramp/landing/flares	<u> </u>				
Temporary obstruction (>0.25") in curb ramp/landing/flares	<u> </u>				
No textured surface at base of curb ramp	X	Х		For intersection, commercial driveway, and park ramps, install	
No color contrast at base of curb ramp	<u> </u>	 			
Landing area does not exist and is needed	<u>.ļ</u>				
Landing area is less than 5' x 5' or slopes greater than 2%	X	Х		Remove and replace landing area	
Curb ramp transition onto roadway is greater than 0.25"	<u> </u>	Χ		Fix curb ramp transition	
Counter slope of the gutter or street at the foot of the curb ramp is					
greater than 5%	<u> </u>				
Ponding occurs at base of curb ramp	l				







Ramp 4A

Opinion of Probable Construction Cost Disclaimer:

The Engineer has no control over the cost of labor, materials, equipment, or over the Contractor's methods of determining prices or over competitive bidding or market conditions. Opinions of probable costs provided herein are based on the information known to Engineer at this time and represent only the Engineer's judgment as a design professional familiar with the construction industry. The Engineer cannot and does not guarantee that proposals, bids, or actual construction costs will not vary from its opinions of probable costs.

Project Location Map Sources:

Esri, DeLorme, NAVTEQ, USGS, Intermap, iPC, NRCAN, Esri Japan, METI, Esri China (Hong Kong), Esri (Thailand), TomTom, 2013, DigitalGlobe, GeoEye, i-cubed, USDA, AEX, Getmapping, Aerogrip, IGN, IGP, swisstopo, and the GIS User Community