Kimley-Horn and Associates, Inc. Project Description for Unsignalized Intersection Priority: 2

Client: Town of Addison Date: 1/2/18 Program: ADA Self-Evaluation and Transition Plan Prepared By: CMP KHA No.: 063543021 Checked By: EPE

Corridor : Project Name: GPS ID: 211 Quorum Dr Intersection of Quorum Dr and driveway (Lat. 32.9500; Long. -96.8254) Town: Addison


Item No.	Item Description	Quantity	Unit	Unit Price	Item Cost
TxDOT 110-6001	EXCAVATION (ROADWAY)	0	CY	\$ 10.00 \$	-
TxDOT 529-6002	CONC CURB (TY II)	0	LF	\$ 15.00 \$	-
TxDOT 531-6001	CONC SIDEWALKS (4")	0	SY	\$ 45.00 \$	-
TxDOT 531	CURB RAMPS	6	EA	\$ 1,500.00 \$	9,000.00
TxDOT 5003-6002	RETROFIT DET WARN SURF (CAST IN PLACE)	0	SF	\$ 50.00 \$	-
TxDOT 104-6015	REMOVING CONC (SIDEWALKS)	40	SY	\$ 9.00 \$	360.00
TxDOT 677	ELIM EXT PAVE MRK & MRKS	0	LF	\$ 2.80 \$	-
TxDOT 666/678	REFL PAV MRK PREP, TY I & TY II (W) 24"(SLD)	0	LF	\$ 8.50 \$	-
	REPAVE ROADWAY	0	LS	\$ 5,000.00 \$	-
	FIX PONDING	0	LS	\$ 2,000.00 \$	-
	FIX CURB RAMP TRANSITION	4	LS	\$ 2,000.00 \$	8,000.00
	MEDIAN NOSE MODIFICATION	0	LS	\$ 5,000.00 \$	-
	REMOVE TEMPORARY OBSTRUCTION	0	LS	\$ 500.00 \$	-
	FIX CURB RAMP COUNTER SLOPE	1	LS	\$ 2,000.00 \$	2,000.00
Basis for Cost Proje		Subtotal: \$	19.360.00		

✓ No Design Completed✓ Preliminary Design


☐ Final Design

20% \$ 20% \$ Engineering: (% +/-)
Contingency: (% +/-) 4,320.00 4,320.00 Estimated Project Cost: 28,000.00

## Project Location







## Field Observations

Intersection Issues		Cros	swalk		Possible Solutions
intersection issues	N	E	S	W	Fossible Solutions
Path of travel pavement condition Path of travel running slope is greater than 5% Path of travel cross slope is greater than 2% for stop control approaches	All dr	iveway path c	of travel issue	es and possible	solutions provided in driveway shapefile (TRPEDDRV)
Path of travel cross slope is greater than 5% for free-flow approaches. Crosswalk width is less than 6' Crosswalk striping condition					

	Curl	Ramp	) ID ('z'	or ' <i>i</i> ' ii	n ramp	np label indicates no
Curb Ramp Issues				existin	g ramp	pp) Possible Solutions
	Ez	1A	2A	3A	4A	
Curb ramp does not exist and is needed	X			<u> </u>		Install 2 Type A ramps
Curb ramp does not land in crosswalk						
No 4' x 4' clear space at base of curb ramp						
Curbed side is not 90° or has traversable adjacent surface						
Flare cross slope is greater than 10%				Ī		
Curb ramp running slope is greater than 8.3%	<u> </u>		Х	Х		
Blended transition running slope is greater than 5%				[		
Cut-thru ramp running slope is greater than 5%	<u> </u>	i		[		Remove and replace curb ramp
Curb ramp cross slope is greater than 2%		Х	Χ	Х	Х	Remove and replace curb famp
Cut-thru ramp cross slope is greater than 2%						
Curb ramp width is less than 48"	i	Х	Χ	Х	Х	
Cut-thru ramp width is less than 60"						
Permanent obstruction (>0.25") in curb ramp/landing/flares					Х	
Temporary obstruction (>0.25") in curb ramp/landing/flares		<u> </u>		<u> </u>		
No textured surface at base of curb ramp		X	Х	X	Х	For intersection, commercial driveway, and park ramps, install
No color contrast at base of curb ramp		X	Х	Х	Χ	color truncated domes
Landing area does not exist and is needed		<b> </b>		<u> </u>		
Landing area is less than 5' x 5' or slopes greater than 2%		X	Х	X	Х	Remove and replace landing area
Curb ramp transition onto roadway is greater than 0.25"		X	Χ	X	Х	Fix curb ramp transition
Counter slope of the gutter or street at the foot of the curb ramp is		Х				Fix curb ramp counter slope
greater than 5%		^		<u> </u>	<u> </u>	The data family addition stope
Ponding occurs at base of curb ramp	Ti Ti	i		i		

Photographs



East Median No Ramp (Ez)



Ramp 2A



Ramp 4A



Ramp 1A



Ramp 3A

## Opinion of Probable Construction Cost Disclaimer:

The Engineer has no control over the cost of labor, materials, equipment, or over the Contractor's methods of determining prices or over competitive bidding or market conditions. Opinions of probable costs provided herein are based on the information known to Engineer at this time and represent only the Engineer's judgment as a design professional familiar with the construction industry. The Engineer cannot and does not guarantee that proposals, bids, or actual construction costs will not vary from its opinions of probable costs.

## Project Location Map Sources:

Esri, DeLorme, NAVTEQ, USGS, Intermap, iPC, NRCAN, Esri Japan, METI, Esri China (Hong Kong), Esri (Thailand), TomTom, 2013, DigitalGlobe, GeoEye, i-cubed, USDA, AEX, Getmapping, Aerogrip, IGN, IGP, swisstopo, and the GIS User Community