
Kimley-Horn and Associates, Inc. Priority: 2 Project Description for Unsignalized Intersection

Client: Town of Addison Date: 1/2/18 Program: ADA Self-Evaluation and Transition Plan Prepared By: CMP KHA No.: 063543021 Checked By: EPE

Corridor : Project Name: Town: GPS ID: 224 Montford Dr Intersection of Montfort Dr and driveway (Lat. 32.9502; Long. -96.8179) Addison

Item No.	Item Description	Quantity	Unit	Unit Pri	ice	Item Cost
TxDOT 110-6001	EXCAVATION (ROADWAY)	0	CY	\$	10.00 \$	-
TxDOT 529-6002	CONC CURB (TY II)	0	LF	\$	15.00 \$	-
TxDOT 531-6001	CONC SIDEWALKS (4")	0	SY	\$	45.00 \$	-
TxDOT 531	CURB RAMPS	2	EA	\$	1,500.00 \$	3,000.00
TxDOT 5003-6002	RETROFIT DET WARN SURF (CAST IN PLACE)	0	SF	\$	50.00 \$	-
TxDOT 104-6015	REMOVING CONC (SIDEWALKS)	8	SY	\$	9.00 \$	72.00
	ELIM EXT PAVE MRK & MRKS	0	LF	\$	2.80 \$	-
TxDOT 666/678	REFL PAV MRK PREP, TY I & TY II (W) 24"(SLD)	0	LF	\$	8.50 \$	-
	REPAVE ROADWAY	0	LS	\$	5,000.00 \$	-
	FIX PONDING	0	LS	\$	2,000.00 \$	-
	FIX CURB RAMP TRANSITION	0	LS	\$	2,000.00 \$	-
	MEDIAN NOSE MODIFICATION	0	LS	\$	5,000.00 \$	-
	REMOVE TEMPORARY OBSTRUCTION	0	LS	\$	500.00 \$	-
	FIX CURB RAMP COUNTER SLOPE	0	LS	\$	2,000.00 \$	-
Basis for Cost Proje					Subtotal: \$	3,072.00
	✓ No Design Completed			Engineering: (% +/-)	20% \$	964.00
	☐ Preliminary Design			Contingency: (% +/-)	20% \$	964.00
	☐ Final Design			Estimated Proj	ect Cost: \$	5,000.00

Project Location







Field Observations

Intersection Issues		Cross	swalk		Possible Solutions	
intersection issues	N	E	S	W	Possible Solutions	
Path of travel pavement condition						
Path of travel running slope is greater than 5%		All driveway path of travel issues and possible solutions provided in driveway shapefile (TRPEDDRV)				
Path of travel cross slope is greater than 2% for stop control						
approaches						
	7 (11 (311	voway patiro	1 11 11 10 10 10 10	o ana possible	ooldiiono provided in driveway orapellie (1711 EBB117)	
Path of travel cross slope is greater than 5% for free-flow approaches						
Crosswalk width is less than 6'						
Crosswalk striping condition						

	Curb Ramp ID ('z' or 'i' in ramp label indicates no						
Curb Ramp Issues			existing ramp)	Possible Solutions			
·	2z	ЗА	0 17				
Curb ramp does not exist and is needed	X			Install curb ramp; if median improvement, see shapefile			
Curb ramp does not land in crosswalk							
No 4' x 4' clear space at base of curb ramp							
Curbed side is not 90° or has traversable adjacent surface							
Flare cross slope is greater than 10%		Х					
Curb ramp running slope is greater than 8.3%	T						
Blended transition running slope is greater than 5%							
Cut-thru ramp running slope is greater than 5%	- i			Remove and replace curb ramp			
Curb ramp cross slope is greater than 2%	T	Х		Tremove and replace curb famp			
Cut-thru ramp cross slope is greater than 2%	T						
Curb ramp width is less than 48"	- i						
Cut-thru ramp width is less than 60"	T						
Permanent obstruction (>0.25") in curb ramp/landing/flares							
Temporary obstruction (>0.25") in curb ramp/landing/flares	<u>. i</u>	<u></u>					
No textured surface at base of curb ramp	<u> </u>	Х		For intersection, commercial driveway, and park ramps, instal			
No color contrast at base of curb ramp	i	Х		color truncated domes			
Landing area does not exist and is needed							
Landing area is less than 5' x 5' or slopes greater than 2%		ļ <u>.</u>					
Curb ramp transition onto roadway is greater than 0.25"		ļl					
Counter slope of the gutter or street at the foot of the curb ramp is							
greater than 5%							
Ponding occurs at base of curb ramp							

Photographs







Ramp 3A

Opinion of Probable Construction Cost Disclaimer:

The Engineer has no control over the cost of labor, materials, equipment, or over the Contractor's methods of determining prices or over competitive bidding or market conditions. Opinions of probable costs provided herein are based on the information known to Engineer at this time and represent only the Engineer's judgment as a design professional familiar with the construction industry. The Engineer cannot and does not guarantee that proposals, bids, or actual construction costs will not vary from its opinions of probable costs.

Project Location Map Sources:

Esri, DeLorme, NAVTEQ, USGS, Intermap, iPC, NRCAN, Esri Japan, METI, Esri China (Hong Kong), Esri (Thailand), TomTom, 2013, DigitalGlobe, GeoEye, i-cubed, USDA, AEX, Getmapping, Aerogrip, IGN, IGP, swisstopo, and the GIS User Community