



RELOCATE EXISTING CONTROL VALVE MARKED "V" TO NEW MAINLINE PIPE ENDED OUT AND CONNECTED TO THE EXISTING MAINLINE PIPE FROM THE SOUTH SIDE OF THE BLDG. AS NECESSARY TO MAINTAIN IN FULL OPERATION.

REPAIR IRRIGATION SYSTEM IN FRONT OF BLDG. AND ON THE NORTH SIDE AS NEEDED TO MAINTAIN EXISTING SPRINKLERS IN FULL OPERATION.

REMOVE EXISTING SPRINKLERS IN NEW BLDG. AREA AND GIVE TO OWNER FOR FUTURE USE.

INSTALL 2" TYPE "K" SOFT COPPER PIPE INSIDE A 4" PVC 50# 40 SLEEVE. THE COPPER PIPE SHALL BE PRESSURE TESTED BEFORE ACCEPTANCE BY THE OWNER OR THE OWNER'S REPRESENTATIVE.

INSTALL NEW 2" TYPE "K" SOFT COPPER PIPE TO THE EXISTING VALVES AND INSTALL NEW WHITE WIRES FROM THE NEW WALKER TO OPERATE THESE VALVES.

REMOVE EXISTING SPRINKLERS IN NEW PARKING AREA AND RELOCATE MAINLINE PIPE ACROSS PARKING AS NECESSARY TO ACCOMPLISH THIS.