ITEM NO.	DESCRIPTION	UNIT	SHEET SUMMARY																						ITEM NO.	PROJ. TOTAL
			SHT 17	SHT 18	SHT 19	SHT 20	SHT 22	SHT 23	SHT 24	SHT 25	SHT 26	SHT 27	SHT 30	SHT 43	SHT 44	SHT 45	SHT 46	SHT 47	SHT 48	SHT 50	SHT 72	MISC				
	SCHEDULE I - PAVING IMPROVEMENTS																									
101	MOBILIZATION	LS																				1			101	1
102	UNCLASSIFIED STREET EXCAVATION	CY																				2143			102	2143
103	REM. & DISPOSE OF EXIST. CONC. PAVEMENT	SY		5604																					103	5604
104	REM. & DISPOSE OF EXIST. CONC. SIDEWALK	SY		1292																					104	1292
105	6" THICK LIME STAB. SUBGRADE	SY			1672	3428	2427	1896	896	1840	1331	757													105	14247
106	HYDRATED LIME (36 LBS/SY)	TON			30.2	61.8	43.8	34.2	16.1	33.2	24.1	13.6													106	257
107	8" 650 PSI FLEX REINF. CONC. PAVEMENT	SY			1441	2113	1887					179													107	5620
108	8" 650 PSI FLEX R.C. DROP SLAB (STREET)	SY										103		39	1120	423									108	1685
109	4" 3000 PSI COMP. REINF. CONC. SIDEWALK	SF			714	679	1078	84		30	888	527													109	4000
110	4" 3000 PSI COMP. R.C. SUBBASE (SIDEWALK)	SF			13533	14516	7725	10068	1080	9096	3648	2199													110	61865
111	6" 3000 PSI COMP. R.C. SUBBASE (SIDEWALK)	SF			538			572	120	185	100														111	1515
112	ITEM DELETED	NA																							112	NA
113	6" 650 PSI FLEX REINF. CONC. DRIVE	SY			89			34			35	60													113	218
114	6" 650 PSI FLEX REINF. CONC INTEGRAL CURB	LF			826	1751	1279	758	173	796															114	5583
115	REINF. CONC. STREET HEADER	LF			68	23	209																		115	300
116	FULL DEPTH SAWCUT EXIST. CONCRETE	LF			427	23	819																		116	1269
117	VEHICULAR BRICK PAVER MATERIALS	SF												1471	10079	3806	1960	798	4906						117	23020
118	STEEL BOLLARD	EA												7			2		62						118	71
119	4" THERMOPLASTIC LANE STRIPE	LF	54																						119	54
120	4" NON-REFL. BUTTON, TYPE I-W	EA	112																						120	112
121	4" REFL. BUTTON, TYPE I-W-C	EA	195																						121	195
122	4" REFL. BUTTON, TYPE II-Y-Y	EA	40																						122	40
123	24" THERMOPLASTIC STOP LINE	LF	71																						123	71
124	12" THERMOPLASTIC YIELD LINE	LF	152																						124	152
125	STREET AND TRAFFIC CONTROL SIGNS	EA	98																						125	98
126	UNISTRUT TELESPAR ST. SIGN POST, FND., ETC.	EA	58																						126	58
127	STREET BARRICADE	LF							37.5	37.5															127	75
128	BARRICADING, SIGNING AND TRAFFIC CONTROL	MO																				18			128	18
129	6' TALL BLACK VINYL COATED CH. LINK FENCE	LF											202												129	202
130	ITEM DELETED	NA											305												130	NA
131	ITEM DELETED	NA																							131	NA
132	ITEM DELETED	NA																							132	NA
133	DOWELLED ON 6" REINF. CONC. CURB	LF																			8				133	8
134	ITEM DELETED	NA																							134	NA
135	THERMOPLASTIC ADVISORY MARKER "YIELD"	EA	8																						135	8
136	8' X 7' REFL. DIAG. SIGN (ADV-D1 & ADV-D2)	EA	2																						136	2
137	8' X 6' REFL. DIAGRAMMATIC SIGN (ADV-D3)	EA	1																						137	1
138	5' X 2' REFL. STREET SIGN (ST-1, ST-2 & ST-3)	EA	3																						138	3
139	REM. EX. STREET LIGHT FOUNDATION	EA		5																					139	5
140	STREET LIGHT FOUND. (QUORUM)	EA		2																10					140	12
141	6" X 6" CLASS "A", TYPE I-C JIGGLE BAR TILE	EA	54																						141	54
142	LONGITUDINAL BUTT JOINT	LF			224		578																		142	802
143	ITEM DELETED	NA																							143	NA
144	INSTALL VEHICULAR BRICK PAVERS	SF												1471	10079	3806	1960	798	4906						144	23020
145	6" 650 PSI FLEX REINF. CONC. PAVEMENT	SY						1582	840	1657	874	328													145	5281
146	6" 650 PSI FLEX REINF. CONC. DROP SLAB (ST.)	SY												125			218	89	439						146	871
147	6.75' X 1.5' REFL. DIAG. SIGN (MWI-8-MOD.)	EA	3																						147	3
148	REMOVE & REPLACE CONC. UNIT PAVERS	SF											2670												148	2670
149	FURNISH & INSTALL 6" COMPACTED FLEX BASE	SY											297												149	297
150	REMOVE & DISPOSE OF CONCRETE FLUME	SY											41												150	41
151	REPLACE EX. VINYL COATED CH. LINK FENCE	LF											240												151	240
152	BUFFALO GRASS SEED AND FERTILIZER	SY											564												152	564
153	TEMP. IRRIGATION AT WATER TOWER SITE	LS											1												153	1
154	CONSTRUCTION SCHEDULES AND REPORTS	LS																				1			154	1

RECORD DRAWING 5/1/98

ISSUED FOR CONSTRUCTION
MARCH 28, 1996

THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY KENNETH A. ROBERTS, P.E. 55446 ON MARCH 28, 1996.

STATE OF TEXAS
KENNETH A. ROBERTS
55446
REGISTERED
PROFESSIONAL ENGINEER

3-28-96

QUANTITY SUMMARY SHEET

ADDISON CIRCLE

PHASE I PUBLIC INFRASTRUCTURE

TOWN OF ADDISON, TEXAS

Huitt-Zollars, Inc./Engineering/Architecture
Dallas, Fort Worth, Houston, El Paso, Phoenix, Tustin, Ontario, San Clemente

DESIGN	DRAWN	APPR.	SCALE	DATE	PROJECT NO.	NO.
HZI	HZI	KAR	NONE	JAN 96	1822-04	2 / 137

h:\proj\182204\dgn\AUCIQTO1.DGN