

ITEM NO.	DESCRIPTION	UNIT	SHEET SUMMARY																	ITEM NO.	PROJ. TOTAL			
			SHT 92	SHT 93	SHT 94	SHT 95	SHT 96	SHT 97	SHT 98	SHT 99	SHT 83	SHT 84	SHT 85	SHT 86	SHT 87	SHT 88	SHT 89	MISC						
SCHEDULE IV - WASTEWATER IMPROVEMENTS																								
401	8" SDR 26 PVC WW LINE INCL. EMBEDMENT	LF						20	5	15													401	40
402	8" SDR 35 PVC WW LINE INCL. EMBEDMENT	LF	193	359	450	190	447																402	1639
403	10" SDR 35 PVC WW LINE INCL. EMBEDMENT	LF	297	60																			403	357
404	12" SDR 26 PVC WW LINE INCL. EMBEDMENT	LF						500	500	564													404	1564
405	6" SDR 35 PVC WW LAT. W/ 2-WAY C.O. & LID	EA		4		5	3	5															405	17
406	4' DIA. WASTEWATER MANHOLE	EA			1	1	1																406	3
407	5' DIA. WASTEWATER MANHOLE	EA	2	2				2	3	2													407	11
408	TV INSPECTION	LF	490	419	450	190	447	520	505	579													408	3600
409	TRENCH SAFETY FOR CONSTRUCTION	LF	505	419	617	251	614	520	505	579													409	4010
SCHEDULE V - WATER IMPROVEMENTS																								
501	CONCRETE BLOCKING	CY									12.6	8.1	0.7	10.2		1.1	12.3					501	45	
502	D.I. CL. 250 IRON FITTINGS	TON									1.0	1.6	0.1	0.5		0.2	2.6					502	6	
503	6" DIA. PVC AWWA C900, DR 18, CL. 150 PIPE	LF									99	40	5	77		4							503	225
504	8" DIA. PVC AWWA C900, DR 18, CL. 150 PIPE	LF									504	537	116	445	296								504	1945
505	12" DIA. PVC AWWA C900, DR 18, CL. 150 PIPE	LF														76							505	76
506	24" AWWA C-303 BAR WRAP, CONC. CYL. PIPE	LF															248						506	248
507	ABANDON & FILL EX. 24" RCCP WATER LINE	LF															200						507	200
508	6" DIA. RESILIENT SEAT GATE VALVE/BOX	EA									3	4	1	3		1							508	12
509	8" DIA. RESILIENT SEAT GATE VALVE/BOX	EA									3	3		2	2								509	11
510	ITEM DELETED	NA																					510	NA
511	FIRE HYDRANT	EA									2	3	1	1		1	1						511	9
512	REM., SALVAGE & DELIVER TO TOWN EXIST. FH	EA																					512	3
513	CONN. TO EXIST. WATER MAIN (ALL SIZES)	EA									1											2	513	3
514	1.5" SERV., METER, BOX & BACKFLOW PREV.	EA									1			1									514	2
515	2" SERV., METER, BOX & BACKFLOW PREV.	EA																					515	1
516	6" SERVICE LINE FOR FIRE PROTECTION	EA									1			2									516	3
517	20" X 8" TAPPING SLEEVE VALVE/BOX	EA																					517	1
518	20" X 12" TAPPING SLEEVE VALVE/BOX	EA															1						518	1
519	2000 PSI CONC. ENCASEMENT	LF									60	20											519	80
520	ADJUST EXIST. WATER VALVE STACK/COVER	EA																				6	520	6
521	TRENCH SAFETY FOR CONSTRUCTION	LF									603	577	121	522	296	80	295						521	2494
522	WATER TEST	LS																				1	522	1
523	ITEM DELETED	NA																					523	NA
524	2" WATER SERVICE LINE	EA									5	1		11		1							524	18
525	INSTALL 24" AWWA C-303 CONC. CYL. PIPE	LF															248						525	248

RECORD DRAWING 5/1/98

ISSUED FOR CONSTRUCTION
MARCH 28, 1996

THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY
KENNETH A. ROBERTS, P.E. 55446
ON MARCH 28, 1996.



QUANTITY SUMMARY SHEET						
ADDISON CIRCLE						
PHASE I PUBLIC INFRASTRUCTURE						
TOWN OF ADDISON, TEXAS						
Huitt-Zollars, Inc./Engineering/Architecture Dallas, Fort Worth, Houston, El Paso, Phoenix, Tustin, Ontario, San Clemente						
DESIGN	DRAWN	APPR.	SCALE	DATE	PROJECT NO.	NO.
HZI	HZI	KAR	NONE	JAN 96	1822-04	5
						137