ITEM NO.	DESCRIPTION	UNIT	SHEET SUMMARY																						ITEM NO.	PROJ. TOTAL
			SHT 43	SHT 44	SHT 45	SHT 46	SHT 47	SHT 48	SHT 49	SHT 50	SHT 51	SHT 52	SHT 53	SHT 121	SHT 122	SHT 123	SHT 124	SHT 125	SHT 126	SHT 127	MISC					
	SCH. VIII - ALT. STREETSCAPE IMPROVE. (PH. II)																									
801	COMPLETE IRRIG. SYSTEM (E. SIDE QUORUM)	LS																			1				801	1
802	RED OAK TREE, 200 GAL., 5'-6" CAL., 16'-18' HT.	EA												15		25									802	40
803	4" PVC SCH. 40 PERF. SUBDRAIN SYSTEM	LF							306	82	633														803	1021
804	WEEPING LOVE GRASS	SF												7280	6700	15130									804	29110
805	STREET LIGHT PULL BOX	EA																			10				805	10
806	2" PVC STREET LIGHT CONDUIT	LF							325	108	633														806	1066
807	STREET LIGHT FOUNDATION	EA							5		9														807	14
808	CAP FOR LIGHT BASE	EA							5		9														808	14
809	3" PVC TREE LIGHT CONDUIT	LF																			1066				809	1066
	SCH. IX - ALT. STREETSCAPE IMPROVEMENTS																									
901	UPGRADED TREE GRATE	EA												28											901	28
902	ITEM DELETED	NA																							902	NA
903	PLANTER POT	EA																			22				903	22
904	ITEM DELETED	NA																							904	NA
905	ITEM DELETED	NA																							905	NA
906	SGL. BOWL DRINK. FOUNTAIN, INCL. PLUMBING	EA													1			1							906	2
907	WITT MEWS WALL MOUNT. CLOCK, INCL. ELEC.	EA																	1						907	1
908	ITEM DELETED	NA																							908	NA
909	ANTIQUE STREET LIGHT, TUE 17 MFND	EA							15	12	18	11	14												909	70
910	ITEM DELETED	NA																							910	NA
911	GRANITE BOLLARD	EA	7			2		62																	911	71
912	ROUNDABOUT DROP SLAB	SY		2060																					912	2060
913	4" CEMENT STABILIZED SUBGRADE (15 LBS./SY)	SY			24		505	144																	913	673
914	1/8" X 4" LANDSCAPE EDGING	LF			13		432	225																	914	670

RECORD DRAWING 5/1/98

ISSUED FOR CONSTRUCTION
MARCH 28, 1996

THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY KENNETH A. ROBERTS, P.E. 55446 ON MARCH 28, 1996.

STATE OF TEXAS
KENNETH A. ROBERTS
55446
REGISTERED PROFESSIONAL ENGINEER

3-28-96

QUANTITY SUMMARY SHEET

ADDISON CIRCLE

PHASE I PUBLIC INFRASTRUCTURE

TOWN OF ADDISON, TEXAS

Huitt-Zollars, Inc./Engineering/Architecture
Dallas, Fort Worth, Houston, El Paso, Phoenix, Tustin, Ontario, San Clemente

DESIGN	DRAWN	APPR.	SCALE	DATE	PROJECT NO.	NO.
HZI	HZI	KAR	NONE	JAN 96	1822-04	7 / 137

h:\proj\182204\dgn\AUCIQTOS.DGN