ADDISON CIRCLE PHASE III BUILDING "3B"

MORRIS AVE.

FUTURE DEVELOPMENT

FUTURE PARK

GOODMAN AVE.

ADDISON CIRCLE PHASE II BUILDING "3A"

ARTIST WAY

LINE 'A'
8" WW

PRIVATE PLUMBER TO EXTEND LINE FROM DOUBLE CLEANOUT TO BUILDING F.L.=6" 624.24

PRIVATE PLUMBER TO EXTEND LINE FROM DOUBLE CLEANOUT TO BUILDING F.L.=6" 630.08

PRIVATE PLUMBER TO EXTEND LINE FROM DOUBLE CLEANOUT TO BUILDING F.L.=6" 631.51

PRIVATE PLUMBER TO EXTEND LINE FROM DOUBLE CLEANOUT TO BUILDING F.L.=6" 622.73

PRIVATE PLUMBER TO EXTEND LINE FROM DOUBLE CLEANOUT TO BUILDING F.L.=6" 629.24

CONSTRUCT 8" WASTEWATER

1+00.00 LINE 'A' MORRIS AVE. = ℄ PAV. STA. 8+11.60, 14.50' RT.
CONN. TO EX. 4' M.H.
EX. RIM=629.70
ADJUST RIM TO 631.82

1+93.56 LINE 'A'
CONST. 6" WW LATERAL W/2-WAY CLEANOUT & CAP

2+18.31 LINE 'A'
CONST. 6" WW LATERAL W/2-WAY CLEANOUT & CAP

3+50.00 LINE 'A'
CONST. 6" WW LATERAL W/2-WAY CLEANOUT & CAP

3+55.43 LINE 'A' = ℄ PAV. 19+97.70, 12.10' RT.
CONST. STD. 4' DIA. M.H.
RIM=637.56
CONST. 6" WW LATERAL W/2-WAY CLEANOUT & CAP

4+86.63 LINE 'A'
CONST. 6" WW LATERAL W/2-WAY CLEANOUT & CAP

10 L.F. CONC. ENCASEMENT

6+32.73 LINE 'A' ARTIST WAY = ℄ PAV. STA. 22+75.00, 12.10' RT.
CONST. STD. 4' DIA. M.H.
RIM=641.06

6+37.73
END & PLUG 8"
FL 632.29

N

0 10 20 30 40
SCALE IN FEET

RECORD DRAWING

1+00.00 LINE 'A'
CONN. TO EX. 4' M.H.
EX. RIM=629.70
ADJUST RIM TO 631.82

1+08+/- LINE 'A'
EX. 24" STM
TO BE REMOVED

1+21+/- LINE 'A'
EX. 6"ϕ

1+29+/- LINE 'A'
PROP. 8" W/R

1+70+/- LINE 'A'
PROP. 18" STM

1+83.56 LINE 'A'
CONST. 6" WW LATERAL

2+18.31 LINE 'A'
CONST. 6" WW LATERAL

2+58+/- LINE 'A'
PROP. 1.5" W/R

3+19+/- LINE 'A'
PROP. 4" W/R

3+27+/- LINE 'A'
PROP. 6" W/R

3+50.00 LINE 'A'
CONST. 6" WW LATERAL

3+55.43 LINE 'A'
CONST STD. 4' DIA M.H.
RIM=637.36

4+17+/- LINE 'A'
PROP. 6"ϕ

4+25+/- LINE 'A'
PROP. 8" W/R

4+65+/- LINE 'A'
PROP. 18" STM

4+86.63 LINE 'A'
CONST. 6" WW LATERAL

6+32.73 LINE 'A'
CONST STD. 4' DIA M.H.
RIM=641.06

PROP GRADE ℄ ℄ PIPE

TAN LIMESTONE

GRAY LIMESTONE

8" PVC ON 3.95%

8" PVC ON 1.0%

10 L.F. CONC. ENCASEMENT

F.L. 8" (IN) 618.93 N
F.L. EX. 8" (OUT) 618.12 E
F.L. 24" 623.65
BITM 613.00
F.L. 8" 622.45
F.L. 8" 620.91
F.L. 18" 627.05
F.L. 8" 622.62
F.L. 6" 622.70
F.L. 8" 622.88
F.L. 8" 623.50
F.L. 6" 623.68
F.L. 8" 624.86
F.L. 1.5" 627.10
F.L. 8" 626.83
F.L. 4" 629.10
F.L. 6" 629.03
F.L. 8" 628.80
F.L. 6" 628.88
F.L. 8" 628.80
F.L. 8" (OUT) 629.02
F.L. 6" (IN) 629.27
F.L. 8" (IN) 629.27
F.L. 8" 629.72
BITM 625.71
F.L. 8" 625.63
F.L. 8" 630.22
F.L. 18" 633.50
F.L. 8" 630.59
F.L. 6" 630.67
F.L. 8" 630.72
F.L. 8" 631.22
F.L. 8" 631.72
F.L. 8" 632.04
F.L. 8" 632.24

CONSTRUCT 532.72 8" PVC SDR 35 WASTEWATER LINE 'A'

1+00 2+00 3+00 4+00 5+00 6+00

605 610 615 620 625 630 635 640 645

BENCHMARKS:

BM#5
"□" CUT ON 8' INLET ON NORTH CURB LINE OF GOODMAN AVE. ±75' EAST OF PASCHAL PLACE.
ELEV. 629.98

BM#6
"□" CUT AT ℄ OF 8' INLET AT THE SOUTHWEST CORNER OF MORRIS AVE. AND WITT PLACE.
ELEV. 627.29

BM#7
"□" CUT AT WEST CORNER OF ADDISON THEATRE CENTRE PARKING LOT, SECOND ENTRANCE NORTH OF ADDISON RD.
ELEV. 637.66

THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY DAVID E. MEYERS, P.E. 81512

STATE OF TEXAS · DAVID E. MEYERS · 81512 · REGISTERED PROFESSIONAL ENGINEER · 12/13/00

DATE	DESCRIPTION	REF NO.
6/23/99	ISSUED FOR CONSTRUCTION	N/A
5/17/99	ISSUED FOR BID	N/A

WASTEWATER PLAN & PROFILE
LINE A - STA. 1+00.00 TO STA. 6+32.73

ADDISON CIRCLE
PHASE II-B PUBLIC INFRASTRUCTURE

TOWN OF ADDISON, TEXAS

Huitt - Zollars, Inc.
3131 Mckinney Ave., Suite 600, Dallas, TX 75204
Phone (214) 871-3311/Fax (214) 871-0757

DESIGN	DRAWN	APPR.	SCALE	DATE	PROJECT NO.	NO.
HZI	HZI	DEM	H: 1"=20' V: 1"=6'	MAR. 99	01-1822-50	WWI

h:\proj\01182250\dgn\AUC3WW01.DGN