

Adjoiner Index

Table with columns: Index, Owner, Vol., Page. Lists various tracts and owners like Texas Turnpike Authority, Texas Federal Subdivision, etc.

Parent Tracts

Owner: City of Addison
Address: 15333 Addison Road City of Addison, Texas
Legal Description: Being all the certain tract of land 373.332 acres, more or less, out of the Edward Cook Survey Abstract 326, the William Lomar Survey Abstract 792, the George Syms Survey Abstract 1344, the William Rowe Survey Abstract 1257, Lot 1R-1, Block A of Coil Addition, Vol. 2002003, Pg. 103, Dallas County, Texas, and part of Lot 1 and Lot 2 of Block "A" of The Carroll Estates Addition, Volume 10 Page 473, Dallas County, Texas

Control Monument

(NAD 83, TEXAS NORTH CENTRAL - 4202)

Table with columns: North, East, Elevation, Desc. Lists monument coordinates and descriptions.

PROPERTY DESCRIPTION

Being a tract of land out of the E. Cook Survey, Abstract No. 326, the William Lomar Survey, Abstract No. 792, the George Syms Survey, Abstract 1344, and the William Rowe Survey, Abstract 1257, and being all of a tract of land described in deed to the City of Addison recorded in Volume 77010, Page 1391 of the Deed Records of Dallas County, Texas, (D.R.D.C.T.), all of a tract of land described in Judgment to the City of Addison recorded in Volume 91079, Page 2687, D.R.D.C.T., LOT 7, Block B of Beltwood North Addition, Phase II, an Addition to the City of Dallas, Texas, according to the map thereof recorded in Volume 78201, Page 0001, D.R.D.C.T., as described in deed to the City of Addison recorded in Volume 82022, Page 1211, D.R.D.C.T., a tract of land described in deed to the Town of Addison recorded in Volume 99015, Page 2143, D.R.D.C.T. a tract of land described in deed to the Town of Addison recorded in Volume 97217, Page 1350, D.R.D.C.T., Lot 1, Block 1, of Kincaid Addition, an Addition to the City of Addison, Dallas County, Texas, according to the Plat thereof recorded in Volume 94087, Page 48, D.R.D.C.T., a tract of land described in deed to the Town of Addison recorded in Volume 99249, Page 5436, D.R.D.C.T., a tract of land described in deed to the Town of Addison recorded in Volume 99078, Page 1254, D.R.D.C.T., a tract of land described in Deed to the City of Addison recorded in Volume 5143, Page 162, D.R.D.C.T., and a tract of land described in Deed to the City of Addison recorded in Volume 81150, Page 1985, D.R.D.C.T., said tracts to be known as the Addison Airport tract and being more particularly described as follows:

Beginning at a concrete monument found with a 3 1/2 inch disk stamped "City of Addison" lying in the west right-of-way line of Westgrove Road (a 60 foot wide right-of-way) said point being the most northerly northeast corner of said Addison Airport tract and the southeast corner of Lot 1, Block A, Academy Addition, an addition to the City of Carrollton, Dallas County, Texas according to the Plat thereof recorded in Volume 79186, Page 1, D.R.D.C.T.;

THENCE South 00 degrees 39 minutes 05 seconds East, along the west right-of-way line of said Westgrove Road, a distance of 1547.64 feet to a 5/8 inch iron rod set with cap stamped "DAL-TECH";

THENCE South 21 degrees 16 minutes 44 seconds East, continuing along said west right-of-way line of Westgrove Road, a distance of 539.35 feet to a 5/8 inch iron rod set with cap stamped "DAL-TECH";

THENCE along a curve to the left of said Westgrove Road having a radius of 340.00 feet, a central angle of 69 degrees 17 minutes 21 seconds and an arc length of 411.17 feet, being subtended by a chord of South 55 degrees 55 minutes 24 seconds East for a distance of 386.57 feet to a 5/8 inch iron rod set with cap stamped "DAL-TECH";

THENCE North 89 degrees 25 minutes 55 seconds East, along the southerly right-of-way line of Westgrove Road for a distance of 2,118.93 feet to a 5/8 inch iron rod set with cap stamped "DAL-TECH" at the corner clip of said southerly right-of-way line of Westgrove Road and the west right-of-way line of Addison Road (a 60 foot wide right-of-way);

THENCE South 45 degrees 37 minutes 02 seconds East, along said corner clip, a distance of 21.23 feet to a 5/8 inch iron rod set with cap stamped "DAL-TECH";

THENCE South 00 degrees 39 minutes 59 seconds East, along said west right-of-way line of Addison Road, a distance of 299.74 feet to a 5/8 inch iron rod set with cap stamped "DAL-TECH";

THENCE South 89 degrees 18 minutes 30 seconds West, departing said west right-of-way line of Addison Road, a distance of 200.12 feet to a chiseled "X" set in concrete;

THENCE South 00 degrees 41 minutes 30 seconds East, a distance of 201.72 feet to a found "X";

THENCE South 42 degrees 48 minutes 04 seconds West, a distance of 1,596.12 feet to a found "X";

THENCE South 47 degrees 17 minutes 56 seconds East, a distance of 202.54 feet to a 5/8 inch iron rod set with cap stamped "DAL-TECH";

THENCE South 21 degrees 16 minutes 56 seconds East, a distance of 350.89 feet to a chiseled "X" set in concrete;

THENCE North 68 degrees 43 minutes 04 seconds East, a distance of 30.00 feet to a chiseled cross set in concrete;

THENCE North 70 degrees 38 minutes 55 seconds East, a distance of 185.74 feet to a 5/8 inch iron rod set with cap stamped "DAL-TECH";

THENCE North 44 degrees 10 minutes 12 seconds East, a distance of 7.05 feet to a 5/8 inch iron rod set with cap stamped "DAL-TECH", said point is the common corner between the aforesaid Addison Airport tract and the southwest corner of a tract of land described in deed to D.J. Broughton and E.E. Ericson recorded in Volume 4350, Page 491 of D.R.D.C.T.;

THENCE North 89 degrees 20 minutes 44 seconds East, along the common line of said Addison Airport tract and the south line of said O.J. Broughton tract for a distance of 818.27 feet to a 5/8 inch iron rod set with cap stamped "DAL-TECH" in the west right-of-way line of aforesaid Addison Road;

THENCE South 00 degrees 39 minutes 59 seconds East, a distance of 490.88 feet to a 5/8 inch iron rod set with cap stamped "DAL-TECH" in the apparent common survey line between the aforesaid William Lomar Survey, Abstract No. 792 and the aforesaid E. Cook Survey, Abstract No. 326;

THENCE North 89 degrees 47 minutes 19 seconds East, a distance of 60.66 feet to a 1/2 inch iron rod set with cap stamped "DAL-TECH" in the aforesaid west right-of-way line of Addison Road;

THENCE along a curve to the left in the said west right-of-way line of Addison Road, having a radius of 746.30 feet, a central angle of 01 degree 54 minutes 15 seconds and an arc length of 24.80 feet, being subtended by a chord of South 25 degrees 45 minutes 41 seconds East for a distance of 24.80 feet to a 5/8 inch iron rod set with cap stamped "DAL-TECH";

THENCE South 26 degrees 42 minutes 49 seconds East, along said west right-of-way line of Addison Road, a distance of 34.05 feet to a 5/8 inch iron rod set with cap stamped "DAL-TECH";

THENCE along a curve to the right in the said west right-of-way line of Addison Road having a radius of 886.30 feet, a central angle of 25 degrees 50 minutes 01 second and an arc length of 309.44 feet, being subtended by a chord of South 13 degrees 47 minutes 49 seconds East for a distance of 306.83 feet to a 5/8 inch iron rod set with cap stamped "DAL-TECH";

THENCE South 00 degrees 52 minutes 49 seconds East, along said west right-of-way line of Addison Road, a distance of 2,973.50 feet to a 5/8 inch iron rod set with cap stamped "DAL-TECH";

THENCE South 03 degrees 27 minutes 59 seconds East, along said west right-of-way line of Addison Road, a distance of 9.28 feet to a 5/8 inch iron rod set with cap stamped "DAL-TECH";

THENCE North 89 degrees 58 minutes 24 seconds West, departing said west right-of-way line of Addison Road, a distance of 165.27 feet to a 5/8 inch iron rod set with cap stamped "DAL-TECH";

THENCE South 00 degrees 09 minutes 24 seconds East, a distance of 243.18 feet to a 5/8 inch iron rod set with cap stamped "DAL-TECH";

THENCE South 61 degrees 10 minutes 39 seconds West, a distance of 17.74 feet to a 1/2 inch iron rod found;

THENCE South 00 degrees 09 minutes 29 seconds East, a distance of 209.98 feet to a 5/8 inch iron rod set with cap stamped "DAL-TECH" in the north right-of-way line of the Fort Worth and Denver Railroad spur;

THENCE South 65 degrees 42 minutes 08 seconds West, along said north right-of-way line of said Fort Worth and Denver Railroad spur, a distance of 759.64 feet to a 5/8 inch iron rod found at the most easterly corner of the Addison Airport Industrial District, an Addition to the City of Addison according to the plat thereof recorded in Volume 50, Page 207, D.R.D.C.T.;

THENCE North 67 degrees 26 minutes 03 seconds West, along the said easterly line of Addison Airport Industrial District addition, a distance of 272.68 feet to a 5/8 inch iron rod found;

THENCE North 21 degrees 09 minutes 30 seconds West, along the said easterly line of Addison Airport Industrial District addition, a distance of 571.54 feet to a 5/8 inch iron rod set with cap stamped "DAL-TECH";

THENCE South 75 degrees 21 minutes 17 seconds West, a distance of 449.71 feet to a found railroad spike;

THENCE North 89 degrees 59 minutes 56 seconds West, a distance of 654.32 feet to a 5/8 inch iron rod set with cap stamped "DAL-TECH";

THENCE North 00 degrees 00 minutes 04 seconds East, a distance of 159.62 feet to a 5/8 inch iron rod set with cap stamped "DAL-TECH";

THENCE North 89 degrees 59 minutes 56 seconds West, a distance of 160.02 feet to a 5/8 inch iron rod set with cap stamped "DAL-TECH" in the east right-of-way line of Midway Road (a 100 foot wide right-of-way);

THENCE North 00 degrees 00 minutes 04 seconds East, along said east right-of-way line of Midway Road, a distance of 10.00 feet to a 5/8 inch iron rod set with cap stamped "DAL-TECH";

THENCE South 89 degrees 59 minutes 56 seconds East, a distance of 792.25 feet to a 1/2 inch iron rod found with cap stamped "MLM #2617";

THENCE North 75 degrees 21 minutes 17 seconds East, a distance of 408.83 feet to a 1/2 inch iron rod found with cap stamped "MLM #2617";

THENCE North 21 degrees 09 minutes 30 seconds West, along the aforesaid easterly line of said Addison Airport Industrial District addition, a distance of 2,385.88 feet record to a 1/2 inch iron rod found;

THENCE North 21 degrees 01 minute 39 seconds West, a distance of 320.94 feet to a 5/8 inch iron rod set with cap stamped "DAL-TECH";

THENCE North 89 degrees 44 minutes 31 seconds East, a distance of 10.21 feet to a 5/8 inch iron rod set with cap stamped "DAL-TECH";

THENCE North 20 degrees 38 minutes 06 seconds West, a distance of 221.75 feet to a 5/8 inch iron rod set with cap stamped "DAL-TECH";

THENCE North 89 degrees 54 minutes 56 seconds West, a distance of 177.90 feet to a 5/8 inch iron rod set with cap stamped "DAL-TECH" in the east right-of-way line of Dooley Road (a 50 foot wide right-of-way);

THENCE North 00 degrees 18 minutes 06 seconds West, along the said east right-of-way line of Dooley Road, a distance of 663.91 feet to a 5/8 inch iron rod set with cap stamped "DAL-TECH" for the apparent intersection of said east right-of-way line of Dooley Road and the north right-of-way line of the old Keller Springs Road (a 50 foot wide right-of-way);

THENCE South 89 degrees 33 minutes 56 seconds West, with the said north line of Keller Springs Road, a distance of 105.61 feet to a 5/8 inch iron rod set with cap stamped "DAL-TECH";

THENCE North 56 degrees 29 minutes 35 seconds West, a distance of 65.57 feet to a 5/8 inch iron rod set with cap stamped "DAL-TECH" in the aforesaid east right-of-way line of Dooley Road (a 60 foot wide right-of-way);

THENCE South 89 degrees 19 minutes 27 seconds West, a distance of 361.02 feet to a 5/8 inch iron rod found;

THENCE North 00 degrees 28 minutes 50 seconds West, a distance of 231.53 feet to a 1/2 inch iron rod found;

THENCE North 89 degrees 17 minutes 19 seconds East, a distance of 1.24 feet to a 1/2 inch iron rod found with cap stamped SJ&F

THENCE North 00 degrees 34 minutes 41 seconds West, a distance of 470.04 feet to a 5/8 inch iron rod set with cap stamped "DAL-TECH" in the east line of Beltwood North Phase 2, an addition to the City of Dallas, Texas, according to the Plat thereof recorded in Volume 78201, Page 1, D.R.D.C.T.;

THENCE East, a distance of 70.73 feet along said Beltwood North Phase 2 addition to a 5/8 inch iron rod set with cap stamped "DAL-TECH";

THENCE North 00 degrees 39 minutes 08 seconds West, along said Beltwood North Phase 2 addition, a distance of 235.73 feet to a 5/8 inch iron rod set with cap stamped "DAL-TECH" for the most southerly corner of Lot 7 of said Beltwood North Phase 2 addition;

THENCE North 21 degrees 08 minutes 57 seconds West, passing the north line of said Beltwood North Phase 2 addition at a called distance of 576.04 feet and continuing on for a total distance of 2,125.91 feet to a 5/8 inch iron rod set with cap stamped "DAL-TECH" for the northeast corner of Beltwood North Addition, according to the plat thereof recorded in Volume 78201, Page 1, D.R.D.C.T., same being the southeast corner of Lot 1R-1, Block A, Coil Addition, according to the plat thereof recorded in Volume 2002003, Page 103, D.R.D.C.T.;

THENCE South 89 degrees 35 minutes 51 seconds West, along the common line between the north line of said Beltwood Addition and the south line of said Coil Addition, a distance of 214.48 feet to a 1/2 inch iron rod found in the east right-of-way line of Midway Road (a 100 foot wide right-of-way);

THENCE North 00 degrees 21 minutes 08 seconds West, along said east right-of-way line of Midway Road, passing a 1/2 inch iron rod found for the North corner of said Lot 1R-1, Block A, at a distance of 564.89 feet and continuing for a total distance of 1,756.20 feet to a 1/2 inch iron rod found with cap stamped "SURVCON";

THENCE North 89 degrees 24 minutes 55 seconds East, a distance of 1,165.10 feet to the POINT OF BEGINNING and CONTAINING 16,492,399 square foot or; 378.6 acres of land, more or less.

I, Alan Moore, a Registered Professional Land Surveyor in the State of Texas, do hereby certify that I prepared this Plat from an actual survey of the land under my supervision in accordance with the "Minimum Standards of Practice" approved by the Texas Board of Professional Land Surveyors.

Alan Moore, RPLS No. 5537

Town of Addison Approval:
City Secretary: Carmen Moran
Scott Wheeler Mayor (Town of Addison)



FINAL PLAT ADDISON AIRPORT TOWN OF ADDISON, TEXAS. Table with columns: DRAWN, JOB NO., CONTRACT NO., SCALE, DATE. Values: DTE, 0216, -, 1"=300', DEC. 2004

