



GENERAL NOTES

1. Notify affected utility companies before starting work and comply with their requirements.
2. Owner assumes no responsibility for actual condition of areas to be demolished.
3. Perform work in manner to eliminate hazards to persons or property and avoid interference with adjacent areas, utilities and structures.
4. Provide and maintain temporary barricades, fences, warning signs, guardrails, warning lights.
5. Protect existing structures, landscaping materials, and appurtenances which are not being demolished.
6. Prevent movement or settlement of adjacent structures and perimeter basement walls that remain. Provide bracing and shoring as necessary and be responsible for safety and support of structure. Assume liability for such movement, settlement, damage or injury.
7. Cease demolition operations immediately if adjacent structures appear to be in danger. Conduct safety operations as necessary. Do not resume demolition operations until directed.
8. Return structures and surfaces to remain to conditions existing prior to commencement of selective demolition work.

JAMES A. RILEY
   
 73231
   
 11-16-98

**AS-BUILT**

NOTE: THESE PLANS HAVE BEEN REVISED TO CONFORM WITH CONSTRUCTION RECORDS PROVIDED BY CONTRACTOR.

<b>DEMOLITION PLAN</b>						
<b>16200 ADDISON ROAD OFFICE BLDG.</b>						
<b>TOWN OF ADDISON</b>						
<b>DALLAS COUNTY, TEXAS</b>						
BROCKETTE · DAVIS · DRAKE, inc. consulting engineers Civil & Structural Engineering · Surveying 4144 North Expressway, Suite 1100 Dallas, Texas 75204 (214) 824-3647, fax (214) 824-7064						
DESIGN	DRAWN	DATE	SCALE	NOTES	FILE	NO.
JAR	CRN	11/97	1"=30'	C97318		<b>C-3</b>