



- CONSTRUCTION NOTES**
- WATER**
- 1 6" FIRE HYDRANT ASSEMBLY WITH 6" GATE VALVE
 - 2 8"x8" TEE WITH THRUST BLOCK PER DETAIL ON SHT. 11
 - 3 8" 45° ELL WITH THRUST BLOCK PER DETAIL ON SHT. 11
 - 4 4" WATER SERVICE ASSEMBLY PER CITY STD SHOWN ON SHT. 11
 - 5 8" FIRE SERVICE ASSEMBLY WITH DOUBLE DETECTOR CHECK CHECK BACKFLOW PREVENTER (IN VAULT W/ BY-PASS METER) PER CITY STANDARDS
 - 6 8" GATE VALVE AND VALVE BOX PER DETAIL ON SHT. 11
 - 7 8" PVC WATER MAIN
 - 8 2" IRRIGATION WATER SERVICE PER CITY STANDARD
- SEWER**
- 10 8" PVC SEWER
 - 11 DOUBLE 8" SANITARY SEWER CLEANOUT PER DETAIL ON SHT. 11
 - 12 8" SANITARY SEWER CLEANOUT PER DETAIL ON SHT. 11
- SLEEVE**
- 21 SLEEVE FOR IRRIGATION PER LANDSCAPE PLANS

- WATER meter sleeves Deeper than 12" from top of meter to finish grade shall have remote Reader Registers and Covers installed in a location near to of meter Box for additional info call B.ellis - 450-2847

- No open cuts in Roadways

BUY-PITTMAN
 UTILITY PLAN
 EXCEL TELECOMMUNICATIONS SERVICE CENTER
 A DEVELOPMENT OF WILCOX/CMC ADDISON, INC.
 Scale: 1" = 40' Date: 12-1-85
 Title: Drawn by: A.B.C.
 Xref: 02701.dwg, 02701.pba
 File: 02701.dwg
 Approved by: O.L.V.
 Project No.: 3027-01
 SHEET 7 OF 12