



- NOTES:**
- 8" waterline shall be C-900 PVC DR-18.
 - Water main to have minimum depth of cover of 4' below existing grade or as required to clear other utilities. Embedment per city specs.
 - F.H. as required by city.
 - 6" sanitary sewer shall be D-3034 PVC DR-35.
 - Steel encasement pipe shall be smooth bore steel pipe, 14" O.D., 1/4" wall thickness, with bituminous coating.
 - Gate valves shall conform to the AWWA standard for gate valves for ordinary waterworks service, AWWA C 500.
 - Gate valves to be installed with valve box covers and extensions as required.
 - Contractor is cautioned that there may be existing utilities and services existing and not shown on the plan, verify location of all utilities.
 - All construction shall conform to City of Addison standards and specifications.
 - Block all fittings with 2000 p.s.i. conc. per city specs.

"AS BUILT"
12-8-87

No.	Date	Revisions
MAR 87	REVISED SAN. SWR. LOCATION	N.B.A.
AUG 86	RELOCATE EXIST. F.H.	L.H.E.

Lois K. King 7-7-86

TRINITY CHRISTIAN ACADEMY
ADDISON, TEXAS

CLIENT: TOM DANCE ARCHITECT
8850 N. CENTRAL EXPRESSWAY
DALLAS, TEXAS 75231

WATER & SANITARY SEWER PLAN

Date: JUNE 1986
Designed by: N.B.A.
Drawn by: P.A.W.A.
Checked by:
Approved by:
Project No. 382.03

P.A.W.A. Winkelmann & Associates, Inc.
CIVIL / TRANSPORTATION ENGINEERS • PLANNERS • SURVEYORS
12660 COTT ROAD, SUITE 200
DALLAS, TX 75251