

ITEM NO.	DESCRIPTION	UNIT	EST. QTY.
ROADWAY IMPROVEMENTS			
101	MOBILIZATION	L.S.	1
102	PREPARE RIGHT-OF-WAY	L.S.	1
103	FULL DEPTH SAWCUT EXISTING PAVEMENT	L.F.	755
104	REMOVE AND DISPOSE OF EXISTING PAVEMENT, INCLUDING CURB	S.Y.	1,650
105	UNCLASSIFIED STREET EXCAVATION	C.Y.	500
106	EMBANKMENT	C.Y.	100
107	10" THICK REINFORCED CONCRETE PAVEMENT, 4000 PSI @ 28 DAYS	S.Y.	2,800
108	FURNISH, INSTALL 10' RECESSED CURB INLET	EA	2
109	CLASS III 18" RCP STORM DRAIN PIPE, INCLUDING FITTINGS	L.F.	108
110	REMOVE AND RELOCATE ROADSIDE SIGN	EA.	0
111	15 MPH SPEED LIMIT SIGN (R2-1)	EA.	2
112	FIRE LANE STRIPING	L.F.	1,100
113	SOLID SODDING	S.Y.	900
114	FURNISH, INSTALL, MAINTAIN AND REMOVE SILT FENCE	L.F.	300
115	INLET PROTECTION (DROP)	EA	2
116	IRRIGATION CONDUIT, 4" SCH 40 PVC	L.F.	114
117	FURNISH, INSTALL, SECURITY GATE WITH ACCESS CONTROL PANEL	LS	1
118	AOA SECURITY FENCE	LF	300
119	REMOVE AND DISPOSE OF TEMPORARY ROAD	LS	1
120	REMOVE AND DISPOSE OF SECURITY FENCE	LF	195
121	CLASS III 12" RCP STORM DRAIN PIPE	LF	95
122	FURNISH, INSTALL MAINTAIN AND REMOVE 20-FT SECURITY GATE	EA	0
123	CONDUIT, 2" SCH 40 PVC	LF	285
124	FOUNDATION, 30' STREET LIGHT POLE	EA	1
125	GROUND MOUNTED PULL BOX, TYPE A	EA	1
126	CABLE INSULATED, #8 AWG	LF	600
127	CABLE, BARE #8 AWG	LF	300

△
△
△
△
△
△

-NOV-2003 10:31 \\39020\Cad\Sheets\opqt01.dgn

NO.	DATE	REVISION	APPROV.	NO.	DATE	REVISION	APPROV.
1.	10/10/03	ADDED LINE ITEMS, MODIFIED QUANTITIES	JSN				
2.	11/18/03	MODIFIED QUANTITIES	JSN				



11/19/03

HNTB ARCHITECTS ENGINEERS PLANNERS <small>The HNTB Companies</small>	
DESIGN CHECK	JSN JDH
DRAWN CHECK	GFS JSN
DATE	SEPTEMBER 2003



TOWN OF ADDISON
AIRPORT PARKWAY REALIGNMENT

QUANTITIES

"As-Built"

SHEET