



FIRE LANE STRIPING DETAIL
NOT TO SCALE

STRIPING DETAIL NOTES:

1. A. PAINT:
 1. STRIPE SHALL BE FIVE (5) INCHES WIDE PAINTED WITH AN EXTERIOR LATEX PAINT. COLOR SHALL BE "TRAFFIC RED" GLIDDEN NO. 63251 OR EQUAL.
 2. LETTERS SHALL BE FOUR (4) INCHES HIGH PAINTED WITH AN EXTERIOR ACRYLIC LATEX PAINT. COLOR SHALL BE "TRAFFIC WHITE" GLIDDEN NO. 563245 OR EQUAL.
- B. APPLICATION:
 1. STRIPE MAY BE BRUSHED OR SPRAYED, ONE COAT TO FINISH.
 2. LETTERS SHALL BE STENCIL FORMED, BRUSH APPLIED AND SPACED AS DETAILED ON THIS SHEET.
2. "FIRE LANE NO PARKING" TO BE PAINTED ENTIRE LENGTH OF DEDICATED FIRE LANE.
3. WHERE PRACTICAL ALL FIRE LANE MARKINGS SHALL BE REQUIRED TO BE PLACED ON THE CURB.
4. FOR ADDITIONAL FIRE LANE SPECIFICATIONS, PLEASE CONTACT THE FIRE DEPARTMENT.

g:\39020\Cad\Sheets\opdt03.dgn 22-SEP-2003 12:28

NO.	DATE	REVISION	APPROV.	NO.	DATE	REVISION	APPROV.



9/22/03

HNTB ARCHITECTS ENGINEERS PLANNERS <small>The HNTB Companies</small>	
DESIGN CHECK	JSN
	JDH
DRAWN CHECK	GFS
	JSN
DATE	SEPTEMBER 2003
SCALE	



TOWN OF ADDISON	SHEET
AIRPORT PARKWAY REALIGNMENT	
MISCELLANEOUS DETAILS	
TOWN OF ADDISON, TEXAS	