



REGISTRATION NO. F-5713

RECORD DRAWINGS 03/10/2015

REV.	DATE	DESCRIPTION	BY

Addison Airport
ADDISON, TEXAS
RUNWAY 33 RSA IMPROVEMENTS

GENERAL NOTES & SHEET INDEX

JOB NO.: 13081100
DATE: NOV. , 2013
DESIGNED BY: MRM
DRAWN BY: MRM

BAR IS ONE INCH ON ORIGINAL DRAWING
0 1" IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.

DRAWING NUMBER G-102

SHEET NUMBER 2

Sheet List Table

Sheet Number	Drawing Number	Sheet Title
GENERAL		
1	G-101	COVER SHEET
2	G-102	GENERAL NOTES & SHEET INDEX
3	G-103	SUMMARY OF QUANTITIES
4	G-201	SAFETY & PHASING PLAN - OVERALL
5	G-202	SURVEY CONTROL PLAN
6	G-203	SAFETY & PHASING DETAILS
7	G-301	SAFETY & PHASING PLAN - PHASE 1
8	G-302	SAFETY & PHASING PLAN - PHASE 1A
9	G-303	SAFETY & PHASING PLAN - PHASE 1B
10	G-304	SAFETY & PHASING PLAN - PHASES 1C & 1D
11	G-305	SAFETY & PHASING PLAN - PHASE 2
12	G-306	SAFETY & PHASING PLAN - PHASE 3
12A	G-307	SAFETY & PHASING PLAN - EMAS BLOCK DELIVERY AND HAUL ROUTES
13	G-401	STORM WATER POLLUTION PREVENTION LAYOUT PLAN
14	G-402	STORM WATER POLLUTION PREVENTION PLAN NOTES
15	G-403	STORM WATER POLLUTION PREVENTION PLAN DETAILS I
16	G-404	STORM WATER POLLUTION PREVENTION PLAN DETAILS II
CIVIL		
17	C-100	RUNWAY 33 RSA TYPICAL SECTION
18	C-101	RUNWAY 33 RSA LAYOUT PLAN
19	C-102	EMAS PLAN VIEW
20	C-103	EMAS PROFILE VIEW
21	C-104	EMAS DETAILS
22	C-105	EMAS UNDERDRAIN DETAILS
23	C-106	EMAS PAVEMENT MARKING PLAN
24	C-107	EMAS PAVEMENT MARKING DETAILS
25	C-200	DRAINAGE SECTION CUTS
26	C-201	DRAINAGE DEMOLITION PLAN
27	C-202	EAST DRAINAGE LAYOUT PLAN
28	C-203	WEST DRAINAGE LAYOUT PLAN
29	C-204	DRAINAGE PROFILES
30	C-205	DRAINAGE DETAILS I
31	C-206	DRAINAGE DETAILS II
32	C-207	LINDBERGH CROSSING JOINT PLAN & DETAILS
33	C-208	EMAS ACCESS ROAD TYPICAL SECTION AND DETAILS
34	C-209	EMAS ACCESS ROAD PLAN & PROFILE
35	C-210	SOUTHWEST ACCESS ROAD TYPICAL SECTION
36	C-211	SOUTHWEST ACCESS ROAD PLAN & PROFILE
37	C-212	SOUTH WATER LINE PLAN & PROFILE
38	C-213	WATER LINE DETAILS
39	C-300	RAINWATER HARVESTING TYPICAL SECTION (ADD ALTERNATE A)
40	C-301	RAINWATER HARVESTING LAYOUT PLAN (ADD ALTERNATE A)
41	C-302	RAINWATER HARVESTING DETAILS I (ADD ALTERNATE A)
42	C-303	RAINWATER HARVESTING DETAILS II (ADD ALTERNATE A)
43	C-304	RAINWATER HARVESTING DETAILS III (ADD ALTERNATE A)
ELECTRICAL		
44	E-001	ELECTRICAL LEGEND AND NOTES
45	E-101	AIRFIELD ELECTRICAL IMPROVEMENTS DEMOLITION PLAN
46	E-102	AIRFIELD ELECTRICAL IMPROVEMENTS INSTALLATION PLAN
47	E-201	RAINWATER HARVESTING ELECTRICAL INSTALLATION PLAN
48	E-301	ELECTRICAL DETAILS I
49	E-302	ELECTRICAL DETAILS II
50	E-303	ELECTRICAL DETAILS III
51	E-304	ELECTRICAL DETAILS IV
52	E-305	ELECTRICAL DETAILS V
53	E-306	ELECTRICAL DETAILS VI
CROSS SECTIONS		
54	CSO	CROSS SECTION OVERVIEW
55	EA-X1	EAST AREA CROSS SECTIONS I
56	EA-X2	EAST AREA CROSS SECTIONS II
57	EA-X3	EAST AREA CROSS SECTIONS III
58	EA-X4	EAST AREA CROSS SECTIONS IV
59	WA-X1	WEST AREA CROSS SECTIONS I
60	WA-X2	WEST AREA CROSS SECTIONS II
61	WA-X3	WEST AREA CROSS SECTIONS III
62	WA-X4	WEST AREA CROSS SECTIONS IV
63	WA-X5	WEST AREA CROSS SECTIONS V
64	WA-X6	WEST AREA CROSS SECTIONS VI
65	SA-X1	SOUTH AREA CROSS SECTIONS I
66	SA-X2	SOUTH AREA CROSS SECTIONS II
67	SA-X3	SOUTH AREA CROSS SECTIONS III

68	SA-X4	SOUTH AREA CROSS SECTIONS IV
69	SA-X5	SOUTH AREA CROSS SECTIONS V
70	SA-X6	SOUTH AREA CROSS SECTIONS VI
71	AR-X1	SOUTHWEST VEHICLE ACCESS ROAD CROSS SECTIONS I
72	AR-X2	SOUTHWEST VEHICLE ACCESS ROAD CROSS SECTIONS II
73	AR-X3	SOUTHWEST VEHICLE ACCESS ROAD CROSS SECTIONS III
74	RW-01	RAINWATER HARVESTING SYSTEM ACCESS CROSS SECTIONS I
75	RW-02	RAINWATER HARVESTING SYSTEM ACCESS CROSS SECTIONS II
76	RW-03	RAINWATER HARVESTING SYSTEM ACCESS CROSS SECTIONS III

GENERAL NOTES

- THE CONTRACTOR SHALL NOTIFY ALL UTILITY COMPANIES 48 HOURS BEFORE WORK IS STARTED TO VERIFY UTILITY LOCATIONS (DIGTESS 1-800-344-8377).
- THE CONTRACTOR SHALL NOTIFY ADDISON AIRPORT OPERATIONS AND THE LOCAL FAA OFFICE (FAA 972 615-2060) 48 HOURS IN ADVANCE OF CONSTRUCTION ACTIVITY TO ALLOW SUFFICIENT TIME FOR COORDINATION OF NOTAMS AND TO LOCATE AND MARK EXISTING FIELD CABLES AND TO AVOID UNSCHEDULED FACILITY OUTAGES. THE CONTRACTOR SHALL PROVIDE 35 DAYS NOTICE TO FAA PRIOR TO BEGINNING CONSTRUCTION. THE CONTRACTOR SHALL PROVIDE CONSTRUCTION SCHEDULE TO FAA.
- THE CONTRACTOR SHALL COMPLETE ALL WORK IN ACCORDANCE WITH THE FAA ADVISORY CIRCULAR 150/5370-2F, OR CURRENT VERSION, "OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION".
- THE CONTRACTOR'S STAGING AREA FOR OFFICE, STOCKPILE, EQUIPMENT, ENGINEER'S OFFICE, MATERIALS STORAGE AND EMPLOYEE PARKING SHALL BE NO CLOSER THAN 25 FEET FROM ANY FENCE LINE. ADDISON OPERATIONS SHALL APPROVE THE EXACT LOCATION OF THE STAGING AREA PRIOR TO ITS USE. THE SUGGESTED LOCATION IS SHOWN, OTHERS PROPOSED MAY BE ACCEPTABLE.
- THE CONTRACTOR SHALL MAINTAIN ALL EXISTING ACCESS AND HAUL ROADS OUTSIDE THE LIMITS OF CONSTRUCTION DURING CONSTRUCTION AND SHALL RESTORE THE ROADS TO A CONDITION EQUAL TO OR BETTER THAN ITS ORIGINAL CONDITION AT NO ADDITIONAL COST TO THE OWNER. THE LOCATION OF ANY ADDITIONAL HAUL ROADS DESIRED BY THE CONTRACTOR IS SUBJECT TO THE APPROVAL OF THE AIRPORT AND ENGINEER.
- THE CONTRACTOR IS RESPONSIBLE FOR CONSTRUCTING AND MAINTAINING TEMPORARY ACCESS AND/OR HAUL ROADS WHERE NECESSARY TO THE CONSTRUCTION LIMITS. THE CONTRACTOR SHALL COMPLETELY REMOVE THE TEMPORARY HAUL ROADS SHOWN ON THE PHASING PLANS UPON COMPLETION OF THE PROJECT AND SHALL RESTORE THE GROUND SURFACE AND TURF IN THE AREA TO ITS CONDITION PRIOR TO THIS CONSTRUCTION.
- DURING MATERIAL DELIVERY / PAVING OPERATIONS, THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING AND MAINTAINING TRAFFIC CONTROL. TRAFFIC CONTROL SHALL BE INCIDENTAL TO THE TOTAL PROJECT.
- ALL EMPLOYEES OF THE CONTRACTOR SHALL ENTER AND EXIT THE WORK SITE AT THE DESIGNATED CONTRACTOR'S ACCESS GATE (AG). AN ADEQUATE SIGN SHALL BE PROVIDED DESIGNATING THIS GATE LOCATION AS THE "CONSTRUCTION EMPLOYEE ENTRANCE". MINIMUM REQUIREMENTS FOR AN ACCESS GATE ARE AS FOLLOWS:
 - ALL VEHICLES MUST STOP PRIOR TO ENTERING THE AIRPORT. IF A GATE GUARD IS USED, THEY MUST WAIT FOR THE GATE GUARD TO SIGNAL THEM TO PROCEED. ONLY AUTHORIZED CONTRACTORS, FAA PERSONNEL, AIRPORT PERSONNEL, AND PROJECT ENGINEERS WILL BE ALLOWED ACCESS. THE CONTRACTOR WILL FURNISH TRAINING AND WRITTEN PROCEDURES TO THE GATE GUARD THAT MUST BE FOLLOWED DURING THE PROJECT.
 - DELIVERY VEHICLES FOR THE CONTRACTOR NEED TO CHECK IN AT THE GATE. THE CONTRACTOR MUST MAINTAIN POSITIVE ESCORT CONTROL OF ALL DELIVERY VEHICLES WHILE ON SITE.
 - THE GATE GUARD SHALL BE EQUIPPED WITH A TELEPHONE TO CONTACT AIRPORT OPERATIONS IF ANY UNAUTHORIZED VEHICLE ATTEMPTS TO ENTER THE AIRPORT AIR OPERATIONS AREA.
 - A GATE GUARD IS REQUIRED WHEN THE GATE IS UNLOCKED. THE GATE MAY BE SECURED (CLOSED AND LOCKED) AFTER EACH VEHICLE IN LIEU OF USING A GATE GUARD. THE CONTRACTOR SHALL PROVIDE LOCKS ON ACCESS GATES.
 - ANY AND ALL FINES THAT MAY BE LEVIED ON THE AIRPORT FOR A SECURITY VIOLATION IN CONNECTION WITH THE ACCESS GATE OR THE CONTRACTOR'S ACTIVITIES SHALL BE PAID BY THE CONTRACTOR. THE FAA MAY ASSESS A FINE DEPENDING ON THE SERIOUSNESS OF THE INFRACTION.
 - THE CONTRACTOR SHALL AT ALL TIMES ENSURE AGAINST UNAUTHORIZED ACCESS TO THE AIRFIELD.
 - PRIVATE AND COMPANY VEHICLES OPERATING WITHIN THE AIRCRAFT OPERATION AREA (AOA) MUST HAVE A COMPANY LOGO / IDENTIFICATION ON BOTH SIDES OF THE VEHICLE. THE CONTRACTOR'S EMPLOYEES' VEHICLES PARKED IN ANY OF THE CONTRACTOR'S STAGING AREA AND NOT USED FOR CONSTRUCTION PURPOSES DO NOT REQUIRE THIS IDENTIFICATION. SIGNS AS DESCRIBED ABOVE ARE REQUIRED ON PRIVATE VEHICLES OPERATED IN AREAS OTHER THAN THE STAGING AREA, DIRECT ACCESS ROUTES TO AND FROM THE STAGING AREA AND WITHIN THE CONSTRUCTION WORK LIMITS.

9. CONSTRUCTION WORK LIMITS ARE AS SHOWN ON THE PLANS. ANY AND ALL WORK CONDUCTED OUTSIDE THE CONSTRUCTION LIMITS, EXCEPT FOR MAINTENANCE ON BARRICADES SHALL BE ACCOMPLISHED WITH THE USE OF AN AIRPORT ESCORT. THE CONTRACTOR WILL PROVIDE AN ESCORT WITH A MINIMUM NOTICE OF TWO WORKING DAYS. NO WORK OR TRAVEL WILL BE PERMITTED OUTSIDE THE CONSTRUCTION LIMITS SHOWN WITHOUT PRIOR APPROVAL BY AIRPORT OPERATIONS AND AN AUTHORIZED ESCORT. AIRPORT OPERATIONS WILL NEED TO KEEP OPEN VARIOUS TAXIWAYS ADJACENT OR IN THE PROXIMITY OF OR CROSSING THE CONSTRUCTION AREA. THE WORK SHALL BE COORDINATED WITH AIRPORT OPERATIONS. NO WORK IS PERMITTED NOR ARE OPEN EXCAVATIONS, STORED MATERIALS, STOCKPILES OR EQUIPMENT ALLOWED OUTSIDE OF THE WORK AREA AS SHOWN IN THE PLANS WITHOUT PRIOR COORDINATION WITH AIRPORT OPERATIONS.

10. THE CONTRACTOR'S ACCESS TO THE AIRFIELD IS LIMITED TO THE LOCATIONS AS SHOWN ON THE PLANS. ACCESS FROM THE GATE TO THE STAGING, STORAGE AND WORK AREAS SHALL BE CONFINED TO THE ROUTES SHOWN AND WITHIN THE WORK AREA LIMITS. ACCESS VIA ANY OTHER ROUTES OR GATES WILL REQUIRE PRIOR WRITTEN APPROVAL BY AIRPORT OPERATIONS.

11. ANY TEMPORARY FACILITIES SHALL BE COMPLETELY REMOVED FROM THE SITE AT THE COMPLETION OF THE PROJECT AND THE SITE RESTORED TO ITS ORIGINAL CONDITION.

12. CONSTRUCTION LIMITS - ALL CONTRACTOR VEHICLES AND TRAFFIC (UNLESS OTHERWISE AUTHORIZED) SHALL REMAIN WITHIN THE DESIGNATED CONSTRUCTION LIMITS OR HAUL ROUTES. CONSTRUCTION, STORAGE AND STOCKPILING LIMITS MUST BE APPROVED BY THE AIRPORT OR ENGINEER.

13. FUEL, DIESEL FUEL, OR OTHER CONTAMINANTS SHALL NOT BE ALLOWED TO ENTER THE STORM SEWER SYSTEM. IF, IN THE EVENT SUCH CONTAMINANTS DO ENTER THE STORM SEWER SYSTEM OR GROUND WATER, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE AIRPORT OF THE SPILL. THE CONTRACTOR WILL BE RESPONSIBLE FOR ALL COSTS INCURRED FOR CLEANUP OF CONTAMINATED AREAS ON AND OFF AIRPORT PROPERTY.

14. CAUTION SHALL BE TAKEN BY THE CONTRACTOR IN PREVENTING ANY DUST OR MUD WHICH MAY BECOME A HAZARD TO AIR AND GROUND OPERATIONS. THE CONTRACTOR SHALL CONTROL DUST AND MUD AT ALL TIMES AND MAY REQUIRE FULL TIME OPERATION WATER TRUCKS OR SWEEPERS. IF, IN THE OPINION OF THE AIRPORT OR THE ENGINEER, DUST OR MUD IS NOT BEING ADEQUATELY CONTROLLED THEY MAY SUSPEND WORK AND MAKE NECESSARY ARRANGEMENTS FOR DUST OR MUD CONTROL. THE COSTS THEREFORE SHALL BE DEDUCTED FROM THE PROGRESS PAYMENTS DUE THE CONTRACTOR.

15. CONTRACTOR SHALL TAKE THE NECESSARY STEPS TO OBTAIN DRIVER'S TRAINING FOR CONTRACTOR EMPLOYEES PRIOR TO ENTERING THE AIR OPERATIONS AREA.

16. MATERIAL / TOPSOIL STOCKPILES SHALL BE AT LOCATIONS APPROVED BY THE AIRPORT. MAXIMUM STOCKPILE HEIGHT IS 20 FEET.

17. THE CONTRACTOR WILL ISSUE AIRPORT APPROVED LAMINATED SAFETY CARDS SHOWING THE ACCESS GATE LOCATION, CONSTRUCTION AREA, ACCESS / HAUL ROUTE, CLOSED PAVEMENTS AND RUNWAY SAFETY AREAS AND/OR ANY OTHER PERTINENT INFORMATION. THESE CARDS WILL BE SUPPLIED BY THE CONTRACTOR. THESE SAFETY CARDS WILL BE SPECIFIC TO EACH INTERMEDIATE PHASE OF THE PROJECT. THE CONTRACTOR IS RESPONSIBLE FOR DISTRIBUTING AND COLLECTING THESE CARDS TO ALL OF THEIR EMPLOYEES, SUBCONTRACTORS AND SUPPLIER DELIVERY DRIVERS WHO WILL ENTER THE AOA. THE CONTRACTOR IS REQUIRED TO BRIEF ALL EMPLOYEES OR SUBCONTRACTORS ON AIRPORT SECURITY AND SAFETY PRIOR TO DISTRIBUTING THE SAFETY CARDS. BEFORE A NEW EMPLOYEE, SUBCONTRACTOR OR SUPPLIER BEGINS WORKING ON THE AIRPORT THE CONTRACTOR IS RESPONSIBLE TO MAKE SURE THEY ARE AWARE OF AIRPORT OPERATIONS, AS WELL AS GIVE THEM A TOUR OF THE PROJECT SITE, SHOWING THEM THE SPECIFIC WORK AREA, HAUL ROUTE AND THE MOVEMENT AREA THAT IS NOT TO ENTERED WITHOUT AIRPORT APPROVAL.

18. ALL EMPLOYEES OF THE CONTRACTOR OR SUBCONTRACTORS SHALL RECEIVE VEHICLE OPERATOR/PEDESTRIAN TRAINING FROM THE PROJECT SUPERINTENDENT. ALL EMPLOYEES SHALL RECEIVE NEW TRAINING WHEN MOVED TO DIFFERENT WORK AREAS OR PHASES OF THE PROJECT. A CONTRACTOR VEHICLE OPERATOR/PEDESTRIAN TRAINING CHECKLIST IS PROVIDED IN THE CONTRACT SPECIFICATIONS. THE CONTRACTOR'S PROJECT SUPERINTENDENT SHALL MAINTAIN THE COMPLETED CHECKLIST AND PROVIDE TO AIRPORT PERSONNEL FOR INSPECTION UPON THEIR REQUEST.

19. IF FOR ANY REASON, THE AIRPORT OR ENGINEER FEELS THAT SAFETY IS NOT BEING ADEQUATELY MAINTAINED, THEY MAY SUSPEND WORK UNTIL THE SAFETY ISSUE IS RESOLVED. THE COSTS THE AIRPORT, ENGINEER, TXDOT AND FAA INCUR TO MITIGATE THE SAFETY ISSUE THEREFORE SHALL BE DEDUCTED FROM THE PROGRESS PAYMENTS DUE THE CONTRACTOR.

20. IN THE EVENT THAT UNANTICIPATED ARCHEOLOGICAL DEPOSITS ARE ENCOUNTERED DURING CONSTRUCTION, WORK IN THE IMMEDIATE AREA WILL CEASE AND THE TXDOT ENGINEER WILL BE NOTIFIED.

21. IN THE EVENT THAT UNANTICIPATED HAZARDOUS MATERIALS ARE ENCOUNTERED DURING CONSTRUCTION, WORK IN THE IMMEDIATE AREA WILL CEASE AND THE TXDOT PROJECT MANAGER WILL BE NOTIFIED.

22. STOCKPILES AND STAGING AREAS WILL NOT BE PLACED WITHIN ANY WATER OF THE UNITED STATES, INCLUDING WETLANDS.

23. HAZARDOUS WASTE: ALL SPILLS MUST BE REPORTED IMMEDIATELY TO THE TXDOT ENGINEER.

