

SHEET NO.	INDEX OF SHEETS
1	COVER SHEET / LOCATION MAP
2	SHEET INDEX/QUANTITIES
3	PROJECT LAYOUT/SURVEY CONTROL
4-5	GENERAL NOTES
6	PROJECT PHASING PLAN
7	TYPICAL SECTIONS
8	CONSTRUCTION PHASING PLAN-PHASE I
9	CONSTRUCTION PHASING PLAN-PHASE II
10	CONSTRUCTION PHASING PLAN-PHASE III
11-12	DEMOLITION AND BORING PLAN
13-14	PAVING AND JOINT LAYOUT PLAN
15	GRADING PLAN
16-17	JOINT ELEVATIONS
18-19	DRAINAGE AND SW3P PLAN
20-21	PAVEMENT MARKING PLAN
22	BARRICADE DETAILS
23	PAVING DETAILS
24	PAVING JOINT DETAILS
25	DRAINAGE DETAILS
26	PAVEMENT MARKING DETAILS
27	STORM WATER POLLUTION PREVENTION NOTES
28	STORM WATER POLLUTION PREVENTION DETAILS

DESCRIPTION - TAXIWAY SIERRA BASE BID				
ITEM	SPEC	DESCRIPTION	QUANTITY	UNIT
1	500-2001 (TXDOT)	MOBILIZATION	1	LS
2	TS-005	MAINTENANCE OF TRAFFIC	1	LS
3	506-2001 (TXDOT)	STORMWATER POLLUTION PREVENTION PLAN AND IMPLEMENTATION	1	LS
4	506-2034 (TXDOT)	SILT FENCE	120	LF
5	506-2036 (TXDOT)	BIODEGRADABLE EROSION CONTROL LOGS (18")	225	LF
6	247-2064 (TXDOT)	6" FLEXIBLE BASE (TYPE D GRADE 4)	4,500	SY
7	202.5 (NCTCOG)	BERMUDA (NON-HYBRID) W/COMPOST	2,500	SY
8	203 (NCTCOG)	REMOVE AND RELOCATE FIRE HYDRANT ASSEMBLY (COMPLETE IN PLACE)	1	EA
9	203.1 (NCTCOG)	REMOVAL OF BITUMINOUS PAVEMENTS AND BASE COURSE	4,200	SY
10	203.1 (NCTCOG)	REMOVAL OF CONCRETE PAVEMENT (7"-8" DEPTH)	75	SY
11	203.1 (NCTCOG)	REMOVAL OF STORM DRAIN	326	LF
12	203.4 (NCTCOG)	UNCLASSIFIED EXCAVATION	100	CY
13	340-2138 (TXDOT)	3" D-GR HMA, TYPE D PG 76-22 (BITUMINOUS SURFACE COURSE)	26	TON
14	302 (NCTCOG)	BITUMINOUS PRIME COAT	165	GAL
15	302 (NCTCOG)	BITUMINOUS TACK COAT	125	GAL
16	303 (NCTCOG)	10 INCH PCC PAVEMENT, NON-REINFORCED	2,350	SY
17	303 (NCTCOG)	10 INCH PCC PAVEMENT, REINFORCED	485	SY
18	303 (NCTCOG)	10-12 INCH PCC PAVEMENT, NON-REINFORCED	580	SY
19	303 (NCTCOG)	10-12 INCH PCC PAVEMENT, REINFORCED	205	SY
20	303 (NCTCOG)	10 INCH PCCP HIGH YIELD EARLY STRENGTH PAVEMENT, NON-REINFORCED	300	SY
21	303 (NCTCOG)	10 INCH PCCP HIGH YIELD EARLY STRENGTH PAVEMENT, REINFORCED	15	SY
22	303 (NCTCOG)	10-12 INCH PCC PAVEMENT, HIGH YIELD EARLY STRENGTH, NON-REINFORCED	220	SY
23	303 (NCTCOG)	10-12 INCH PCC PAVEMENT, HIGH YIELD EARLY STRENGTH, REINFORCED	3	SY
24	501.6 (NCTCOG)	12 INCH RCP, C76, CLASS IV, INCL EMBEDMENT	107	LF
25	501.6 (NCTCOG)	15 INCH RCP, C76, CLASS IV, INCL EMBEDMENT	446	LF
26	501.6 (NCTCOG)	18 INCH CLASS III TEMPORARY STORM DRAIN	53	LF
27	502 (NCTCOG)	15 INCH SLOPED END TREATMENT - AIRPORT RATED	8	EA
28	502 (NCTCOG)	12 INCH CLASS IV 45° BEND	1	EA
29	502 (NCTCOG)	PIPE TO PIPE CONNECTION (PIPE COLLAR)	1	EA
30	502.12 (NCTCOG)	#20 CATCH BASIN (2FT DEPTH) - AIRPORT RATED (HANSON OR APPROVED EQUAL)	2	EA
31	504 (NCTCOG)	STORM DRAIN BACKFILL - CLASS B	90	CY
32	804 (NCTCOG)	TEMPORARY PAVMENT MARKINGS	525	SF
33	804 (NCTCOG)	PAVEMENT MARKINGS, NON REFLECTIVE, BLACK	1,800	SF
34	804 (NCTCOG)	PAVEMENT MARKINGS TYPE I, REFLECTIVE, YELLOW	400	SF
35	804 (NCTCOG)	PAVEMENT MARKINGS, NON REFLECTIVE, YELLOW	500	SF
36	804 (NCTCOG)	TWO WAY BLUE REFLECTIVE LED MARKER WITH EPOXY INSTALLED	36	EA
37	804 (NCTCOG)	TEMPORARY PAVEMENT REPAIR	162	SY
38	502 (NCTCOG)	6 INCH CONCRETE FLUME	175	SY
39				
40		CONSTRUCTION CONTINGENCY	1	LS


AS BUILT PLANS



13-JUN-2008 10:52 C:\V45601\CadSheets\Twsqt01.dgn

NO.	DATE	REVISION	APPROV.	NO.	DATE	REVISION	APPROV.
1	11/7/07	MODIFIED QUANTITIES	JSN				

THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY J.S. NICEWANDER, P.E. 87843 ON NOVEMBER 7, 2007.



**HNTB** Corporation  
The HNTB Companies  
Engineers Architects Planners

DESIGN CHECK: JSN, MAH  
DRAWN CHECK: CCH, MAH  
DATE: SEPTEMBER 2007  
SCALE:

PROJECT NO. 45601



TOWN OF ADDISON		SHEET 2 OF 28
TAXIWAY SIERRA		
SHEET INDEX/QUANTITIES		2
TOWN OF ADDISON, TEXAS		QT-1