DWG No. CC5-0005

BROADWAY STREET

DETAIL B CC1-0001 TBM-1

DETAIL 01 CC1-0001

S3.21

EXISTING RAIL LINE

Bicycle Parking S3.56

One Way S3.17

S3.11

S3.21

SPEED LIMIT 10

STOP RI-1

SCALE (IN FEET) 0 20 40 80

One Way S3.17

Authorized Personnel Only S3.53

Bicycle Parking S3.57

FF=633.50

PED. CROSSWALK PAINT STRIPES (TYP)

4" WHITE PAINT STRIPES (TYP)

DETAIL 01 AC9-0001

QUORUM DRIVE

Except Buses S3.12

S3.11

STOP S3.10

4" WHITE PAINT STRIPES 12" SPACE APART (TYP)

DETAIL 01 CC6-0002

6" YELLOW PAINT STRIPE

6" YELLOW PAINT STRIPE

ARAPAHO RCAD ( REALIGNED ROADWAY BY OTHERS )

Passenger Load/Unload S3.20

Passenger Load/Unload S3.20

STOP RI-1

TBM-2

Except Buses S3.12

STOP S3.10

SPEED LIMIT 10

STOP RI-1

ARAPAHO ROAD

NOTE:
1. REFER TO SPEC. SECTION 10441 FOR DETAILS RELATED TO TRAIL BLAZER (PATHFINDER) SIGNS.

2. CONTRACTOR SHALL COORDINATE WITH THE CONTRACTING OFFICER FOR PLACEMENT OF DIRECTIONAL ARROWS AND 12" STOP BARS AT ALL DRIVEWAYS.

STATE OF TEXAS JACK L. MOSELEY 34089 REGISTERED PROFESSIONAL ENGINEER

THE SEAL OF JACK L. MOSELEY P.E. No. 34089 SHOWN HEREON APPLIES ONLY TO THE CHANGES AND/OR MODIFICATIONS TO THE DESIGN INDICATED FOR REVISION No. 1 AS SHOWN IN CLOUDED AREAS.

CE#014 SA#010

Record Technical Drawings

Tom Knox President

ROADWAY

7-7-99

| REV | DATE | DESCRIPTION | BY | ENG | CHK | APP |
|---|---|---|---|---|---|---|
| 1 | 2/8/99 | ADDED BICYCLE RACK | DC | JCM | TJS | JLM |
| 2 | | | | | | |
| 3 | | | | | | |
| 4 | | | | | | |
| 5 | | | | | | |

ORIGINAL SEAL(S) RESIDE IN DART FOR THE FOLLOWING REVISION(S):

REV 01 SEALED BY CHRISTOPHER L. MILLER LANDSCAPE ARCHITECT No. 682

WENDY LOPEZ & ASSOC.
LOCKWOOD, ANDREWS & NEWNAM
THE SWA GROUP
GERARD & ASSOCIATES
ZAXON

WENDY LOPEZ & ASSOCIATES, INC.
ENGINEERING • SURVEYING • CONSTRUCTION SERVICES
1825 MARKET CENTER BLVD - SUITE 510
DALLAS, TEXAS 75207
(214) 746-7777

DART PROJECT

| | |
|---|---|
| SCALE | 1"=40' |
| DRAWN | D. KRUCIAK |
| DESIGNED | P. ZHAO |
| CHECKED | V. STEVENS |
| IN CHARGE | V. STEVENS |
| DATE | AUG. 14, 1997 |

CONTRACT SHEET No. 26 OF 95

# ADDISON TRANSIT CENTER

## PAVEMENT MARKING & SIGNING PLAN

| CONTRACT | DWG No. | REV |
|---|---|---|
| C-97000136 | CC5-0005 | 1 |


PRF ROTATION=270.000000, F:\TRANSIT CENTERS\ABTC\abtcwrl.050, 32
Tue Feb 8 14:52:04 1999
\plot\tables\lgdarf:\prf\cadd\abtccp05.prf
DART CADD
*no ref logical*, *no ref levels*
F:\TRANSIT CENTERS\ABTC\abtcprl.040, 1-11,13-45,47-49,51-60
F:\TRANSIT CENTERS\ABTC\abtctpr1.040, 3,4,6,8-10,13-16,18-20,23-28,33-34,38-39,53-58
F:\TRANSIT CENTERS\ABTC\abtcutrl.040, 1-62
F:\TRANSIT CENTERS\ABTC\basehz.dgn, 2,4-40,43-61
F:\TRANSIT CENTERS\ABTC\abtcborl.001, 1-6,15-22,24-31,35-62
F:\TRANSIT CENTERS\ABTC\abtcvdan\abtccp05.040