

SUMMARY OF ESTIMATED QUANTITIES

BID ITEM NUMBER	501	502	503	504	505	506	507	508	509	510
TXDOT SPEC NUMBER	416			420				422	425	428
BRIDGE ELEMENT	DRILLED SHAFTS			CLASS F CONC 5000 PSI				REINFORCED CONCRETE SLAB (CLASS "S")	PRESTRESSED CONCRETE MEMBER U54	CONCRETE SURFACE TREATMENT
	48" LF	60" LF	96" LF	ABUT CY	BENT 2-8 & 11-14 CY	BENT 9 & 10 CY	DIAPHRAGMS CY	SF	LF	SY
TOTAL	147	312	365	79.3	1,037.5	505.2	99.4	83,680	6,089	9,298

BID ITEM NUMBER	511	512	513	514	515	516	517	518	519	520
TXDOT SPEC NUMBER	442	442		450	450	450	454	534		
BRIDGE ELEMENT	STRUCT STL (ARCH)	STRUCT STL (STINGER)	STRUCT STRAND (2 1/2") TECH SPEC SSH	PEDESTRIAN RAIL	RAIL T4 (S) (MOD) A	RAIL T4 (S) (MOD) B	SEALED EXPANSION JOINT 4" (MOD)	STRUCTURAL APPROACH SLABS	"ADDISON" LOGO FORM LINER	STANDARD 24" x 24" MONUMENT PLAQUE
	LB	LB	LS	LF	LF	LF	LF	CY	LS	EA
TOTAL	175,000	⚠ 12,701	1	1,604	1,577	1,576	363.7	73.6	1	2



				245
1	06/01/04	ADDENDUM CHANGES		CRH
NO.	DATE	REVISION		APPROV.
GREYSTONE CENTRE 3000 LBJ FREEWAY, SUITE 1300 DALLAS, TX 75234				
ARAPAHO ROAD - PHASE III SURVEYOR BOULEVARD TO ADDISON ROAD				
ESTIMATED QUANTITIES				
TOWN OF ADDISON, TEXAS				
Design	Drawn	DATE	SCALE	PROJECT NO. SHEET NO.
Check	Check	05-07-04		25768 BR-7