



- SITE UTILITY GENERAL NOTES**
- UNLESS OTHERWISE NOTED, ALL MATERIALS AND CONSTRUCTION WILL CONFORM TO TOWN OF ADDISON STANDARD SPECIFICATIONS.
 - THE SITE UTILITY CONTRACTOR SHALL MAKE ARRANGEMENTS WITH THE APPROPRIATE UTILITY AUTHORITY FOR CONNECTION TO THE EXISTING MAINS.
 - ALL WATER LINES SHALL HAVE A MINIMUM COVER OF 48" ABOVE TOP OF PIPE.
 - CONTRACTOR SHALL INCLUDE IN HIS BID TO ADJUST LOCATION OF PROPOSED WATER LINES AS REQUIRED TO AVOID CONFLICTS WITH STORM SEWER OR OTHER UTILITIES.
 - THRUST BLOCKS SHALL BE PROVIDED AT ALL TEES, ELBOWS, AND BENDS OF SUFFICIENT SIZE TO COMPLY WITH MINIMUM STANDARDS OF N.F.P.A. - 24 FOR EXISTING SOIL CONDITIONS. GATE VALVES SHALL BE CITY APPROVED AND WILL AT A MINIMUM BE RESILIENT SEAT CONFORMING TO AWWA C-509.
 - SHOULD LATENT SOIL CONDITIONS NECESSITATE, CONTRACTOR SHALL INSTALL SPECIAL SUPPORTS FOR PIPING AND/OR APPURTENANCES INCLUDING THE REMOVAL OF UNSUITABLE MATERIAL AND BACKFILLING WITH GRAVEL OR OTHER MATERIAL. CONTRACTOR SHALL PERFORM ANY SUCH WORK AS DIRECTED BY THE ENGINEER. COSTS SHALL BE INCLUDED IN THE BASE BID.
 - ALL MATERIALS SHALL BE U.L. LISTED AND FACTORY MUTUAL APPROVED UNLESS DIRECTED OTHERWISE BY THE ENGINEER.
 - THE EXISTING UTILITY FACILITIES AND LOCATIONS SHOWN ON THE DRAWINGS ARE TAKEN FROM READILY AVAILABLE INFORMATION. THE ACTUAL LOCATIONS OF THE UTILITY FACILITIES MAY VARY SOMEWHAT FROM THE LOCATIONS SHOWN AND THERE MAY BE UTILITY FACILITIES EXISTING THAT ARE NOT SHOWN OR INDICATED ON THE DRAWINGS. THE SITE UTILITY CONTRACTOR SHALL CONTACT ALL AGENCIES WITH UTILITY FACILITIES IN THE VICINITY OF THE WORK AND SHALL LOCATE ALL UNDERGROUND FACILITIES BEFORE BEGINNING WORK. THE CONTRACTOR SHALL PROTECT ALL UTILITY FACILITIES AND REPAIR ANY DAMAGES RESULTING FROM THEIR WORK, IN CONFORMANCE WITH THE CONTRACT DOCUMENTS AND SPECIFICATIONS AND RELOCATED IF REQUIRED.
 - CONNECTIONS TO EXISTING WATER LINE SHALL BE PERFORMED BY CONTRACTOR. THE SITE UTILITY CONTRACTOR SHALL COORDINATE WITH TOWN OF ADDISON AND PAY FOR CONNECTIONS.
 - CONTRACTOR IS RESPONSIBLE FOR OBTAINING & PAYING FOR ALL PERMITS REQUIRED TO COMPLETE ITS WORK.
 - ALL WORK TO CONFORM TO STATE AND LOCAL PLUMBING AND BACKFLOW PREVENTION CODES AND THE SPECIFICATIONS OF THE TOWN OF ADDISON UTILITY.
 - ALL WATER LINES 3" AND LARGER MUST BE DISINFECTED. SAMPLES FROM THREE CONSECUTIVE DAYS MUST BE TAKEN TO AN APPROVED TESTING LAB. AND THE LAB ANALYSIS REPORTS MUST BE SUBMITTED TO THE WATER ENGINEERING DEPARTMENT SHOWING THAT THE SAMPLES HAVE PASSED THE TESTS FOR THREE CONSECUTIVE DAYS. VACUUM BEAKERS MUST BE INSTALLED ON ALL EXISTING OR PROPOSED HOSE BIBBS, MOP/SERVICE SINKS, WALL/YARD HYDRANTS.
 - BACKFLOW DEVICE MUST BE TESTED BY A CROSS-CONNECTION CONTROL DEVICE INSPECTOR AT THE TIME OF INSTALLATION AND REPORT SUBMITTED TO WATER ENGINEERING BEFORE CERTIFICATE OF COMPLIANCE IS RELEASED.

AS BUILT

Winkelmann & Associates Inc. hereby certifies that this plan, to the best of our knowledge is "As Built." All modifications to the original approved construction documents have been made as per information provided by the contractor. Winkelmann & Associates, Inc. does not certify as to the correctness or quality of construction as no field inspection was performed.

[Signature] DATE: 7-10-95
WINKELMANN & ASSOCIATES, INC.

BENCH MARK:
"0" cut top of curb at the curb return east side of Commercial Drive and Beltline Road.
Elev = 582.16

• MIN. FINISH FLOOR ELEVATION ARE FROM REPORT PREPARED BY O'BRIEN ENGINEERS DATED: 7/7/94

APPROV.	REVISION	DATE	NO.

Winkelmann & Associates, Inc.
CONSULTING CIVIL ENGINEERS & SURVEYORS
2800 BELLEVILLE ROAD, SUITE 200
IRVINE, TEXAS 75339
(512) 892-7000
(512) 892-7006 FAX

T.L. CHEWNETH SURVEY, ABSTRACT NO. 923
D. MEYERS SURVEY, ABSTRACT NO. 923
CITY OF ADDISON, DALLAS COUNTY, TEXAS

OWNER:
RED ROBIN RESTAURANT INTERNATIONAL
28 EXECUTIVE PARK, SUITE 200
IRVINE, CA 92714

UTILITY PLAN
BLOCK 3, BELTLINE MARSH BUSINESS PARK
ADDISON, TEXAS

Scale: 1" = 30' Date: 7/16/95
Designed By: TL
Drawn By: TL
Checked By: MC
File: 0930JUL
Project No.: 0930J01

SHEET
C-7
OF
8