



TRAFFIC CONTROL NOTES:

1. Traffic control shall be maintained during the construction of improvements along Beltline as provided for in Part VI "Construction and Maintenance" section of the "Texas Manual on Uniform Traffic Control Devices" by the State of Texas Department of Highways and Public Transportation.
2. Construction shall be performed from start to finish on either the median side or the outside lane (one side at a time). This is to minimize the effect of construction on any one traffic lane at a time.
3. Once begun, construction on either side shall be conducted as expeditiously as possible in order to complete the work.
4. Construction to Beltline shall be performed between the hours of 9:30 AM and 3:30 PM, Monday through Saturday. Sunday hours would be limited to daylight. The traffic lane effected by construction may be fully closed, utilizing the appropriate temporary devices, during these hours and must be re-opened during non-construction hours. When an edge of driving lane is a hazard during non-construction hours it shall be lined with flashing vertical panels spaced no greater than 40 feet apart.

TRAFFIC CONTROL PLAN

WAL-MART
SAM'S CLUB
 BELTLINE + MIDWAY
 ADDISON, TEXAS

DUNAWAY ASSOCIATES, Inc.
 ENGINEERS - PLANNERS - ARCHITECTS
 8001 WERSHALL CIRCLE, SUITE 1000
 FORT WORTH, TEXAS 76114
 PHONE (817) 355-1111 FAX (817) 355-7487

JOB No. 9102800
 DESIGNED BY: T.S.G.
 CHECKED BY: T.O.H.
 DATE: JAN. 10, 1992
 SCALE: 1" = 50'-0"
 SHEET 20 OF 24 SHEETS



DATE: 3/3/92

No.	DATE	REVISION DESCRIPTION