


- NOTES:**
- ALL ROOF TRUSSES ARE SPACED AT 24" O.C. U.N.O. COORDINATE HEIGHT AND CONFIGURATIONS WITH ARCHITECTURAL DRAWINGS.
 - ALL HORIZONTAL FRAMING LUMBER TO BE #2 KD SYP UNLESS NOTED OTHERWISE, OR LUMBER WITH EQUIVALENT OR BETTER STRUCTURAL PROPERTIES. OTHER LUMBER SPECIES MUST BE APPROVED IN WRITING BY THE ENGINEER.
 - ALL EXTERIOR WALLS SHALL BE LOAD BEARING.
 - ALL WOOD BEAMS ARE FLUSH BEAMS OR LOAD BEARING HEADERS UNLESS NOTED OTHERWISE (DB = DROP BEAM, PB = POCKET BEAM).
 - REFERENCE SHEET S1.01 FOR STRUCTURAL NOTES AND SCHEDULES.

- SHEARWALL NOTES**
- ALL SHEARWALLS INDICATED ON PLAN ARE LOCATED AT FLOOR BELOW.
 - ALL SHEARWALLS INDICATED ON PLAN ARE TYPE A TYPICAL UNLESS NOTED OTHERWISE. REFERENCE SHEARWALL SCHEDULE 4/S1.01.

LEGEND


X = SHEARWALL REFERENCE SHEARWALL NOTES THIS SHEET, AND SHEARWALL SCHEDULE 4/S1.01

1 ROOF FRAMING PLAN
SCALE: 1/4"=1'-0"



WOOD FRAMING SCHEDULE		
WOOD BEAM & HEADER		STUD / COLUMN SUPPORT
MARK	SIZE	MINIMUM SIZE
(A)	2-2x8	2-2x STUDS
(B)	2-2x10	2-2x STUDS
(C)	3-2x8	3-2x STUDS
(D)	3-2x10	3-2x STUDS
(E)	2-2x12	3-2x STUDS
(F)	3-2x12	3-2x STUDS

FILE INFO: 8018s202.dwg 1=48 09/25/00 09:13



THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY R. TRENT PERKINS, P.E. 84264 ON 27 JULY 00

THIS DOCUMENT IS THE RENDERING OF A PROFESSIONAL SERVICE, THE ESSENCE OF WHICH IS THE PROVIDING OF ADVICE, JUDGEMENT, OPINION, OR SIMILAR PROFESSIONAL SKILL.

P P O
Parkin • Perkins • Olsen
Consulting Engineering, Inc.
12970 Pandora Drive Suite 200
Dallas, Texas 75238
Tel 214.221.2220 Fax 214.221.2252
Project No. 38018

R-F
ROGERS - FORD
ARCHITECTURE - INTERIOR DESIGN
2616 THOMAS AVENUE
DALLAS, TEXAS 75204
TELEPHONE (214) 971-9388
FAX (214) 971-3155

LONG STAR BANK
4650 Beltline Road
Addison, TX
Project # 1804

7-27-2000 PERMIT ISSUE
8-17-2000 ISSUE FOR BID
8-25-2000 ADDENDUM #1

S2.02

ROOF FRAMING PLAN