



LEGEND

--- Sawcut
40.00 Existing Spot Elevation
46.99 Proposed Spot Elevation

CONCRETE PAVING SECTIONS

3000 PSI Reinf. Conc. Pavement
w/ #3 @ 24" OCEW
(4" minimum thickness for sidewalk areas)
(5" minimum thickness for parking areas)

* Subgrade shall be compacted to a min. of 95% of it's maximum
Standard Proctor dry density (ASTM D-698) at a moisture
content in the range of -2% to +3% as determined by that test.

Town of Addison Benchmark 20
BM ELEVATION = 638.13'

Square cut in concrete on inlet 400 feet south of Beltline Road
on the East side of Landmark Blvd.

STATE OF TEXAS
MATTHEW P. KOSTAL
88549
LICENSED PROFESSIONAL ENGINEER

10/05/05

PLAZA AT THE QUORUM II

PAVING PLAN
TOWN OF ADDISON
DALLAS COUNTY, TEXAS
ORACLE ENGINEERING
7012 Lindsley Avenue
Dallas, Texas 75223
TEL: (214) 321-1436
FAX: (214) 881-9101

DESIGN	DRAWN	DATE	SCALE	FILE	NO.
MPK	MPK	10/2005	1"=10'	-	C4

C:\ORACLE\2005\QUORUM II\CIVIL4-PAV.DWG