



- LEGEND**
- - - Sawcut
  - 40.00 Existing Spot Elevation
  - 40.00 Proposed Spot Elevation
- CONCRETE PAVING SECTIONS**
- 3000 PSI Reinf. Conc. Pavement  
w/ #3 @ 24" OCEW  
(4" minimum thickness for sidewalk areas)  
(5" minimum thickness for parking areas)
- \* Subgrade shall be compacted to a min. of 95% of it's maximum Standard Proctor dry density (ASTM D-698) at a moisture content in the range of -2% to +3% as determined by that test.

Town of Addison Benchmark 20  
BM ELEVATION = 638.13'

Square cut in concrete on Inlet 400 feet south of Beltline Road  
on the East side of Landmark Blvd.

STATE OF TEXAS  
MATTHEW P. KOSTAL  
88549  
LICENSED PROFESSIONAL ENGINEER  
10/05/05

PLAZA AT THE QUORUM II

PAVING PLAN  
TOWN OF ADDISON  
DALLAS COUNTY, TEXAS  
ORACLE ENGINEERING  
7012 Lindsley Avenue  
Dallas, Texas 75223  
TELEPHONE (214) 321-1436  
FAX (214) 853-9381

DESIGN	DRAWN	DATE	SCALE	FILE	NO.
MPK	MPK	10/2005	1"=10'	-	C5

C:\ORACLE\2005\QUORUM II\CIVIL\5-PAV.DWG