

PLANT LEGEND

SYMBOL	SIZE	BOTANICAL NAME	COMMON NAME	QUANTITY
	2 1/2" CALIFER	ACER TRUNCATUM	SHANTING MAPLE	1
	3" CALIFER	BETULA NIGRA	RIVER BIRCH	3 - MULTI
	2 1/2" CALIFER	CERCIS C. TEXENSIS	TEXAS REDBUD	4
	3" CALIFER	JUNIPERUS VIRGINIANA	EASTERN RED CEDAR	4
	4" CALIFER	PROSOPIS GLANDULOSA	HONEY MESQUITE	2
	MATCH OAK CALIFER	QUERCUS SP.	OAK TREE	4
	1 GAL	BOULEAUX GRANA	BIDECAUS GRANA	19
	1 GAL	DWARF MAIDEN GRASS	DWARF MAIDEN GRASS	• 24" OC.
	1 GAL	STIPA TENUISSIMA	HEXAMER FEATHER GRASS	• 24" OC.
	1 GAL	LIRIODENDRON MUSCARI	LILTYURE	• 16" OC.
	1 GAL	ROSMARINUS O. PROSTRATUS	PROSTRATE ROSEMARY	• 16" OC.
	4" POTS	SAPONARIA OFFICINALIS	BOUNCING BET	• 8" OC.
	5 GAL	ACER TRUNCATUM	SHANTING MAPLE	2
	9 GAL	PINUS T. THUNDERBALD	DWARF JAPANESE BLACK PINE	5

AREA CALCULATIONS:
 CONSTRUCTION LIMITS: 23,234
 LANDSCAPE: 35,844 - 5%

PLANTING NOTES
 CONTRACTOR SHALL VERIFY LOCATION OF ALL UNDERGROUND UTILITIES AND SERVICES PRIOR TO ANY DIGGING. CONTRACTOR ASSUMES FULL RESPONSIBILITY FOR ALL DAMAGE CAUSED BY FAILURE TO DO SO.
 PLANT MAINTENANCE WORK SHALL CONSIST OF APPLYING WATER, WEEDING, FERTILIZING PER SPECIFICATIONS.
 THE ENTIRE PROJECT IS TO BE MAINTAINED FOR A PERIOD OF 60 DAYS FROM THE DATE OF COMPLETION OF THE PROJECT. CONTRACTOR SHALL BE RESPONSIBLE FOR THE MAINTENANCE OF THE LANDSCAPE ARCHITECT'S WORK THROUGHOUT THIS PERIOD.
 CONTRACTOR SHALL BE RESPONSIBLE FOR DISEASE AND PEST CONTROL DURING THE MAINTENANCE PERIOD.
 CONTRACTOR SHALL VERIFY SOIL CONDITIONS PRIOR TO PROPER LEVEL OF PLANT MATERIAL. CONTRACTOR SHALL COVER ALL EXPOSED SOIL WITH PLANT MATERIAL. CONTRACTOR SHALL COVER ALL EXPOSED SOIL WITH PLANT MATERIAL.
 CONTRACTOR TO VERIFY WITH LOCAL AGENCIES THE SOIL AMENDMENT AND FERTILIZER REQUIREMENTS. CONTRACTOR TO VERIFY WITH LOCAL AGENCIES THE SOIL AMENDMENT AND FERTILIZER REQUIREMENTS.
 ALL SHRUBS AND GROUND COVER TO BE INSTALLED 1" ABOVE BACKFILL GRADE. CONTRACTOR TO REMOVE MAJOR SETTLING OF PLANT MATERIAL.
 PLANTS CALLED OUT ON PLAN ARE CONSIDERED IN QUANTITIES EVEN IF NOT ATTACHED BY CONNECTING LINES. CALLOUTS WILL HAVE TOTAL COUNTS NOTED.
 ALL PLANTING BEDS TO RECEIVE 7" DEPTH OF FIR BARK MULCH - FOREST FLOOR OR EQUAL.
 ALL TREES WITHIN FIVE FEET (5') OF HARDSCAPE OR WALLS TO BE INSTALLED WITH A ROOT BARRIER.

