MATCH LINE SHEET 34

MATCH MARK STA. 1+40 "B"

MATCH LINE SHEET 36

MATCH MARK STA. 2+65 "A"

G.W. FISHER SURVEY ABST. 488

J. PANCOAST SURVEY ABST. 1146

PENTECO INC. ABST. NO. 1146 Pgs 218I DATE 6-28-76

ELECTRIC DATA SYSTEMS INC. # 945 ACRES ABST. 1146 Page 2 DATE 6-28-76

LOT C (NO BLOCK #)

LOT D (NO BLOCK #)

LOT E (NO BLOCK #)

LOT F (NO BLOCK #)

LOT G (No Block #)

LOT H (NO BLOCK #)

LOT I (No Block #)

LOT J (NO BLOCK #)

LINE "A"

LINE "B"

LINE "C"

LINE "D"

DALLAS PKWY

ADDISON DALLAS

N 85°30'06" W 882.99'

S 85°31'25" W 164.28'

10+41.70 CONST. STD. 4.0' DIA. MANHOLE

4+19.83 LINE "A" = 0+00 LINE "C" CONST. STD. 4.0' DIA. MANHOLE

6+18.83 LINE "A" = 0+00 LINE "B" CONST. STD. 4.0' DIA. MANHOLE

4+00 CONST. STD. 4.0' DIA. MANHOLE

4+21.09 LINE "C" = 0+00 LINE "D" CONST. STD. 4.0' DIA. MANHOLE

11+92.16 END & CAP

7+62. END.

CONNECT TO EXIST INSTALL: 1-8"x8" TAPPING SLEEVE AND 8" VALVE. 1-8" VALVE. 1-8"x6" TEE. 1-6" 11¼° BEND. 1-6" VALVE. 1-6" 90° BEND. 1-F.H.

CONNECT TO EXIST INSTALL: 1-8"x8" TAPPING SLEEVE AND 8" VALVE

CONNECT TO EXIST INSTALL: 1-8"x8" TAPPING SLEEVE AND 8" VALVE. 1-8" VALVE. 1-8"x6" TEE. 1-6" 11¼° BEND. 1-6" VALVE. 1-6" 90° BEND. 1-F.H.

INSTALL: 10 L.F. 2" WATER SERVICE FOR 2" METER FOR IRRIGATION PURPOSES

INSTALL: 1-8"x6" TEE 1-6" VALVE 1-6" PLUG

INSTALL: 1-8"x6" TEE 1-8" VALVE 1-6" VALVE 1-FIRE HYDRANT

INSTALL: 1-8"x8" TEE 1-8" VALVE 1-6" VALVE 1-FIRE HYDRANT

INSTALL: 1-8"x8" TEE 1-8" VALVE 1-8"x6" REDUCER 1-6" VALVE 1-6" 90° BEND 1-6" PLUG

INSTALL: 1-8"x8" CROSS 3-8" VALVES 1-8" 90° BEND 1-8" PLUG

INSTALL: 1-8"x8" CROSS 2-6" VALVES 2-6" PLUGS

INSTALL: 1-8"x8" CROSS 1-8" VALVE 1-6" VALVE 1-FIRE HYDRANT 1-8"x6" REDUCER

INSTALL: 1-8"x6" TEE 1-8" VALVE 1-6" VALVE 1-FIRE HYDRANT 1-8" PLUG

INSTALL: 1-8"x6" TEE 1-8" VALVE 1-6" VALVE 1-FIRE HYDRANT 1-8" 11¼° BEND

INSTALL: 1-8"x6" TEE 1-8" VALVE 1-6" VALVE 1-FIRE HYDRANT 1-8" PLUG

INSTALL: 1-8"x6" TEE 1-8" VALVE 1-6" VALVE 1-FIRE HYDRANT 1-8" 90° BEND

INSTALL: 1-8"x6" TEE 1-8" VALVE 1-6" VALVE 1-FIRE HYDRANT 1-8" PLUG

INSTALL: 1-8"x6" TEE 1-8" VALVE 1-6" VALVE 1-FIRE HYDRANT 1-8" 90° BEND 1-6" PLUG

INSTALL: 1-8"x6" TEE 1-8" VALVE 1-6" VALVE 1-FIRE HYDRANT 1-8