



NOTES

1. CONTACT COMPANY REPRESENTATIVE FOR (1) ROUTING OF CONDUIT LINE, (2) SIZE OF CONDUIT, AND (3) INSTALLATIONS REQUIRING MORE THAN ONE RISER ON POLE.
2. LIMIT CONDUIT RUN TO THREE 90° BENDS. IF MORE THAN THREE 90° BENDS ARE REQUIRED, CONTACT COMPANY REPRESENTATIVE.
3. DISTANCE BETWEEN 90° BENDS SHALL BE FIVE FEET MINIMUM.
4. ALL PRIMARY HORIZONTAL AND VERTICAL CONDUIT BENDS SHALL BE 90° WITH 36 INCH MINIMUM RADIUS.

APPROVED BY ONCOR	TERMINATION OF PRIMARY CONDUIT AT RISER POLE
	DCS-5 DETAIL SHEET 19 OF 19

COPYRIGHT 2013 ONCOR ELECTRIC DELIVERY COMPANY. ALL RIGHTS RESERVED.

04 - 13



Ch Morak , P.E. 10-24-13
 Signature of Registrant Date

FIRM REGISTRATION NUMBER: 312

NO.	REVISION	BY	DATE		
TOWN OF ADDISON DALLAS COUNTY, TEXAS					
BELT LINE ROAD UNDERGROUND ELECTRICAL					
ONCOR DUCT BANK DETAIL 4E6					
HALFF 1201 NORTH BOWSER ROAD, RICHARDSON, TEXAS 75081-2275 TEL (214) 348-6200 FAX (214) 739-0095					
PROJECT	DESIGN	DRAWN	DATE	FILE	SHEET
29350	HALFF	HALFF	OCT. 2013	29350 ELEC 26d	ELE-26