



- NOTES:**
- 1.) MAXIMUM SLOPE ON SIDEWALK RAMP MUST NOT EXCEED 1" PER FOOT IN ANY DIRECTION.
  - 2.) LOCATION OF SIDEWALK RAMP MAY BE SHIFTED TO CLEAR OBSTRUCTIONS AS DIRECTED BY THE ENGINEER.
  - 3.) PAYMENT FOR CONCRETE SIDEWALK RAMP WILL BE PAID UNDER ITEM 531-503.
  - 4.) DIMENSIONS SHOWN ARE FOR 5 3/4" HIGH CURBS. FOR CURBS WITH HEIGHT GREATER THAN 5 3/4", DIMENSIONS MUST BE INCREASED ACCORDINGLY.
  - 5.) REINFORCEMENT FOR ALL RAMPS SHALL BE THE SAME AS SPECIFIED FOR SIDEWALK.

REVISION #4 BARS TO #3 BARS IN SECTION B-B 9/2/97 RT

SHEET 6 OF 7

**BARTON-ASCHMAN ASSOCIATES, INC.**

MISCELLANEOUS DETAIL SHEET HANDICAP RAMPS				
ADDISON TRANSIT PASS ADDISON, TEXAS				
Texas Department of Transportation		DART		
REVISION	DATE	FED. ROAD DIV. No.	FEDERAL AID PROJECT NO.	SHEET No.
		6	CM 97 (449)	28
		STATE	STATE DIST.	COUNTY
		TEXAS	DALLAS	DALLAS
		CONT.	SECT.	JOB
		8050	18	034
		HIGHWAY No.		
		BELT LINE RD		
DESIGNED BY:	R.A.Y.			
DRAWN BY:	B-A			
CHECKED BY:	L.M.P.	BA FILE NAME :		

