

**LEGEND**

ITEM NO.	DESCRIPTION
104	① REMOVE CONCRETE (PAV)
104	② REMOVE CONCRETE (MED)
104	③ REMOVE CONCRETE (SIDEWALK)
104	④ REMOVE CONCRETE (DRIVEWAY)
104	⑤ REMOVE CONCRETE (FND)
104	⑥ REMOVE CONCRETE (CURB OR C&G)
104	⑦ REMOVE CONCRETE (RET. WALL)
105	⑨ RMV STB BS AND/OR ASH PAV (CL 2) VAR DEP
677	⑪ ELIM EXT PAV MRK & MRKR (24")
677	⑭ ELIM EXT PAV MRK & MRKR (RAIS PAV MRKR)
	⑮ REMOVE CONCRETE PAVERS. SUBSIDIARY TO ITEM 100 - PREP. R.O.W.


**NOTES :**

1. REMOVAL AND SALVAGE OF SMALL ROADSIDE SIGNS SHALL BE SUBSIDIARY TO ITEM 100 PREP R.O.W. SALVAGED SIGNS SHALL BE DELIVERED TO THE TOWN OF ADDISON SERVICE CENTER AT 16801 WESTGROVE ROAD, ADDISON, TEXAS.
2. CURB ON TOP OF CONCRETE PAVEMENT TO BE REMOVED WILL NOT BE PAID FOR DIRECTLY, BUT SHALL BE SUBSIDIARY TO ITEM 104 REMOVE CONCRETE (PAV).
3. DART SIGNS SHALL BE RELOCATED TO LOCATIONS DESIGNATED BY THE ENGINEER AND SHALL BE PAID FOR UNDER ITEM 649. SEE PAVING AND DRAINAGE PLAN/PROFILE SHEETS FOR LOCATION OF DART SIGNS.

SHEET 2 OF 2

**BARTON-ASCHMAN ASSOCIATES, INC.**

**REMOVAL PLAN SHEET**  
 BELT LINE ROAD AT QUORUM DRIVE  
 ADDISON TRANSIT PASS  
 ADDISON, TEXAS



REVISION	DATE	FED. ROAD DIV. No.	FEDERAL AID PROJECT NO.	SHEET No.
		6	CM 97 (449)	36
		STATE	STATE	COUNTY
		TEXAS	DALLAS	DALLAS
		CONT.	SECT.	JOB
DESIGNED BY:	R.A.Y.	8050	18	034
DRAWN BY:	B.A.A.			BELT LINE RD
CHECKED BY:	L.M.P.	BA FILE NAME :		