

SUMMARY OF QUANTITIES			
ITEM NO.	DESCRIPTION	QUANTITY	UNIT
1	24" DIA. WATER LINE	10,000	LF
2	20" DIA. WATER LINE	6,000	LF
3	16" DIA. WATER LINE	9,000	LF
4	12" DIA. WATER LINE	100	LF
5	10" DIA. WATER LINE	100	LF
6	8" DIA. WATER LINE	100	LF
7	24" VALVES	10	EA
8	20" VALVES	6	EA
9	16" VALVES	9	EA
10	8" VALVES	8	EA
11	6" VALVES	25	EA
12	AIR RELEASE VALVES	2	EA
13	FIRE HYDRANTS	20	EA
14	TIE-IN TO EXIST. WATER LINE	13	EA
15	ROAD BORING NO. 1	40'	LS
16	ROAD BORING NO. 2	100'	LS
17	ROAD BORING NO. 3	120'	LS
18	1" OR 3/4" SERVICE LINES W/CURB STOP	750	LF
19	PUMP STATION	—	LS
20	LANDSCAPE	—	LS
21	SPRINKLER SYSTEM	—	LS
22	MISC. CONCRETE	10	CY
23	12" VALVES	1	EA
24	ROAD BORING NO. 4	30'	LS

INDEX TO DRAWINGS	
TITLE	SHT. NO.
COVER	1
QUANTITIES & INDEX	2
SHEET INDEX	3
LINE D	4
LINE D & C	5
LINE B, A & AA	6
LINE L & LL	7
LINE L	8
LINE N & M	9
LINE Q	10
LINE S	11
SITE LAYOUT	12
YARD PIPING	13
PUMP STATION PIPING PLAN	14
PUMP STATION FLOOR PLAN	15
PUMP STATION ELEVATIONS	16
WALL SECTIONS	17
FOUNDATION PLAN & DETAILS	18
ROOF FRAMING PLAN	19
LANDSCAPE PLAN	20
ELECTRICAL	21
ELECTRICAL	22
ELECTRICAL	23
ELECTRICAL	24



CITY OF ADDISON DALLAS COUNTY, TEXAS	
WATER PUMP STATION AND WATER MAINS	
QUANTITIES & INDEX	
GINN & STACY, INC. CONSULTING ENGINEERS — DALLAS, TEXAS	
DESIGNED BY: HWG	SCALE: _____
DRAWN BY: JOS	DATE: SEPT 77