


SECTION A-A

TEMPORARY MANHOLE PANEL


NOTE: MK WAL-1 & WAL-4 AT LIFTING INSERTS, AND MK WAL-3 & WAL-12 NOT SHOWN. SEE DWG. TEX. 83-007-2



OUTSIDE FACE

INSIDE FACE

STRESS PLATE DETAILS



SECTION B-B

N. T. S.

THE DETAILS SHOWN ON THIS DRAWING SHALL BE PRODUCED WITHIN THE GUIDELINES AND REQUIREMENTS SPECIFIED IN PRELOAD CO. CONSTRUCTION SPECIFICATIONS & PROCEDURES NO. 'CS-28'.

MISC. IRON SCHEDULE								
MS	QUANTITY	DESIGN	ORDER	SIZE	LENGTH	WT. (LBS.)	SKETCH	LOCATION
ANC-2	10.8	11		1 x 1 = 1/4 L (15 PLF)	20'-0"	390	FORMULA: TOTAL NO. WAL-10 L WAL-12 BARS 0.58 (TO NEXT HIGHER 20')	PANEL JOINTS
ANC-3	8	8		3/4" φ	4'-7"	55	STAINLESS STEEL	ROOF AT OVER FLOW
ANC-4	234	239		1/2" φ	1'-4"	212	2 1/2" THREAD	WATER STOP ENCASUREMENT
ANC-5	4	4		1/2" φ	2'-4"	6	2 1/2" THREAD	D.I. INLET PIPE
ANC-8	4	4		1" φ	2'-9"	29	2 1/2" THREAD	ROOF FOR WIREWINDER
ANC-9	4	4		1" φ	6'-4"	68	2 1/2" THREAD	ROOF FOR WIREWINDER
ANC-10	8	9		5/8" φ	4'-4"	41	2 1/2" THREAD	AT INLET PIPE

LEGEND

- STOP AND COAT WIRE
- ▲ DIRECTION OF APPLICATION
- DIE ON TOP OF MACHINE
- DIE ON BOTTOM OF MACHINE
- \* - WIRES ANCHORED TO STRESS R


TEMPORARY MANHOLE PRESTRESSING PROCEDURE

1. Weld bottom half of clamps to stress plate using E70XX electrodes. All welding shall be in accordance with ANSI/AWS D-1-1-81.
2. Wrap wires over temporary manhole making sure wires drop into threaded slots of the clamps.
3. Install top half of clamps and tighten with bolts.
4. Cut wires 1" from edge of clamps as shown.
5. Wires to be cut starting at center line of opening alternating wires above and below opening (maximum unbalanced load = 2 wires).
6. Apply pneumatic mortar to cover wires, anchorages and temporary manhole.

PRESTRESS WIRE QUANTITIES

PHASE	WALL		DOME RING		TOTAL	REMARKS
	WRAPS	WEIGHT	WRAPS	WEIGHT		
I	121	5671				
II	225	10545				
III	155	7264				
IV	121	5671				
V	120	5624				
VI	115	5390				
VII	79	3702				
VIII	14	656				
IX	13	609				
TOTAL	963				963	TOTAL WRAPS
TOTAL		45132			45132	TOTAL WEIGHT
WEIGHT OF WIRES/LFT		0.164 = 0.07188	LFT OF WIRE / WRAP =		206 ÷ 2(0.71) x π = 652'	
			I.D. + (2 x WALL THICK)			

TOTAL OVERALL HEIGHT OF PRESTRESS PHASES = 73'



WIREWINDING SCHEDULE

NOTES:

1. WIREWINDING SCHEDULE IS BASED ON A WIRE DIAMETER OF 0.164" SIZES AND NUMBERS MAY BE ALTERED AS NECESSARY TO ATTAIN PROPER TOTAL INITIAL FORCE.
2. INITIAL FORCE IN WIRE (BASED ON SIZES INDICATED): WALL --- 3170 LBS.
3. INITIAL UNIT STRESS IN WIRE NOT TO EXCEED 155,000 P.S.I.
4. PROVIDE ONE INCH PNEUMATIC MORTAR PROTECTIVE COVER OVER OUTERMOST LAYER OF WIRES.
5. WIREWINDING SEQUENCE SHOWN SHOULD NOT BE ALTERED WITHOUT PRIOR APPROVAL BY PRELOAD ENGINEERS.

WORKING DRAWING

ONE 6.0 M.G. WATER STORAGE TANK  
ADDISON, TEXAS  
TEMPORARY MANHOLE PANEL  
AND WIREWINDING SCHEDULE

DESIGNED: PV SCALE: NONE CONTRACT: 86 PE 004  
DRAWN: FD MTO: NUMBER: 83-007-3  
CHECKED: RAO DATE: 4-24-86 DRAWING NUMBER: 83-007-3

REVISIONS				
NO.	DATE	DESCRIPTION	BY	CKD
1	9/18/86	REV. NOTE - TEMP. MANHOLE PANEL	E	RAO



839 STEWART AVENUE, GARDEN CITY, NEW YORK, 11530  
THIS DRAWING IS THE PROPERTY OF THE PRELOAD COMPANY, INC. AND/OR PRELOAD TECHNOLOGY, INC. AND IS SUBJECT TO RETURN ON DEMAND. IT CONTAINS FEATURES OF DESIGN WHICH ARE FULLY COVERED BY PATENTS AND PATENTS PENDING AND COPYRIGHTS. IT IS SUBMITTED FOR USE ONLY IN CONNECTION WITH PROPOSALS OR CONTRACTS OF PRELOAD OR ITS LICENSEES, UPON THE EXPRESS CONDITION THAT IT MAY NOT BE USED ON ANY OTHER DIFFERENT PROJECTS WITHOUT PRIOR APPROVAL OF PRELOAD.