



- LEGEND**
- XXXX PROPOSED PAVEMENT BRIDGE AND APPROACH SLAB DECK
 - XXXX PORTABLE CONCRETE TRAFFIC BARRIER (PCTH)
 - A 4M1A
 - B 4A1B
 - C 4Y1A
 - D 12W1B

- NOTES**
1. ALL WORK ZONE PAVEMENT MARKINGS SHALL COMPLY WITH TxDOT'S STD. 212.03-01
 2. BRIDGE DEMOLITION BEGAN HANGING OPERATIONS SHALL BE PERFORMED DURING OFF PEAK TRAFFIC ONLY AND TRAFFIC DETOURING SHALL PROVIDED BY CONTRACTOR. SCHEDULING OF OPERATIONS MUST BE APPROVED BY NITA WORK IS PERFORMED.
 3. DURING BRIDGE OPERATIONS CONTRACTOR RESPONSIBLE FOR CAPTURING FALLING DEBRIS IN AREAS WHERE TRAFFIC IS MAINTAINED.



Note: Orange safety Fence to be placed as required to prevent Pedestrian Traffic.

West Grange
DETOUR ←
M4-5H
M4-0L
Place NB Dallas Parkway @ Trinity Mills
Place SB Dallas Parkway @ Keller Springs

DALLAS NORTH TOLLWAY	
NITA NORTH TEXAS TOLLWAY AUTHORITY	
TRAFFIC CONTROL PLAN PHASE I STA 685+00 TO STA 697+00	
PATE ENGINEERS <small>2801 W. HAWK DR. SUITE 100, FORT WORTH, TX 76104</small>	STA 17.1 PLAN 02
DATE: 02/02/08 BY: [Signature]	DATE: 02/02/08 BY: [Signature]

NITA ENGINEERING
 2801 W. HAWK DR. SUITE 100
 FORT WORTH, TEXAS 76104
 ATTACHED AS