



**CITY OF ADDISON  
APPROVED**  
FOR CONSTRUCTION

BUILDING DEPARTMENT

DATE: \_\_\_\_\_  
NOTE: CONTRACTOR IS HEREBY INSTRUCTED TO EXERCISE CARE IN INSTALLING OR REPAIRING ALL REQUIREMENTS OF FEDERAL, STATE AND LOCAL CODES AND/OR ORDINANCES APPLICABLE TO HIS WORK. APPROVAL OF THESE PLANS SHALL NOT BE CONSTRUED TO BE A WARRANTY OR LIABILITY OR IMPLY VARIANCE TO SUCH.

- NOTES-
1. Water lines shall be located a minimum of 48" depth.
  2. All materials and workmanship to conform to City of Addison standards.
  3. Sanitary Sewer under existing Spectrum Drive to be constructed by bore.
  4. Bored sewer lines to be encased in welded steel casing. Outside casing to be grouted.
  5. Sanitary manholes to be poured in place.
  6. Water and sewer crossing to be concrete encased.
  7. Water and sewer embedment to consist of 6" sand below, around and above pipe.

REVISION NOTE: September 24, 1981  
Relocated Tapping Sleeve and adjacent Water Line near Spectrum Drive at Dallas Parkway to West side of existing 24" Storm Pipe.

REVISION NOTE: Sept. 10, 1981  
Added optional bore at Sanitary Line "A" Revised Parking near S.W. Corner of Garage.

These plans revised and updated for construction through August 1, 1981.

UTILITY PLAN						
THE QUORUM REGISTRY HOTEL						
THE REGISTRY HOTEL CORPORATION 16250 DALLAS NORTH PARKWAY, SUITE 105 DALLAS, TEXAS 75248						
CITY OF ADDISON, TEXAS						
DESIGN	DRAWN	DATE	SCALE	NOTES	FILE	NO.
HUITT - ZOLLARS, INC.	HUITT - ZOLLARS, INC.	JUNE, 81	1" = 40'			3 of 6
8150 KING GEORGE DR. SUITE 101 DALLAS, TEXAS 75235 PROJECT NO. 51145						

**BENCH MARKS**

Standard Water Department B.M. top of inlet on West side of Dallas Parkway 40' South of Spectrum Drive. Elevation: 625.97.

Top Southeast corner of "Y" inlet, 230' North of Southeast property corner and 27' West of East propertyline. Elevation: 623.49.

Top operating nut of a Fire Hydrant 270' South of Northwest property corner. Elevation: 630.78.