

SPECIAL INSTRUCTIONS
Sidewalk Repairs, Ramp, Curb & Gutter Construction

1.0 GENERAL

- 1.01 The contractor shall furnish all labor and materials necessary for the complete construction of any repairs. Construction shall be in accordance with the latest edition of the NTCOG Standard Specifications for Public Works Construction, and/or as shown on approved plans.
- 1.02 All work within the public right-of-way shall also comply with all applicable sections of the Town of Addison Code of Ordinances, Chapter 70.
- 1.03 Scheduling of construction shall be under the direction of the Street Superintendent and will be permitted only between the hours of 7:00 a.m. - 7:00 p.m., Monday through Friday, or 8:00 a.m. - 7:00 p.m., Saturday and Sunday, when within 300 feet of a residence. All lane blockages shall be approved by the Street Superintendent. See Sec. 70-113.
- 1.04 Where Sprinkler systems have previously been installed, the Contractor shall relocate, at his own expense, the entire portion of that system in conflict with sidewalk construction. This relocation shall be completed by a licensed irrigator, registered with, and approved by, the Town of Addison. No part of this system shall remain beneath the new sidewalk, with the possible exception of the water meter. Special attention shall be given to the replacement of the proper sprinkler heads in order to ensure adequate coverage. All sprinkler system relocation shall be completed within five (5) days, beginning at the time of shut off. Contractor shall be responsible for hand watering all landscape materials during this time, and take any action necessary, as determined by the Street Superintendent, or the Parks Department Superintendent, to ensure the integrity of all landscaping. Any landscape material within the right-of-way requiring relocation due to the construction, shall be moved by the Contractor at his expense. Live sod, matching the predominate grasses (St. Augustine, Bermuda, etc.), shall be applied as necessary, leaving the construction area in the condition as near as possible to that existing before such construction began.
- 1.05 The contractor shall submit a copy of the concrete batch design for approval, prior to construction.
- 1.06 Contractor shall adjust all water meter boxes, valve stacks, clean outs, etc. to finished grade as directed.
- 1.07 The Addison Street Department shall remove/relocate all street name and/or regulatory signs after being given 24 hour notice by contractor.
- 1.08 Where power poles, fire hydrants, and similar obstructions exist, contractor shall widen sidewalk around obstruction to provide a minimum three foot wide clear walk, or as required to comply with the ADA and/or TAS.