PLAN — SURVEYED ____ DATE ____ | PLOTTED ____ BY ____ | NOTE BOOK ____ ALIGNMENT CHECKED ____ | NO. ____ RT. OF WAY CHECKED ____

NOTE:
AT NO TIME SHALL MORE THAN ONE TAXIWAY BE CLOSED DURING CONSTRUCTION

30' WIDE TAXIWAY
AWECO INC.
CONC.
TAXIWAY
CONC.
VAN-HOFF CO.
CONC.
50' WIDE TAXIWAY
TEXAS FEDERAL SAVING & LOAN
SEPTIC TANK
F.H.
F.H.
EX. 8" WATER
ASPH. PVM'T.
FRANK LUKE ST.
9+18 CONST. STD. M.H. W/ 8" STUBOUT & PLUG
INSTALL 8"x4" P.V.C. "Y" LOCATE IN FIELD
ASPH. PVM'T
8"
INSTALL 8"x4" P.V.C. "Y" LOCATE IN FIELD
4+50 CONST. STD. M.H.
C.O.
W.M.
W.M.
W.M.
W.M.
W.M.
Mc KAMEY AVIATION
T- HANGER
T- HANGER
T- HANGER
T- HANGER
AERO PLACE
ASPH. PVM'T.
5.0'
5.0'
PULL PIPE
EX. 10" STUB-OUT
EX. 8" SANI. SWR.
EX. 10" C.A.C.P. WATER
EX. M.H.
ADDISON ROAD (ASPH.)
CONST. STD. DROP M.H. W/ 8" STUBOUT & PLUG
EX. 8" SAN. SWR. CONST. STD. DROP M.H.

SAW CUT EXIST. ASPH. BOTH EDGES
2" HMAC TYPE "D"
6" BLACK BASE
BACKFILL W/SELECT MATERIAL HAND COMPACTED TO 95% STD. PROCTOR
SAND
PEA GRAVEL
6"
2'-0"

ASPH. PVM'T. REPLACEMENT DETAIL
NO SCALE

GENERAL NOTES

1. Embedment shall be select material from ditch free of rocks and organic material. The ditch shall be excavated 3" below barrel of pipe and backfill to grade with pea gravel and 6" sand above the top of pipe and carefully hand placed and hand completed.
2. All work shall be in accordance with the specifications and standard drawings of the City of Addison, Texas.

BENCH MARK:
□ ON CONC. BASE OF F.L.A.S. POLE @ OLD Mc KAMEY AVIATION
ELEV: 640.86

CITY OF ADDISON, TEXAS
ADDISON MUNICIPAL AIRPORT
PROPOSED 8" SEWER MAIN

Riewe & Wischmeyer, Inc.
CONSULTING ENGINEERS
DALLAS, TEXAS

DESIGNED: J.W.
APPROVED: J.T.M.
DATE: APRIL 1979
JOB NO. 7004
SHEET NO. 1 OF 1
SCALE: 1" = 50' HORIZ., 1" = 5' VERT.

PROFILE — SURVEYED ____ BY ____ DATE ____ | PLOTTED ____ | NOTE BOOK ____ GRADES CHECKED ____ | NO. ____ B.M.'S NOTED ____ | STRUCTURE NOTATIONS CHECKED ____

645 640 635 630 625

9+18 CONST. STD. M.H. W/ 8" STUBOUT & PLUG
T+55+ INST. 8"x4" "Y" LOCATE IN FIELD
4+50 CONST. STD. M.H.
4+00 INST. 8"x4" "Y" LOCATE IN FIELD
2+70 INST. 8"x4" "Y" LOCATE IN FIELD
0+00 EX. SAN. SWR. CONST. STD. DROP M.H. (VERT. ELEV. ESTD.)
FUTURE EXTENSION
F.L. 634.46
8" PVC ON 0.33%
F.L. 632.02
8" PVC ON 0.33%
REMOVE & RELAY 8" P.V.C.
DROP ST. GRADE 639.16±
F.L. 8" IN 638.45 F.L. 8" OUT 638.00± (VERT. IN FIELD)

FURNISH & INSTALL 918 L.F. 8" P.V.C. SEWER PIPE

14 13 12 11 10 9 8 7 6 5 4 3 2 1 0

PLATE 1 - PLAN - PROFILE - F.A.S.
CLEARPRINT PAPER CO., S. F., CAL.
NO. 1000H-1