



- GENERAL NOTES:
1. All 8" water main to be 800-10 PVC with #12 tracer wire.
 2. All 8" water mains to have a minimum of 4' cover below street grades or as required to clear other utilities.
 3. Fire hydrant and valve grade adjustments (after paving) shall be the responsibility of the utility contractor.
 4. Water and sanitary sewer easements shall also include additional area of working space for construction and maintenance of the system. Additional easement area is also provided for installation and maintenance of manholes, cleanouts, fire hydrants, services, laterals, meters, and other appurtenances necessary for proper operation of the system.
 5. Sanitary sewer pipe joints shall conform to current A.S.T.M. designation C-245, 800-35 PVC.
 6. Unless otherwise noted, all material and construction shall conform to the standard specifications of the City of Addison, Texas. In the event an item is not covered in the City of Addison specifications, the City Engineer's decision shall apply.
 7. The location of all existing utilities to be verified by contractor prior to start of construction.
 8. Contractor to notify utility companies at least 48 hours (2 working days) prior to start of construction.
 9. All fire hydrants shall be Mueller Centurion model.
 10. Tapping sleeves to be Mueller or Clow.

WATER OF ADDISON APPROVED
GATEWAY CENTRE
 WILLIAM L. FORX & CURVEY, ABST. 792
 ADDISON, T.X.
 SPAIN AYRES & ASSOCIATES, INC.
 CONSULTING ENGINEERS
 214 FABENS RD. DALLAS, TEXAS
 214 243-7881 75225

REVISED SEPT. 11, 79
 REVISED OCT. 25, 77 (A. BOUT)