

QUANTITY SUMMARY SHEET

| ITEM NO. | DESCRIPTION | UNIT | PAVING | | | DRAINAGE | | | NET TOTAL | BID TOTAL |
|----------|---|------|--------|-----|-----|----------|--|-----|-----------|-----------|
| | | | 6 | 7 | 8 | 9 | | | | |
| 1 | MOBILIZATION | LS | | | | | | 1 | | |
| 2 | INSTALL WHEELCHAIR RAMP | EA | 2 | | | | | 2 | | |
| 3 | PAVEMENT SAWCUT (FULL DEPTH) | LF | 10 | | 10 | | | 20 | | |
| 4 | REMOVE CONCRETE CURB & GUTTER | LF | 262 | 350 | 248 | | | 860 | | |
| 5 | REMOVE CONCRETE SIDEWALK | SY | 145 | 194 | 141 | | | 480 | | |
| 6 | REMOVE CONCRETE DRAINAGE HEADWALL | EA | | | | 1 | | 1 | | |
| 7 | REMOVE STORM DRAIN INLET | EA | | | | 2 | | 2 | | |
| 8 | REMOVE REINFORCED CONCRETE PIPE | LF | | | | 22 | | 22 | | |
| 9 | UNCLASSIFIED ROADWAY EXCAVATION | CY | 96 | 301 | 171 | | | 568 | | |
| 10 | SELECT FILL | CY | 419 | 89 | 2 | | | 510 | | |
| 11 | CEMENT TREATED BASE | SY | 500 | 644 | 286 | | | | | |
| 12 | CONCRETE CURB & GUTTER | LF | 221 | 350 | 269 | | | 840 | | |
| 13 | HOT MIX ASPHALTIC CONCRETE - TYPE "B" | TON | 122 | 157 | 69 | | | 348 | | |
| 14 | HOT MIX ASPHALTIC CONCRETE - TYPE "D" | TON | 41 | 52 | 23 | | | 116 | | |
| 15 | CONCRETE SIDEWALK | SY | 127 | 194 | 149 | | | 470 | | |
| 16 | BLOCK SOD | SY | 135 | 205 | 160 | | | 500 | | |
| 17 | REINFORCED CONCRETE HEADWALL | CY | | | | 4.7 | | 4.7 | | |
| 18 | 18" REINFORCED CONCRETE PIPE (CLASS III) | LF | | | | 23 | | 23 | | |
| 19 | 24" REINFORCED CONCRETE PIPE (CLASS III) | LF | | | | 14 | | 14 | | |
| 20 | 36" REINFORCED CONCRETE PIPE (CLASS III) | LF | | | | 73 | | 73 | | |
| 21 | STORM DRAIN INLET (10' RECESSED) | EA | | | | 2 | | 2 | | |
| 22 | BARRICADING, SIGNS, & TRAFFIC HANDLING | MON | | | | | | 3 | | |
| 23 | INSTALL AND REMOVE SILT FENCE | LF | 275 | 350 | 275 | | | 900 | | |
| 24 | INSTALL & REMOVE BALED HAY AT INLETS | EA | | | | 20 | | 20 | | |
| 25 | RELOCATE DART TRAFFIC SIGN | EA | | | | | | 1 | | |
| 26 | RELOCATE STREET NAME SIGN | EA | | | | | | 1 | | |
| 27 | INSTALL SIGN R2-1 | EA | | | | | | 1 | | |
| 28 | INSTALL SIGN R3-7R | EA | | | | | | 2 | | |
| 29 | INSTALL SIGN R3-9b | EA | | | | | | 3 | | |
| 30 | INSTALL THERMO. PVMT. MRKG. ARROW | EA | | | | | | 9 | | |
| 31 | INSTALL THERM. PVMT. MRKG. WORD | EA | | | | | | 3 | | |
| 32 | INSTALL 4" YELLOW DOUBLE-REFL. BUTTON | EA | | | | | | 160 | | |
| 33 | INSTALL 4" YELLOW NON-REFL. BUTTON | EA | | | | | | 232 | | |
| 34 | INSTALL 4" WHITE SINGLE-REFL. BUTTON | EA | | | | | | 109 | | |
| 35 | INSTALL 4" WHITE NON-REFL. BUTTON | EA | | | | | | 72 | | |
| 36 | REMOVE 24" STOP LINE | LF | | | | | | 11 | | |
| 37 | REMOVE RAISED BUTTON | EA | | | | | | 610 | | |
| 38 | REMOVE PVMT. MRKG. ARROW | EA | | | | | | 6 | | |
| 39 | REMOVE PVMT. MRKG. WORD | EA | | | | | | 4 | | |
| 40 | INSTALL WZ PVMT MRKR (SHORT TERM)TAB (TYPE Y-2) | EA | | | | | | 200 | | |
| 41 | INSTALL WZ PVMT MRKR (SHORT TERM) TAB (TYPE W) | EA | | | | | | 200 | | |


 3/5/99

REV. 1 - ADD PVMT. MRKG. QUANT. AND RENUMBER ITEMS. 3/5/99

| | | | | | | |
|--------------------------------------|-------|------|-------|-------|------|--------|
| PAVING QUANTITY SUMMARY SHEET | | | | | | |
| KELLER SPRINGS ROAD | | | | | | |
| FROM ADDISON ROAD TO LEDGEMONT LANE | | | | | | |
| DEPARTMENT OF PUBLIC WORKS | | | | | | |
| TOWN OF ADDISON, TEXAS | | | | | | |
| DESIGN | DRAWN | DATE | SCALE | NOTES | FILE | NUMBER |
| PTC | PTC | 5-98 | | | | |