

PAVING SUMMARY

SHT NO.	CL STATION LIMITS	(100) PREPARE R.O.W. (KM)	(360) CPCD (200 mm) m2	(260) LTS (200 mm) m2	(260) LIME (6% BY WT) Mg	(529) CONCRETE CURB/GUTTER m	(531) CONCRETE SIDEWALKS m2	(5027) MEDIAN PAVESTONE m2	EDGE RESTRAINT FOR PAVESTONE M	(3022) TY-B ACP (BASE) (100 mm) Mg	(160&162) TOPSOIL & BLOCK SOD (100 mm) m2	(168) VEG WATER KL	(166) FERTILIZER Mg
1	BEGIN TO STA 0+220	0.127	2211.5	2521.5	53.3	499.1	97.7	107.7	2.3	592.3	165	12.5	0.002
2	STA 0+220 TO STA 0+340	0.120	2630.8	3125.0	66.1	489.9	345.4	65.9	1.8	734.1	1250	95.0	0.014
3	STA 0+340 TO STA 0+460	0.120	2190.1	2502.0	52.9	446.8	357.8	19.5	9.8	587.7	1307	99.3	0.015
4	STA 0+460 TO STA 0+580	0.120	2171.2	2561.2	54.2	441.2	383.8	13.3	3.8	601.6	1309	99.5	0.015
5	STA 0+580 TO STA 0+700	0.120	1873.8	2172.3	46.0	475.2	368.2	5.0	4.9	510.3	3973	301.9	0.044
6	STA 0+700 TO STA 0+820	0.120	2245.5	2487.0	52.6	379.0	363.3	17.6	10.4	584.2	1857	141.1	0.021
7	STA 0+820 TO END	0.123	2027.5	2291.0	48.4	423.8	322.5	0	0	538.2	1400	106.4	0.016
8	TARPLEY ROAD	0.037	614.0	988.0	20.9	59.9	0	0	0	232.1	130	9.9	0.001
9	KELLER SPRINGS ROAD EAST	0.037	694.5	783.5	16.6	149.2	0	25.3	0	184.0	115	8.7	0.001
10	KELLER WAY	0.031	427.0	474.0	10.0	76.2	0	0	0	111.3	155	11.8	0.002
TOTALS		0.955	17,085.9	19,905.5	421.0	3440.3	2238.7	254.3	33.0	4675.8	11661	886.1	0.131

NOTE: SHEET NUMBERS ARE PAVING SHEETS.

SUMMARY OF DOWELED CURB	
130 m	

SUMMARY OF CONDUIT			
75mm	50mm	38mm	PULL BOX
130m	765m	725m	16


REMOVE SMALL STRUCTURE		
SHT. NO.		m2
2	WALL/FOUNDATION	72

LOCATION	(104) REMOVING CONCRETE m2	(105) 0.15m STABILIZED BASE &/OR ASPHALTIC CONCRETE (CLASS 2) m2
	WEST OF MARSH LANE	1278
EAST OF MARSH LANE	1498	974
TARPLEY ROAD	2103	0
KELLER SPGS RD EAST & KELLER WAY DRIVEWAYS	3458	0
	348	0
TOTAL	8685	974

• CONCRETE PAVEMENT AND SIDEWALKS

- 3 REV. 6/3/98 AHH
- 2 REV. 9/29/97
- 1 REV. 8/18/97 MWH

1
1

PAVING SUMMARY									
KELLER SPRINGS ROAD									
DALLAS COUNTY, TEXAS									
TEXAS DEPARTMENT OF TRANSPORTATION									
 Halff Associates <small>ENGINEERS - ARCHITECTS - SCIENTISTS - PLANNERS - SURVEYORS</small>									
DESIGN	DRAWN	NOTES	FED. NO. DIV. NO.	STATE	FEDERAL AID PROJECT NO.	SHEET NO.			
CADD			8	TEXAS		1			
DATE	FILE	SCALE	STATE DIST. NO.	COUNTY	CONTROL NO.	SECTION NO.	JOB NO.	HIGHWAY NO.	
JULY 1999	708SUB02	NONE	11	DALLAS	0981	46	222	CS	