

SUMMARY OF PERMANENT REFLECTORIZED PAVEMENT MARKINGS (ITEM 666)									
SHEET NO.	STATION LIMITS	TY 1 - THERMOPLASTIC							
		100 mm (W) SOLID METER	100 mm (Y) SOLID METER	300 mm (W) SOLID METER	600 mm (W) SOLID METER	ARROW (STRAIGHT) (W) EACH	ARROW (LT TURN) (W) EACH	ARROW (RT TURN) (W) EACH	DBL ARROW (RT TN/STR) (W) EACH
1	BEGIN TO 0+420	711.1	508.3	518.8	40.0	9	4	1	2
2	0+420 TO 0+740	610.3	574.8	0	14.9	0	0	0	0
3	0+740 TO END	307.2	281.0	0	35.0	0	0	0	0
TOTALS:		1628.6	1364.1	518.8	89.9	9	4	1	2

SUMMARY OF PERMANENT RAISED PAVEMENT MARKERS (ITEM 672)			
SHEET NO.	STATION LIMITS	TYPE 1-C RPM CLASS B EACH	
		TYPE W CLASS C EACH	
1	BEGIN TO 0+420	△ 354	255
2	0+420 TO 0+740	△ 115	210
3	0+740 TO END	160	158
TOTALS:		△ 629	623

SUMMARY OF TEMPORARY PAVEMENT MARKINGS			
PHASE NO.	100 mm (Y) SOLID METER	100 mm (Y) DASHED METER	TEMP ACP TYPE B M <sup>2</sup>
	1	1180.1	15.6
2	415.1	0	256.4
3	1941.0	59.7	0
TOTALS:	△ 3536.2	75.3	554.4

STORM WATER POLLUTION PREVENTION PLAN SUMMARY (ITEM 506)					
PROJECT TOTALS	BALED HAY (EA)	REMOVE BALED HAY (EA)	ROCK FILTER DAM CLASS 3 (m)	REMOVE ROCK FILTER DAM CLASS 3 (m)	BLOCK SOD (m <sup>2</sup> )
		100	100	38	38

NOTE: SHEET NUMBERS ARE STRIPING SHEETS

△ REV. 6/3/98 AHH

△ REV. 8/18/97

PAVEMENT MARKING AND STORM WATER POLLUTION PREVENTION PLAN SUMMARY									
KELLER SPRINGS ROAD									
DALLAS COUNTY, TEXAS									
TEXAS DEPARTMENT OF TRANSPORTATION									
 <b>Halff Associates</b> <small>ENGINEERS - ARCHITECTS - SCIENTISTS - PLANNERS - SURVEYORS</small>									
DESIGN	DRAWN	NOTES	FED. NO. DIV. NO.	STATE	FEDERAL AID PROJECT NO.	SHEET NO.			
	CADD		6	TEXAS	STP 95 0903 MM	1			
DATE	FILE	SCALE	STATE DIST. NO.	COUNTY	CONTRACT NO.	SECTION NO.	JOB NO.	HIGHWAY NO.	
JULY 1998	706SLN04	NONE	10	DALLAS	0910	45	222	CR	