

ITEM NO. 636 & SP
SUMMARY OF ALUMINUM SIGNS (TY A)

SHEET NO.	LOCATION	QUANTITY, SF		
		GROUND MOUNT	OVERHEAD	PORTAL *
8	MIDWAY RD. - STA. 10+00	36.00	100.75	58.50
9	STA. 10+00 - STA. 33+00		-	58.50
10	STA. 33+00 - ADDISON RD.		123.50	
	TOTAL	36.00	224.25	117.00

* MATERIALS & LABOR FOR SIGN MOUNTING TO BE SUBSIDIARY TO PORTAL SIGN.

ITEM NO. 666 & SP
SUMMARY OF REFL PVMT MARKINGS (TY I)

SHEET NO.	LOCATION	QUANTITY, EA		QUANTITY, LF		
		WHITE				
		ARROW	WORD	4" SOLID	4" BROKEN	18" SOLID
8	MIDWAY RD. - STA. 10+00			1720		141
9	STA. 10+00 - STA. 33+00			4600	10	
10	STA. 33+00 - ADDISON RD.			305	60	44
	TOTAL			6625	70	185

ITEM NO. SS 760
SUMMARY OF LIGHTING POLE LUMINAIRES (INSTALL)*

SHEET NO.	LOCATION	QUANTITY, EA	
		11-400-10-40MH	111-400-10-40MH
18	MIDWAY RD. - STA. 3+50	2	-
19	STA. 3+50 - STA. 8+00	4	2
21	STA. 23+00 - STA. 28+00	1	1
22	STA. 28+00 - STA. 33+00	4	-
23	STA. 33+00 - ADDISON RD.	2	1
	TOTAL	13	4

* ALL LUMINAIRES SHALL BE PROVIDED BY NTTA.

ITEM NO. 644 & SP
SUMMARY OF SMALL ROADSIDE SIGN ASSEMBLIES

SHEET NO.	LOCATION	QUANTITY, EA						
		TY A	TY A (B-B)	TY A-1	TY B	TY D-2	TY D-6	SM
8	MIDWAY RD. - STA. 10+00	11.00		1.00	6.00	2.00	1.00	1.00
9	STA. 10+00 - STA. 33+00	5.00						1.00
10	STA. 33+00 - ADDISON RD.	9.00	1.00	4.00	4.00	2.00	1.00	
	TOTAL	25.00	1.00	5.00	10.00	4.00	2.00	2.00

ITEM NO. 672 & SP
SUMMARY OF RAISED PAVEMENT MARKERS

SHEET NO.	LOCATION	QUANTITY, EA			
		CL B	CL C	CL B	CL A
		TY II-A-A	TY Y TRAF BTN	TY II-C-R	TY Y JIGGLE BAR
8-10	MIDWAY RD. - ADDISON RD.	310	925	7	156
	TOTAL	310	925	7	156

ITEM NO. SS 760
SUMMARY OF LIGHTING POLE FLOODLIGHTS (INSTALL)*

SHEET NO.	LOCATION	QUANTITY, EA
18	MIDWAY RD. - STA. 3+50	6
19	STA. 3+50 - STA. 8+00	4
	TOTAL	10

* ALL FLOODLIGHTS SHALL BE PROVIDED BY NTTA.

ITEM NO. 647 & SP
SUMMARY OF LARGE ROADSIDE SIGN SUPPORTS

SHEET NO.	LOCATION	QUANTITY, LBS
		MOUNT TYPE 321
8	STA. 1+75	255.20
	TOTAL	255.20

ITEM NO. SS 760
SUMMARY OF SIGN-MOUNT SIGNAL LIGHTS (INSTALL)*

SHEET NO.	LOCATION	QUANTITY, PAIR
8	STA. 1+75, MEDIAN SIGN	1.00
8	STA. 6+05, LT. CANT. SIGN	1.00
8	STA. 9+75, OVERHEAD STRUC	1.00
9	STA. 26+25, OVERHEAD STRUC	1.00
10	STA. 35+15, LT. CANT. SIGN	1.00
	TOTAL	5.00

* ALL SIGN-MOUNT SIGNAL LIGHTS SHALL BE PROVIDED BY NTTA.

ITEM NO. SS 760
SUMMARY OF LIGHTING POLES (INSTALL)* AND LIGHTING POLE FOUNDATIONS

SHEET NO.	LOCATION	GROUND MOUNTED POLES EA	LIGHTING POLE FOUNDATIONS EA	POLES MOUNTED ON EXISTING WALL EA
18	MIDWAY RD. - STA. 3+50	5	5	-
19	STA. 3+50 - STA. 8+00	4	4	4
21	STA. 23+00 - STA. 28+00	2	2	-
22	STA. 28+00 - STA. 33+00	4	4	-
23	STA. 33+00 - ADDISON RD.	2	2	-
	TOTAL	17	17	4

* ALL LIGHTING POLES SHALL BE PROVIDED BY NTTA.

ITEM NO. 650 & SP
SUMMARY OF OVERHEAD SIGN SUPPORTS

SHEET NO.	LOCATION	CANT. SPAN X TOWER HEIGHT	QUANTITY, EA
8	STA. 6+05, LT.	30'-0" X 16'-0"	1.00
10	STA. 35+15, LT.	30'-0" X 22'-6"	1.00
	TOTAL		2.00

ITEM NO. SS 760
SUMMARY OF SIGN FACE LUMINAIRES (INSTALL)*

SHEET NO.	LOCATION	QUANTITY, EA
8	STA. 6+05, LT. CANT. SIGN	2.00
10	STA. 35+15, LT. CANT. SIGN	4.00
	TOTAL	6.00

* ALL SIGN LIGHTS SHALL BE PROVIDED BY NTTA.

THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY RICHARD K. LAIRD, P.E. NO. 59187 ON JANUARY 12, 1999. ALTERATION OF A SEALED DOCUMENT WITHOUT PRIOR NOTIFICATION TO THE RESPONSIBLE ENGINEER IS AN OFFENSE UNDER THE TEXAS ENGINEERING PRACTICE ACT.



FINAL RECORD
DRAWING
Date: 12/25/99

No.	REVISION	BY	DATE
NORTH TEXAS TOLLWAY AUTHORITY ADDISON AIRPORT TUNNEL			
QUANTITY/ITEM SUMMARIES			
MCE MATED CONSULTING ENGINEERS, INC. 5540 PETERSON LANE SUITE 225 DALLAS, TEXAS 75240 (972) 233-6700			SECTION XIII
DRAWN: TMF	DATE: 5/97	DESIGNED: RKL	DATE: 5/97
CHECKED: SCF	DATE: 5/97	SCALE: NONE	
CONTRACT No. DNT-260 SHEET 3 OF 52			