SUMMARY OF SMALL SIGNS

PLAN SHEET NO.	SIGN NO.	SIGN TYPE	SIGN TEXT	SIGN DIMENSIONS	REFLECTIVE SHEETING	PLYWOOD TYPE A	ALUMINUM TYPE A	TYPE OF MOUNT: A	A (B-B)	A-1	B	C	D-1	D-2	SM*	D-4	D-5	D-6	F	G	DRIVEABLE TY I	DRIVEABLE TY II	MILEPOSTS MP	MILEPOSTS MW
10	46	R5-1	DO NOT ENTER	30X30	C		1	1																
	47	R1-2	YIELD	36X36X36	C		1	1																
	48	R3-8(MOD)	LANE USE (SYMBOL)	48X30	C		1							1										
	49	R3-8(MOD)	LANE USE (SYMBOL)	48X30	C		1							1										
	50	DNT-1	DNT (SYMBOL)	24" DIA.	C		1	1																
		M6-3G	↑	21X15	C		1																	
	50A	DNT-1	DNT (SYMBOL)	24" DIA.	C		1	1																
		M6-3G	↑	21X15	C		1																	
	51	R14-3	HAZARD. CARGO PROHIB. (SYM.)	24X24	C		1				1													
		ATT-1	Addison Toll Tunnel	24X24	C		1																	
		M6-1 L	←	21X15	C		1																	
		DNT-1	DNT (SYMBOL)	24" DIA.	C		1																	
		M6-1GR	→	21X15	C		1																	
	52	R14-3	HAZARD. CARGO PROHIB. (SYM.)	24X24	C		1				1													
		ATT-1	Addison Toll Tunnel	24X24	C		1																	
		M6-8 L	LEFT LANE	24X18	C		1																	
↓		DNT-1	DNT (SYMBOL)	24" DIA.	C		1																	
10		M6-8GR	RIGHT LANE	24X18	C		1																	
8	53	SPECIAL	HANDICAPPED SPACE SIGN (SYM.)	12X16	C		1																	
↓		PLAQUE	VAN ACCESSIBLE	12X06	C		1	1																
8	54	SPECIAL	50¢ TOLL ALL VEHICLES	108X36	C		1											1						
10	55	SPECIAL	50¢ TOLL ALL VEHICLES	108X36	C		1											1						
			PAGE TOTALS					5			2			2				2						
			PROJECT TOTALS					25	1	5	10			4	2			2						

Sign supports shall be located as shown on the plans, except that the Engineer may shift the sign supports, within design guidelines, where necessary to secure a more desirable location or to avoid conflict with utilities. Unless otherwise shown on the plans, the Contractor shall stake and the Engineer will verify all sign support locations.

Reflective sheeting will be designated as:

Type C - High Specific Intensity

* FOR STRUCTURE MOUNTING DETAILS, SEE SHEETS 15 THRU 17.

Note:

1. The DNT and the Addison Toll Tunnel Logo Sign Trailblazers will come from the NTTA for installation by the contractor.

THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY RICHARD K. LAIRD, P.E. NO. 59187 ON JANUARY 12, 1999. ALTERATION OF A SEALED DOCUMENT WITHOUT PRIOR NOTIFICATION TO THE RESPONSIBLE ENGINEER IS AN OFFENSE UNDER THE TEXAS ENGINEERING PRACTICE ACT.

FINAL RECORD DRAWING
Date: 12/25/99

STATE OF TEXAS
RICHARD K. LAIRD
59187
REGISTERED
PROFESSIONAL ENGINEER

No.	REVISION	BY	DATE

NORTH TEXAS TOLLWAY AUTHORITY
ADDISON AIRPORT TUNNEL

SUMMARY OF SMALL SIGNS

MCE MATEO CONSULTING ENGINEERS, INC.
5580 PETERSON LANE SUITE 225
DALLAS, TEXAS 75240 (972) 233-6700

SECTION XIII

DRAWN: TMF DATE: 5/97 DESIGNED: RKL DATE: 5/97
CHECKED: SCF DATE: 5/97 SCALE: NONE

CONTRACT No. DNT-260 SHEET 7 OF 52

112SUM02.SHT