MATCH LINE D

Chatham Court

Beltway Drive

6' Wrought Iron Fence

Fire Hydrant

6' Brick Wall

6' Wrought Iron Fence

Note: Remove Existing Landscape Area Along Wrought Iron Fencing

5' Sidewalk to be Removed

Note:
All measurements made from Baseline B are at 90 degrees from back of curb.

Refer to Sheet C-2.10 for Plaza B Enlargement

6' Brick Wall

Telephone Riser to be Relocated so as not to conflict with flatwork, Coordinate with Town of Addison and utility company

Trash Receptacle
Sheet D-1, Details 4 & 5

6' Concrete Trail
Sheet D-1, Details 1 & 2

Plaza B

BASELINE B
(Beltway Drive Back of Curb)

Refer to Sheet C-2.11 for Plaza C Enlargement

Les Lacs Drive

Sign to be Relocated by Contractor, Coordinate with Town of Addison

Telephone Riser to be Relocated so as not to conflict with flatwork, Coordinate with Town of Addison and utility company

5' Sidewalk to be Removed

Remove existing sidewalk to this point and align location and elevation of new trail with remaining sidewalk, provide expansion joint and dowel into existing concrete walk

4 Existing Trees To Remain

Cable Marker

6' Concrete Trail

Plaza C

Trash Receptacle

Sign

Note: Remove Existing Landscape Area At Corner

Remove existing sidewalk to corner of brick wall and align location and elevation of new trail with remaining sidewalk, provide expansion joint and dowel into existing concrete walk

6' Concrete Trail
Sheet D-1, Detail 1 & 2

Trash Receptacle
Sheet D-1, Details 4 & 5

MATCH LINE E

0 5 10 20 40

Layout and Dimensioning Plan Area Five

STATE OF TEXAS
DAVID L. RUTZ
1353
REGISTERED LANDSCAPE ARCHITECT

LES LACS LINEAR PARK

TOWN OF ADDISON PARKS & LEISURE SERVICES DEPARTMENT 16801 WESTGROVE ROAD ADDISON, TEXAS 75001 214/450-2851

7950 ELMBROOK DRIVE SUITE250 DALLAS, TEXAS 75247 - 4951
(214) 638 0145 FAX (214) 638 0447
Carter::Burgess

REVISIONS

JOB NUMBER
93324001D

DESIGNED SLA
DRAWN SLA
CHECKED DLR/LPO

ISSUE DATE
August 18, 1994

SHEET NUMBER
C-2.5

Copyright © 1993 by Carter & Burgess, Inc.