

DATE: 11/18/2020
 TIME: 12:07:35 PM
 FILE NAME: N:\PROJECTS\14285_00_A Addison_2017 Various Projects\R14285.01_White Rock Drainage\07_DGN\076_Sheets\14285.01_Summary of Quantity.dgn

SUMMARY OF QUANTITY			
Item #	Bid Qty.	Unit	Description
General			
1	1	LS	Mobilization
Paving			
2	880	SY	Remove & Dispose of Existing Pavement
3	160	SY	Remove & Dispose of Existing Sidewalk
4	880	SY	8-inch Reinforced Concrete Pavement (High Early Strength)
5	130	SY	4-inch Reinforced Concrete Sidewalk (Exposed Aggregate)
6	405	LF	6" Monolithic Curb
7	3	EA	Speed Hump (Match Existing Stamped Concrete)
8	140	SY	Sod W/ Topsoil (4" Depth)
9	2	EA	Project Sign
10	100	SY	Temporary Pavement
11	2	EA	Barrier Free Ramp
12	26	LF	Furnish and Install REF PAV MRK TY I (W) 12" (SLD) (125 MIL)
13	2	EA	Furnish & Install Small Roadside Sign Assembly
14	1	EA	Construct Median Nose
15	20	CY	Stabilized Construction Exit (Stone)
16	3	MO	Traffic Control
Storm Water Drainage			
17	1	LS	Storm Water Pollution Prevention Plan (SW3P) - Including Maintenance, Inlet Protection and Erosion Control
18	50	LF	18-inch Class III Reinforced Concrete Pipe
19	550	LF	21-inch Class III Reinforced Concrete Pipe
20	140	LF	21-inch Class III Reinforced Concrete Radius Pipe (Joint Length = 4 feet)
21	270	LF	24-inch Class III Reinforced Concrete Pipe
22	1,010	LF	Trench Safety
23	4	EA	10-foot Standard Concrete Curb Inlet (Exposed Aggregate)
24	1	EA	20-foot Standard Concrete Curb Inlet (Exposed Aggregate)
25	2	EA	4'x4' Storm Water Manhole
26	1	EA	Pipe to Existing Structure Connection
27	1,010	LF	Television Inspection
28	1,010	LF	Construction Surveying & Staking
29	2	EA	Water Main Lowering
30	6	EA	4-inch Sanitary Sewer Service
31	2	EA	Adjust Water Meter
32	7	EA	Furnish & Install 1-inch Standard Water Service

RECORD DRAWINGS
 THE INTENT OF THE OWNER AND ENGINEER WAS TO CONSTRUCT THE FACILITIES ACCORDING TO THESE PLANS AS APPROVED BY THE TOWN OF ADDISON. THE OWNER OR ENGINEER DID NOT VERIFY LINES OR GRADES AFTER CONSTRUCTION AND IS NOT AWARE OF ANY CHANGES OR REVISIONS TO THESE PLANS DURING CONSTRUCTION EXCEPT AS NOTED BASED ON INFORMATION PROVIDED BY: JOE FUNK CONSTRUCTION, INC. 11226 INDIAN TRAIL DALLAS, TX 75229



REVISIONS			
REV NO.	DATE	DESCRIPTION	BY
1			
2			



CRIADO 4100 SPRING VALLEY ROAD, SUITE 1001
 DALLAS, TX 75244
 O: 972-392-9092 F: 972-392-9192
 FIRM NO. F-4373

**SUMMARY OF QUANTITY SHEET
 (SHEET 1 OF 1)
 OAKS NORTH DRIVE
 DRAINAGE IMPROVEMENTS
 TOWN OF ADDISON, TEXAS**

DESIGN	DRAWN	DATE	SCALE	NOTES	FILE	NO.
CRIADO	CRIADO	NOV 2019	AS SHOWN	R14285.01	SUMMARY OF QUANTITY	2