SUMMARY OF ESTIMATED QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	PAVING SHEETS	DRAINAGE SHEETS	MISC.	TOTAL
100.1	Prepare right-of-way	Sta.				8.5
104.1	Sawed break-out groove	LF				472
110.1	Roadway excavation	CY				970
260.1	6" Lime treatment	SY				3139
264.1	Hydrated lime (type A) #27/sy	Ton				42
340.1	HMACP (Type "D" Cl. A) Surf. coarse #110/in./sy	Ton				26
340.2	HMACP (Type "B" Cl. A) Base coarse #110/in./sy	Ton				41
360.1	8" Reinf. concrete pavement (3000 psi)	SY				2614
360.2	6" Integral conc. curb (3000psi)	LF				832
465.1	18" RCP, Class III	LF				26
465.2	21" RCP, Class III	LF				245
465.3	24" RCP, Class III	LF				106
465.4	30" RCP, Class III	LF				155
465.41	30" RCP 30° bend, Class III	Ea				1
470.1	10' Recessed curb inlet	Ea				3
470.2	10' Modified recessed curb inlet	Ea				1
475.1	Adjust exist. grate inlet	Ea				3
479.1	Adjust sanitary sewer manhole	Ea				1
479.2	Adjust sanitary sewer cleanout	Ea				1
530.1	6" Reinf. conc. driveway pavement (3000 psi)	SY				726
582.1	Adjust water valve	Ea				1
582.2	Adjust water valve & fire hydrant	Ea				2
582.3	Lower water line	LF				90
670.1	4" Fire lane striping	LF				801
674.1	4" Bi-Directional reflective yellow marker (P-117Y)	Ea				102
591	Irrigation system replacement	LS				1

INDEX TO DRAWINGS

SHEET NO.	DESCRIPTION
1	Cover Sheet
2	Summary of Quantities
3	Construction Sequence & Property Ownerships
4	Paving Plan & Profile Sta. 0-03.00 to Sta. 5+00
5	Paving Plan & Profile Sta. 5+00 to Sta. 8+46.5
6	Drainage Area Map
7	Drainage Plan & Profile
8	Paving Details
9	Storm Sewer & Driveway Details
10	Curb Inlet Details
11	Water Details
12	Sanitary Sewer Details

STATE OF TEXAS
RANDALL C. HILL
45234
REGISTERED PROFESSIONAL ENGINEER

Randall C. Hill
4-14-87

No	Revision	By	Date

TOWN OF ADDISON
DALLAS COUNTY, TEXAS

RATLIFF LANE IMPROVEMENTS

SHEET INDEX & SUMMARY OF QUANTITIES

GINN, INC.
Consulting Engineers Dallas, Texas

Designed - R.L.O.	Drawn - R.L.O.	Date - OCT. 86	Job No. - 293
Approved - H.W.G.	Checked - R.C.H.	Scale - N/A	Sheet 2 Of 12