



TOWN OF ADDISON
 BUILDER'S COPY OF PLANS
 This set of plans contains various corrections and comments made by the City Staff. All trades will be required to comply with these corrections and comments; failure to inform all trades of this information will not be accepted as a reason to approve construction which is in violation of local ordinances.
 This set of plans is to be kept on the job site at all times and is to be made available for use by city inspectors at their request. Failure to have these plans available may delay approval of a requested inspection.

01 PLUMBING RISER DIAGRAMS
 P7.1 NTS

PLUMBING LEGEND

— — — — —	COLD WATER SUPPLY
— · — · —	HOT WATER SUPPLY
— G — — —	GAS LINE
— · — · —	PLUMBING VENT
— — — — —	SOIL OR WASTE ABOVE FLOOR
— — — — —	SOIL OR WASTE BELOW FLOOR
OC FD	FLOOR DRAIN W/DEEP-SEAL P-TRAP
OF FCO	FLOOR, OR GRADE, CLEANOUT
O RD	ROOF DRAIN
DS	DOWNSPOUT
VTR	VTR
— S — — —	STORM SEWER

- PLUMBING FIXTURE SCHEDULE**
- WC-1 WATER CLOSET: AMERICAN STANDARD "WATER-SAVER MARIANA" 2221.018 VITREOUS CHINA, FLOOR-MOUNTED, SIPHON-JET, ELONGATED BOWL, 1 1/2" TOP SPUD, 10" ROUGH-IN. SUPPLY COMPLETE WITH: BOLT COVERS; WHITE, SOLID-PLASTIC, ELONGATED, OPEN-FRONT SEAT WITH STAINLESS-STEEL HINGE WITH CONCEALED CHECK; CLOSET FLANGE & SEAL; AND SLOW "ROYAL" 110-3 FLUSH VALVE.
 - WC-2 WATER CLOSET: AMERICAN STANDARD ELONGATED WATER-SAVER CREST 318E VITREOUS CHINA, FLOOR-MOUNTED, SIPHON-JET, ELONGATED BOWL, 1 1/2" TOP SPUD, 10" ROUGH-IN, 18" HIGH FOR HANDICAP. SUPPLY COMPLETE WITH: BOLT COVERS; WHITE, SOLID-PLASTIC, ELONGATED OPEN-FRONT SEAT WITH STAINLESS-STEEL HINGE WITH CONCEALED CHECK; CLOSET FLANGE & SEAL; AND SLOW "ROYAL" 110-3 FLUSH VALVE.
 - UR-1 URINAL: AMERICAN STANDARD "LYMBROOK" 6531.018 VITREOUS CHINA, WALL-MOUNTED, FLOORING RIM, INTEGRAL TRAP, PRIVATE STUBS, 1 1/4" TOP SPUD, 2" OUTLET. SUPPLY COMPLETE WITH: SLOW "ROYAL" 110 FLUSH VALVE AND JOSAM SERIES 37000 URINAL CARRIER.
 - LAV-1 LAVATORY: AMERICAN STANDARD "OVAL HORIZON" 3302.018 ENAMELED CAST IRON, SELF-RIMMING COUNTERTOP, 20 x 17" FAUCET INLETS ON 8" CENTERS. SUPPLY COMPLETE WITH: 1 1/4" CHROME-PLATED CAST BRASS P-TRAP WITH CLEANOUT; 1/2 x 3/8" ANGLE SUPPLY STOPS WITH 3/8" NOMINAL FLEXIBLE RISERS; AND AMERICAN STANDARD "HERITAGE" 2248.623 COMBINATION LAVATORY FAUCET WITH INLETS ON 8" CENTERS, POP-UP DRAIN WITH 1 1/4" TALLPIECE, AERATOR, AND CHROME HANDLES.
 - SK-1 SINGLE-COMPARTMENT SINK: ELKAY "LUSTERONE" LR-2522, 18-GAGE TYPE-302 STAINLESS STEEL, 28" LENGTH x 22" WIDTH x 8" DEPTH, 3 FAUCET HOLES ON 4" CENTERS, 11-3/8 STRAINER, 11-1/2" FACET, PROVIDE 1/4" AND 1/2" ANGLE VALVES WITH WHEELHANDLE STOPS AND FLEXIBLE RISERS, AND 1 1/2" CHROME-PLATED CAST-BRASS "P" TRAP WITH CLEANOUT.
 - SS-1 SERVICE SINK: FIAT T50-800 PRECAST TERAZZO TOP SERVICE BASIN, 34 1/2 x 16" x 2" WIDE SHOULDERS, STAINLESS STEEL DRAIN BODY CAST INTEGRAL 3" OUTLET. SUPPLY COMPLETE WITH: 850-8A SERVICE FAUCET WITH VACUUM BREAKER, INTEGRAL STOPS, ADJUSTABLE WALL BRACKETS, 1/4" HOSE THREAD ON SPOUT, INLETS ON 8" CENTERS, AND FOUR-ARM HANDLES; AND 850-8A HOSE & HOSE BRACKET.
 - DF-1 DRINKING FOUNTAIN: ELKAY D44-16 WALL-MOUNTED ELECTRIC WATER COOLER, 16 GPM CAPACITY, 500WATT 1/4 HP 120V/60 COMPRESSION MOTOR. SUPPLY COMPLETE WITH: STAINLESS-STEEL PANELS; GLASS FILLER; 1/2 x 3/8" ANGLE SUPPLY STOP WITH 3/8" NOMINAL RISERS; AND 1 1/4" CHROME-PLATED CAST-BRASS P-TRAP.
 - SH-1 SHOWER VALVE & TRIM: AMERICAN STANDARD "THERMOQUAD" 1361.039 PRESSURE-BALANCING VALVE WITH 1/2" INLETS, ANGLE SHOWERHEAD STOPS, AND CHROME LEVER HANDLES. SUPPLY COMPLETE WITH: 1444-017 "HERITAGE" SHOWER ARM AND 1413.020 "ASTRAJET" SHOWERHEAD.
 - WM-1 WASHING MACHINE SUPPLY & DRAIN BOX: SYMONS "LAUNDRY-MATE" M-602 IN-WALL, FLOOR-MOUNTED SUPPLY & DRAIN BOX WITH SINGLE-LEVER MIXING VALVE, 1/2" HOT & COLD WATER INLETS, AND 2" DRAIN.
 - GMH-1 GAS WATER HEATER: STATE COMMERCIAL MODEL SB750-65E, 50-GALLON STORAGE CAPACITY, FIRST-HOUR DELIVERY 95 GALLONS AT 100° F TEMPERATURE RISE, RECOVERY RATE 61 GPM AT 100° F TEMPERATURE RISE, 65,000 BTU/NATURAL GAS INPUT.
 - GMH-2 GAS WATER HEATER: STATE COMMERCIAL MODEL SB751-155E, 75 GALLON STORAGE CAPACITY, FIRST-HOUR DELIVERY 134 GALLONS AT 100° F TEMPERATURE RISE, RECOVERY RATE 145 GPM AT 100° F TEMPERATURE RISE, 135,000 BTU/NATURAL GAS INPUT.
 - FD-1 FLOOR DRAIN: JOSAM 30002 CAST IRON FLOOR DRAIN WITH 6" DIAMETER, NICKEL/BRONZE, ADJUSTABLE STAINER AND 2" BOTTOM OUTLET, INSIDE CAULK CONNECTION.
 - FD-2 FLOOR DRAIN: JOSAM 30003. SAME AS ABOVE EXCEPT 3" OUTLET.
 - FD-3 FLOOR DRAIN: JOSAM 30004. SAME AS ABOVE EXCEPT 4" OUTLET.
 - RD ROOF DRAIN: JOSAM 21000 SERIES COATED CAST IRON ROOF DRAIN WITH: NONREBORING LOCKING CONE MOVING 124 SQUARE INCH FREE AREA, DECK CLAMP; DRAIN RECEIVER; NON-PUNCTURING CLAMP; RINGS WITH INTEGRAL GRAVEL STOP; SUPPORT RING; ADJUSTABLE TOP WITH WIDE 3000-FLANGE; LARGE SUMP WITH ANCHOR FLANGE; AND BOTTOM OUTLET, INSIDE CAULK CONNECTION.
 - DN DOWNSPOUT NOZZLE: JOSAM 25010 SERIES CAST BRONZE DOWNSPOUT NOZZLE, LOOSE WALL FLANGE, AND INLET THREADED CONNECTION.
 - WH WALL HYDRANT: JOSAM 71000 SERIES CAST BRONZE, BOX-TYPE, NON-FREEZE WALL HYDRANT WITH: SATIN FACE; WROUGHT STAINLESS STEEL, SELF-OPENING, REMOVABLE LOCKING COVER BOX, 3/4" NPT OUTLET; INTEGRAL VACUUM BREAKER - BACKFLOW PREVENTER; PRESSURE RELIEF VALVE; BRONZE CASING AND OPERATING PARTS; AND 3/4" FEMALE 1" MALE NPT INLET CONNECTION.
 - SA WATER HAMMER ARRESTER: JOSAM 75000 SERIES SHOCK ABSORBER WITH: STAINLESS-STEEL SHELL; HYDRO-PNEUMATIC CUSHION OF ARGON GAS & PURE GLYCERINE; ELASTOMER BELLOWS; STAINLESS-STEEL ADAPTER; AND MALE THREADED PLUG.

EDI ARCHITECTS, INC.
 ARCHITECTURE PLANNING ENGINEERING INTERIOR DESIGN
 AMERICAN BLDG. CO. BLDG.
 SUITE 2000
 AUSTIN, TEXAS 78701
 512 / 488-8808

TOWN OF ADDISON

ADDISON

ADDITION TO PUBLIC WORKS SERVICE CENTER
 Westgrove Road
 Addison Texas

DATE:
 11 JUNE 86
 24 JULY 1986 - BID

SHEET NO.
P7.1
 OF SHEETS
 JOB NO: 851-137

INTERFIELD ENGINEERING CO.
 CONSULTING ENGINEERS
 8401 N. CENTRAL EXPWY.
 SUITE 340
 DALLAS, TEXAS 76206
 (214) 628-8854